



VINE AND DAYLILY PLANTING DETAIL

**AECOM** 

## GENERAL PLAN NOTES - LANDSCAPING:

- THE CONTRACTOR SHALL USE CARE IN GRADING OR EXCAVATING NEAR ANY AND ALL EXISTING ITEMS WHICH WILL NOT BE REMOVED. ANY DAMAGE DONE TO EXISTING ITEMS BY THE CONTRACTOR SHALL BE REPAIRED BY THE CONTRACTOR AT THE CONTRACTOR'S EXPENSE.
- 2. THE CONTRACTOR SHALL TAKE ALL NECESSARY PRECAUTIONS FOR THE PROTECTION OF EXISTING PLANT MATERIAL FOR WHICH THE CONTRACT DOES NOT PROVIDE REMOVAL. THE PROTECTION OF EXISTING PLANT MATERIAL AND THE REPAIR OR REPLACEMENT OF EXISTING PLANT MATERIAL DAMAGED BY THE CONTRACTOR SHALL BE DONE IN ACCORDANCE WITH THE REQUIREMENTS OF SECTION 201 OF THE STANDARD SPECIFICATIONS.
- 3. THE SEEDING DATES FOR BARE EARTH SEEDING OF MIXTURE CLASS 2A SHALL BE FROM APRIL 1 TO JUNE 1 AND FROM AUGUST 15 TO SEPTEMBER 30. ALL SEEDING NOT SOWN ACCORDING TO THE SPECIFIED SEASONAL DATE SHALL REQUIRE PRIOR APPROVAL FROM THE ENGINEER. FAILURE TO SECURE SUCH APPROVAL SHALL RESULT IN THE REJECTION OF THE SEEDING AND REPLACEMENT BY THE CONTRACTOR AS HIS/HER EXPENSE.
- 4. AREAS TO BE SEEDED BETWEEN NOVEMBER 15 AND MARCH 31 SHALL REQUIRE DORMANT SEEDING, WHICH SHALL BE INCLUDED IN THE COST OF "SEEDING CLASS 2A," "SEEDING CLASS 4 (MODIFIED)," OR "SEEDING, CLASS 5A (MODIFIED)."
- 5. THE SEEDING DATES FOR BARE EARTH SEEDING OF MIXTURE CLASSES 4 AND 5 SHALL BE FROM APRIL 15 TO JUNE 30 AND FROM OCTOBER 15 TO DECEMBER 1. ALL SEEDING NOT SOWN ACCORDING TO THE SPECIFIED SEASONAL DATE SHALL REQUIRE PRIOR APPROVAL FROM THE ENGINEER. FAILURE TO SECURE SUCH APPROVAL SHALL RESULT IN THE REJECTION OF THE SEEDING AND REPLACEMENT BY THE CONTRACTOR AS HIS/HER EXPENSE.
- 6. LAYOUT OF LANDSCAPED AREAS WILL REQUIRE APPROVAL OF THE ENGINEER PRIOR TO TOPSOIL PLACEMENT, SEEDING, AND PLANTING.

## GENERAL PLAN NOTES - PLANTING BED:

- SEE LANDSCAPING PLANS FOR SPECIFIC LOCATIONS AND QUANTITIES OF VINES, SHRUBS, AND DAYLILIES.
- 8. ALL COMPOST AND TOPSOIL AREAS SHALL BE THOROUGHLY ROTOTILLED TO A DEPTH OF 12" PRIOR TO PLANTING AND/OR SEEDING
- 9, THE CONTRACTOR SHALL ORDER THE FOLLOWING PLANT MATERIAL IMMEDIATELY FOLLOWING EXECUTION OF THE CONTRACT TO ASSURE AVAILABILITY OF THE PLANT MATERIAL FOR SPRING PLANTING AT THE CONCLUSION OF THE CONTRACT:

   VINE-PARTHENOCISSUS QUINQUEFOLIA (VIRGINIA CREEPER), 1-GALLON

   VINE-PARTHENOCISSUS TRICUSPIDATA (BOSTON JVY), 1-GALLON

   PERENNIAL PLANTS, DAYLILIES (HAPPY RETURNS DAYLILY), 1-GALLON
- 10. MULCH BED SHALL BE PLACED OVER ROTOTILLED COMPOST/TOPSOIL AS SHOWN IN THE PLANTING DETAILS AND ACCORDING TO IDOT STANDARD SPECIFICATION 253.11, EXCEPT THAT NO WEED BARRIER FABRIC IS REQUIRED. COST OF MULCH COVER IS INCLUDED WITH PAYMENT FOR THE VINES, DAYLILIES, AND SHRUBS.
- 11. PRE-EMERGENT GRANULAR HERBICIDE SHALL BE PLACED IN MULCHED BEDS ACCORDING TO THE SPECIAL PROVISION.
- 12. FERTILIZER NUTRIENTS SHALL BE ADDED AND APPLIED TO THE VINE BEDS AT A 5:3:2
  RATIO AS FOLLOWS:
  NITROGEN FERTILIZER NUTRIENTS: 90 LBS/ACRE
  PHOSPHORUS FERTILIZER NUTRIENTS: 54 LBS/ACRE
  POTASSIUM FERTILIZER NUTRIENTS: 36 LBS/ACRE
  THIS FERTILIZER SHALL BE TILLED AND CULTIVATED INTO THE SOIL TO A DEPTH OF 12"

F.A.I. RTE.	SECTION	ı	COUNT	Y	TOTAL	SHEET NO.
90/94	•		COOK		565	287
STA.		TO	STA.			
FED. ROAD	DIST, NO. 1	ILLINOIS	FED.	AID	PROJECT	

62301 • (2021-922 PT2 ETC 2324.6-IP) R-10

## SCHEDULE OF LANDSCAPE ITEMS

PAY ITEM DESCRIPTION	COMMON: NAME	SIZE	SPACING	UNIT	TOTAL
VINE - PARTHENOCISSUS QUINQUEFOLIA, 1- GALLON POT	VIRGINIA CREEPER	1-GALLON	SEE PLANS	EACH	931
VINE - PARTHENOCISSUS TRICUSPIDATA	BOSTON IVY	1-GALLON	SEE PLANS	EACH	201
PERENNIAL PLANTS, DAYLILIES	HAPPY RETURNS DAYLILY	1-GALLON	12" C-C"	UNITS	8.36

REVISIONS		ILLINOIS DEPARTMENT	OF TRANSPORTATION	**
NAME	DATE	F.A.I. 90/94 (DAN R	YAN EXPRESSWAY)	ã.
		GARFIELD BLVD TO 31ST ST	TREET (NB LOCAL LANES)	12:32:12
				8
		LANDSCAPING NOTE	ES AND DETAILS	
				8
		SCALE: NONE	DRAWN BY: PHP	7/20
		DATE: June 9, 2006	CHECKED BY: RMG	2