

# SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
599	(26-150)M	ROCK ISLAND	116	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	URBAN 80% FED 20% STATE 1000
20101100	TREE TRUNK PROTECTION	EACH	2	
20200100	EARTH EXCAVATION	CU YD	6679	
• 25000210	SEEDING, CLASS 2A	ACRE	2.8	
• 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	252	
• 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	252	
• 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	252	
+ 25000750	MOWING	ACRE	2.8	
• 25100115	MULCH, METHOD 2	ACRE	2.8	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	2240	
28000300	TEMPORARY DITCH CHECKS	EACH	21	
28000400	PERIMETER EROSION BARRIER	FOOT	5561	
28000500	INLET AND PIPE PROTECTION	EACH	8	
28100107	STONE RIPRAP, CLASS A4	SQ YD	32	
28200200	FILTER FABRIC	SQ YD	32	
31100910	SUB-BASE GRANULAR MATERIAL, TYPE A 12"	SQ YD	3017	
31100920	SUB-BASE GRANULAR MATERIAL, TYPE A 15"	SQ YD	1036	
31100965	SUB-BASE GRANULAR MATERIAL, TYPE A 24"	SQ YD	2637	
35101400	AGGREGATE BASE COURSE, TYPE B	TON	3824	
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	27	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	7	
40600300	AGGREGATE (PRIME COAT)	TON	18	
40600895	CONSTRUCTING TEST STRIP	EACH	1	
40600990	TEMPORARY RAMP	SQ YD	520	
40800040	INCIDENTAL BITUMINOUS SURFACING	TON	26	
44000012	BITUMINOUS SURFACE REMOVAL 4 1/2"	SQ YD	6030	
44000100	PAVEMENT REMOVAL	SQ YD	2558	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	50	
44002020	CONCRETE MEDIAN SURFACE REMOVAL	SQ FT	119	
44200274	PAVEMENT PATCHING TYPE I	SQ YD	45	
44200276	PAVEMENT PATCHING TYPE II	SQ YD	45	
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	2451	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	60	
48202410	BITUMINOUS SHOULDERS SUPERPAVE 6-1/2"	SQ YD	2068	
48202415	BITUMINOUS SHOULDERS SUPERPAVE 6-3/4"	SQ YD	2268	
50104400	CONCRETE HEADWALL REMOVAL	EACH	2	

• SPECIALTY ITEMS  
+ NON-PARTICIPATING

CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	URBAN 80% FED 20% STATE 1000
50800105	REINFORCEMENT BARS	POUND	122	
54200220	PIPE CULVERTS, CLASS D, TYPE I 15"	FOOT	48	
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	1	
54213693	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 48"	EACH	2	
54215550	METAL END SECTIONS 15"	EACH	2	
54247190	GRATING FOR CONCRETE FLARED END SECTION 48"	EACH	2	
54248510	CONCRETE COLLAR	CU YD	3	
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	17	
550A0120	STORM SEWERS, CLASS A, TYPE 1 24"	FOOT	543	
• 56400300	FIRE HYDRANTS TO BE ADJUSTED	EACH	1	
60107700	PIPE UNDERDRAINS 6"	FOOT	133	
60224075	MANHOLES, TYPE A, 6'-DIAMETER	EACH	1	
60246605	MEDIAN INLET (604101)	EACH	3	
60255500	MANHOLES TO BE ADJUSTED	EACH	4	
63500105	DELINEATORS	EACH	2	
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	27	
66700305	PERMANENT SURVEY MARKERS, TYPE II	EACH	2	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	7	
67100100	MOBILIZATION	L SUM	1	
70100200	TRAFFIC CONTROL AND PROTECTION, STANDARD 701331	EACH	1	
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	20	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	682	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	28582	
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	64	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	9653	
• 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	234	
• 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	19452	
• 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	1238	
• 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1100	
• 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	88	
• 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	194	
78300100	PAVEMENT MARKING REMOVAL	SQ FT	2904	

• SPECIALTY ITEMS  
+ NON-PARTICIPATING

PLT DATE = Wed Jun 21 13:08:28 2006  
PLT SCALE = 5000000 / IN  
USER NAME = meglj

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCALE: VERT. DATE  
HORIZ. DATE

DRAWN BY  
CHECKED BY

## SUMMARY OF QUANTITIES