CONTRACT NO. 64A46

| F.A.P. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|---|---|---|---|---|
| 599 | (26-15DIM | ROCK ISLAND | 116 | 17 |
| STA. | | TO STA. | | |
| FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT | | |

# SCHEDULE OF QUANTITIES

PAVEMENT PATCHING TYPE II

| SQ YD | LOCATION |
|---|---|
| 45 | TO BE DETERMINED BY ENGINEER |
| 45 | TOTAL |

STRIP REFLECTIVE CRACK CONTROL TREATMENT

| FOOT | LOCATION | | | |
|---|---|---|---|---|
| 2451 | RT | 1240+00 | - | 1264+51 |
| 2451 | TOTAL | | | |

AGGREGATE SHOULDERS, TYPE B

| TONS | LOCATION | | | |
|---|---|---|---|---|
| | TURKEY HOLLOW ROAD | | | |
| 34 | RT | 97+50 | - | 99+29 |
| 26 | LT | 97+50 | - | 98+88 |
| 60 | TOTAL | | | |

BITUMINOUS SHOULDERS SUPERPAVE 6-1/2"

| SQ YD | LOCATION | | | |
|---|---|---|---|---|
| 90 | RT | 1237+21 | - | 1238+22 |
| 89 | LT | 1237+21 | - | 1238+22 |
| 797 | RT | 1240+00 | - | 1250+84 |
| 870 | RT | 1252+44 | - | 1264+51 |
| | TURKEY HOLLOW ROAD | | | |
| 116 | RT | 97+50 | - | 99+68 |
| 106 | LT | 97+50 | - | 99+62 |
| 2068 | TOTAL | | | |

BITUMINOUS SHOULDERS SUPERPAVE 6-3/4"

| SQ YD | LOCATION | | | |
|---|---|---|---|---|
| 2085 | LT | 1240+25 | - | 1264+50 |
| 183 | LT | 1264+51 | - | 1267+54 |
| 2268 | TOTAL | | | |

CONCRETE HEADWALL REMOVAL

| EACH | LOCATION | | OFFSET |
|---|---|---|---|
| 1 | LT | 1245+45 | 40.5' |
| 1 | RT | 1245+45 | 41.5' |
| 2 | TOTAL | | |

REINFORCEMENT BARS

| POUND | LOCATION | | OFFSET |
|---|---|---|---|
| 61 | LT | 1245+45 | 40.5' |
| 61 | RT | 1245+45 | 41.5' |
| 122 | TOTAL | | |

PIPE CULVERTS, CLASS D, TYPE I 15"

| FOOT | LOCATION | | | |
|---|---|---|---|---|
| 48 | LT | 1264+31 | - | 1264 +79 |
| 48 | TOTAL | | | |

PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"

| EACH | LOCATION | | OFFSET |
|---|---|---|---|
| 1 | RT | 1258+46 | 60 |
| 1 | TOTAL | | |

PRECAST REINFORCED CONCRETE FLARED END SECTIONS 48"

| EACH | LOCATION | | OFFSET |
|---|---|---|---|
| 1 | LT | 1245+45 | 40.5' |
| 1 | RT | 1245+45 | 41.5' |
| 2 | TOTAL | | |

METAL END SECTIONS 15"

| EACH | LOCATION | |
|---|---|---|
| 1 | LT | 1264+31 |
| 1 | LT | 1264+79 |
| 2 | TOTAL | |

GRATING FOR CONCRETE FLARED END SECTION 48"

| EACH | LOCATION | | OFFSET |
|---|---|---|---|
| 1 | LT | 1245+45 | 40.5' |
| 1 | RT | 1245+45 | 41.5' |
| 2 | TOTAL | | |

CONCRETE COLLAR

| CU YD | LOCATION | | OFFSET |
|---|---|---|---|
| 1.5 | LT | 1245+45 | 40.5' |
| 1.5 | RT | 1245+45 | 41.5' |
| 3 | TOTAL | | |

STORM SEWERS, CLASS A, TYPE 1 12"

| FOOT | LOCATION | | | |
|---|---|---|---|---|
| 17 | RT | 1264+33 | - | 1264+45 |
| 17 | TOTAL | | | |

STORM SEWERS, CLASS A, TYPE 1 24"

| FOOT | LOCATION | | | |
|---|---|---|---|---|
| 248 | RT | 1258+48 | - | 1261+00 |
| 145 | RT | 1261+00 | - | 1262+50 |
| 150 | RT | 1262+50 | - | 1264+00 |
| 543 | TOTAL | | | |

FIRE HYDRANTS TO BE ADJUSTED

| EACH | LOCATION | | OFFSET |
|---|---|---|---|
| 1 | RT | 1264+19 | 59' |
| 1 | TOTAL | | |

PIPE UNDERDRAINS 6"

| FOOT | LOCATION | |
|---|---|---|
| 50 | RT | 1261+00 |
| 45 | RT | 1262+50 |
| 38 | RT | 1264+45 |
| 133 | TOTAL | |

| REVISIONS | |
|---|---|
| NAME | DATE |

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCALE: VERT. HORIZ.

DATE

DRAWN BY

CHECKED BY

SCHEDULE OF QUANTITIES

PLOT DATE = Wed Jun 21 13:08:28 2006
FILE NAME = c:\pw_pw1\c220708\d97704sw.dgn
PLOT SCALE = 50.0000 ' / IN.
USER NAME = meglilj