

SCHEDULE OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
599	126-150M	ROCK ISLAND	116	19
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

THERMOPLASTIC PAVEMENT MARKING - 4"

FOOT	LOCATION		
748	LT&RT	1236+26 -	1240+00
120	CENTER LIN	1236+26 -	1240+00
374	CENTER LIN	1236+26 -	1240+00
170	CENTER LIN	1240+00 -	1240+85
5000	LT&RT	1240+00 -	1265+00
3956	LT&RT	1240+84 -	1251+18
4517	LT&RT	1251+97 -	1264+56
983	LT	1264+51 -	1270+70
3168	CENTER LIN	1265+87 -	1273+66
TURKEY HOLLOW ROAD			
416	LT&RT	97+50 -	98+88
19452	TOTAL		

EDGE LINE
SKIP DASH YELLOW (EB)
SINGEL YELLOW (WB)
DOUBLE YELLOW
EDGE LINE
PAINTED MEDIANS
PAINTED MEDIANS
EDGE LINE
PAINTED MEDIANS

PAVEMENT MARKING REMOVAL

SO FT	LOCATION		
410	RT & LT	1236+26 -	1240+00
849	LT	1240+00 -	1264+51
1645	LT & CENTE	1264+51 -	1273+66
2904	TOTAL		

EDGE LINE/PAINTED MED

RAISED REFLECTIVE PAVEMENT MARKER REMOVAL

EACH	LOCATION		
120	STA.	1236+26 -	1273+66
120	TOTAL		

HEAVY DUTY HANDHOLE

EACH	LOCATION	OFFSET
1	RT	1260+50 38'
1	RT	1262+46 45'
1	RT	1264+09 44'
3	TOTAL	

ELECTRIC CABLE IN CONDUIT, LEAD-IN NO. 18 3PB

FOOT	LOCATION		
209	RT	1260+50 -	1262+46
329	RT	1262+46 -	1264+09
308	RT	1264+09 -	1264+71
846	TOTAL		

DETECTOR LOOP, TYPE 1

FOOT	LOCATION		
30	RT	1260+50	
40	RT	1262+46	
74	RT	1264+09	
144	TOTAL		

REMOVE EXISTING HANDHOLE

EACH	LOCATION		
1	RT	1259+94	
1	RT	1262+05	
1	RT	1264+09	
3	TOTAL		

STORM SEWER (WATER MAIN REQUIREMENTS) 24"

FOOT	LOCATION		
40	RT	1264+00 -	1264+45
40	TOTAL		

REMOVE CONCRETE FLARED END SECTIONS

EACH	LOCATION	OFFSET
1	RT	1264+33 67'
1	RT	1264+45 51'
2	TOTAL	

CONDUIT INSTALLED 1" DIA. NON-METALLIC

FOOT	LOCATION		
6	RT	1260+50	
6	RT	1262+46	
9	RT	1264+11 -	1264+18
21	TOTAL		

THERMOPLASTIC PAVEMENT MARKING - 8"

FOOT	LOCATION		
76	RIGHT TURN	1246+15 -	1248+44
272	RIGHT TURN	1248+44 -	1251+16
240	LEFT TURN	1251+97 -	1254+37
78	LEFT TURN	1254+37 -	1256+71
76	RIGHT TURN	1259+73 -	1262+00
252	RIGHT TURN	1262+00 -	1264+52
168	LEFT TURN	1265+87 -	1267+55
76	LEFT TURN	1267+55 -	1269+82
1238	TOTAL		

38@ 2' EACH SKIP DASH
SOLID LINE
SOLID LINE
39@ 2' EACH SKIP DASH
38@ 2' EACH SKIP DASH
SOLID LINE
SOLID LINE
38@ 2' EACH SKIP DASH

THERMOPLASTIC PAVEMENT MARKING - 12"

FOOT	LOCATION		
395	LT&RT	1241+16 -	1251+16
405	LT&RT	1254+57 -	1264+56
300	LT&RT	1266+97 -	1273+66
1100	TOTAL		

PAINTED MEDIANS
PAINTED MEDIANS
PAINTED MEDIANS

THERMOPLASTIC PAVEMENT MARKING - 24"

FOOT	LOCATION		
11	CENTER LIN	1251+98	
26	RT	1264+54	
26	RT	1265+87	
TURKEY HOLLOW ROAD			
25	RT	98+46	
88	TOTAL		

STOP BAR
STOP BAR
STOP BAR
STOP BAR

RAISED REFLECTIVE PAVEMENT MARKER

EACH	LOCATION		
DOUBLE AMBER			
6	CENTER LIN	1236+26 -	1243+27
12	STA.	1240+83 -	1243+27
12	STA.	1251+97 -	1254+37
18	STA.	1265+87 -	1269+00
4	STA.	1273+00 -	1273+66
SINGLE AMBER			
42	STA.	1243+27 -	1250+78
54	STA.	1254+37 -	1264+55
22	STA.	1269+00 -	1273+00
SINGLE CRYSTAL			
7	RIGHT TURN	1248+44 -	1251+16
6	LEFT TURN	1251+97 -	1254+37
6	RIGHT TURN	1262+00 -	1264+52
5	LEFT TURN	1265+87 -	1267+55
194	TOTAL		

PAINTED MEDIAN
PAINTED MEDIAN
PAINTED MEDIAN
PAINTED MEDIAN

PAINTED MEDIAN
PAINTED MEDIAN
PAINTED MEDIAN

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	

SCALE: VERT. _____
HORIZ. _____
DATE _____ DRAWN BY _____
CHECKED BY _____

SCHEDULE OF QUANTITIES

PLOT DATE = Wed Jun 21 13:08:08 2006
 PLOT SCALE = 1/8" = 100'
 PLOT DEVICE = HPGL
 USER NAME = mgj11j