



# Illinois Department of Transportation

Division of Aeronautics

1 Langhorne Bond Drive / Capital Airport / Springfield, Illinois / 62707-8415

September 13, 2017

**SUBJECT:** Dixon Municipal Airport – Charles R. Walgreen Field  
Dixon, Illinois  
Lee County  
IL Project Number: C73-4284  
SBG Project Number: 3-17-SBGP-87/95  
Item No. 01A, September 22, 2017 Letting  
Contract No. DI028  
Rehabilitate Lights on both Runways  
Addendum A

## NOTICE TO PROSPECTIVE BIDDERS

Attached is an addendum to the plans or proposal. This addendum involves revised and/or deleted material.

### Reason for Addendum:

Construction Safety Phasing Plan Revisions issued as Addendum A

### To All Plan Holders:

### **Construction Plan Changes:**

1. Replace Existing Plan Sheet 3 with Revised Plan Sheet 3
  - Revised Work Area Table
  - Deleted Work Area 1B and 1C
  - Added Point “H”
2. Replace Existing Plan Sheet 5 with Revised Plan Sheet 5
  - Added Point “I”
  - Added Point “J”
3. Replace Existing Plan Sheet 6 with Revised Plan Sheet 6
  - Revised Construction Point Table

Revisions to the Special Provisions: None

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Questions on this addendum may be directed to D. Kyle Peabody, Project Engineer of Crawford, Murphy & Tilly, Inc. at 630-907-7024 or [kpeabody@cmtengr.com](mailto:kpeabody@cmtengr.com).

DATE: Wednesday, September 13, 2017 2:06:26 PM  
 FILE: K:\Dixon\15244-02\_RevLighting\Draw\Sheets\Final\_7-27-2017\03\_Sequence Of Construction - Sheet 1.dwg  
 UPDATE BY: Jim Orise  
 LAYOUT: Layout1  
 IMAGE FILES: CMT\_136\_cmyk.jpg  
 CMT\_block\_rgb.jpg  
 XREF DWG: Fencing - tbcnt.dwg  
 Dixon-base.dwg

WORK AREA	ALLOWABLE WORK PERIOD	OPERATION STATUS/RESTRICTIONS
1	NO RESTRICTIONS	RUNWAY 12/30 OPEN RUNWAY 8/26 CLOSED TAXIWAY A CLOSED SOUTH OF RUNWAY 12/30 TAXIWAY C CLOSED NORTH OF RUNWAY 8/26 TAXIWAY E CLOSED ALL OTHER TAXIWAYS OPEN

- NOTES**
- WHEN HAUL ROUTE IS IN USE ON ACTIVE AIRFIELD PAVEMENTS, THE CONTRACTOR WILL BE REQUIRED TO HAVE A CROSSING GUARD FOR CONSTRUCTION PERSONNEL, CONSTRUCTION TRAFFIC, CONTRACTORS VEHICLES AND EQUIPMENT CROSSING BY, TO OR FROM WORK ZONE. STOP SIGNS SHALL BE IN PLACE AT ALL TIMES IN THIS AREA. THIS WORK SHALL BE INCIDENTAL TO THE CONTRACT.
  - RUNWAY 8/26 SHALL STAY CLOSED FOR THE DURATION OF PHASE 1.

- LEGEND**
- CONTRACTOR'S STAGING AND STORAGE AREA
  - EXISTING BUILDING
  - EXISTING PAVEMENT
  - EXISTING FENCE
  - RIGHT OF WAY (R.O.W.)
  - AIRPORT PROPERTY LINE
  - TAXIWAY OBJECT FREE AREA (TOFA)
  - RUNWAY OBSTACLE FREE ZONE (ROFZ)
  - AIRCRAFT MOVEMENT AREA
  - CONTRACTOR'S ACCESS/HAUL ROAD
  - TEMPORARY CLOSED TAXIWAY MARKER (SEE NOTE 2)
  - TEMPORARY CLOSED RUNWAY MARKER
  - WORK AREA NUMBER
  - TEMPORARY TYPE II BARRICADES WITH RED FLASHING LIGHT
  - CROSSING GUARD STOP-A.O.A. SIGN (SEE NOTE 1) OR CONTRACTOR'S ESCORT WITH RADIO




IL. CONTRACT: **DI028**  
 IL. LETTING ITEM: **01A**  
 IL. PROJECT: **C73-4284**  
 S.B.G. PROJECT: **3-17-SBGP-87 & 95**

SURVEY BOOK # BOOK #

REVISIONS		
NUMBER	BY	DATE
1	DKP	9/13/17

0 1 2  
 THIS BAR IS EQUAL TO 2"  
 AT FULL SCALE (34X22).



**DIXON MUNICIPAL AIRPORT**  
**DIXON, ILLINOIS**  
**REHABILITATE LIGHTS ON BOTH RUNWAYS**  
**SEQUENCE OF CONSTRUCTION - PHASE 1**  
**PER AC 150/5370-2F (LATEST EDITION)**



DESIGN BY:	RMD
DRAWN BY:	JRO
CHECKED BY:	DKP
APPROVED BY:	DLP
DATE:	7/28/17
JOB No:	15244-02
<b>FINAL</b>	
SHEET	3 OF 16 SHEETS



DATE: Wednesday, September 13, 2017 2:07:33 PM  
 FILE: K:\Dixon\15244-02\_RwyLighting\Draw\Sheets\Final\_7-27-2017\05\_Sequence of Construction - Sheet\_3.dwg  
 UPDATE BY: Jim Ohse  
 LAYOUT: Layout1  
 IMAGE FILES: CMT\_3C\_cmyk.jpg  
 CMT\_block\_glb.jpg  
 RREF DWG: Fencing - bchrc1.dwg  
 Dixon-base.dwg


WORK AREA	ALLOWABLE WORK PERIOD	OPERATION STATUS/RESTRICTIONS
3A	WORK WITHIN AREA WILL BE EXPEDITED, ONLY 1 CALENDAR DAYS ALLOWED TO COMPLETE WORK	RUNWAY 12/30 CLOSED RUNWAY 8/26 OPEN TAXIWAY A CLOSED NORTH OF RUNWAY 12/30 AND SOUTH OF TAXIWAY D ALL OTHER TAXIWAYS OPEN
3B	NO RESTRICTIONS	NO CLOSURES
3C	NO RESTRICTIONS	RUNWAY 12/30 OPEN RUNWAY 8/26 OPEN TAXIWAY B CLOSED SOUTH OF TAXIWAY C AND NORTH OF TAXIWAY E
3D	NO RESTRICTIONS	RUNWAY 12/30 OPEN RUNWAY 8/26 OPEN TAXIWAY C CLOSED

**NOTES**

- WHEN HAUL ROUTE IS IN USE ON ACTIVE AIRFIELD PAVEMENTS, THE CONTRACTOR WILL BE REQUIRED TO HAVE A CROSSING GUARD FOR CONSTRUCTION PERSONNEL, CONSTRUCTION TRAFFIC, CONTRACTORS VEHICLES AND EQUIPMENT CROSSING BY, TO OR FROM WORK ZONE. STOP SIGNS SHALL BE IN PLACE AT ALL TIMES IN THIS AREA. THIS WORK SHALL BE INCIDENTAL TO THE CONTRACT.
- RUNWAY 12/30 SHALL ONLY BE CLOSED DURING PHASE 3A.

**LEGEND**

-  CONTRACTOR'S STAGING AND STORAGE AREA
-  EXISTING BUILDING
-  EXISTING PAVEMENT
-  EXISTING FENCE
-  RIGHT OF WAY (R.O.W.)
-  AIRPORT PROPERTY LINE
-  TAXIWAY OBJECT FREE AREA (TOFA)
-  RUNWAY OBSTACLE FREE ZONE (ROFZ)
-  AIRCRAFT MOVEMENT AREA
-  CONTRACTOR'S ACCESS/HAUL ROAD
-  TEMPORARY CLOSED TAXIWAY MARKER (SEE NOTE 2)
-  TEMPORARY CLOSED RUNWAY MARKER
-  WORK AREA NUMBER
-  TEMPORARY TYPE II BARRICADES WITH RED FLASHING LIGHT
-  CROSSING GUARD STOP-A.O.A. SIGN (SEE NOTE 1) OR CONTRACTOR'S ESCORT WITH RADIO




IL. CONTRACT: **DI028**  
 IL. LETTING ITEM: **01A**  
 IL. PROJECT: **C73-4284**  
 S.B.G. PROJECT: **3-17-SBGP-87 & 95**

SURVEY BOOK # BOOK #

REVISIONS		
NUMBER	BY	DATE
1	DKP	9/13/17

0 1 2  
 THIS BAR IS EQUAL TO 2"  
 AT FULL SCALE (34X22).



**DIXON MUNICIPAL AIRPORT**  
**DIXON, ILLINOIS**  
**REHABILITATE LIGHTS ON BOTH RUNWAYS**  
**SEQUENCE OF CONSTRUCTION - PHASE 3**  
**PER AC 150/5370-2F (LATEST EDITION)**

  
 License No. 184-00613  
 © Copyright CMT, Inc. 2014

DESIGN BY:	RMD
DRAWN BY:	JRO
CHECKED BY:	DKP
APPROVED BY:	DLP
DATE:	7/28/17
JOB No:	15244-02

**FINAL**  
 SHEET 5 OF 16 SHEETS

