FOR INDEX OF SHEETS, SEE SHEET NO. 2

FOR LIST OF HIGHWAY STANDARDS, SEE SHEET NO. 2 09-22-2023 LETTING ITEM 007

TRAFFIC DATA

ADT:

0

0

RIVERSIDE DRIVE: 3,600 (2021)

ROADWAY

SPEED POSTED

DESIGN SPEED

RIVERSIDE DRIVE

45 MPH

45 MPH

DESIGN DESIGNATION

RIVERSIDE DRIVE: MAJOR COLLECTOR


STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

PLANS FOR PROPOSED FEDERAL AID HIGHWAY

FAU ROUTE 0156 (RIVERSIDE DRIVE)

VILLAGE LIMITS SOUTH OF RUNNING BROOK
FARM BLVD TO JOHNSBURG ROAD
ROADWAY RESURFACING AND CULVERT
REPLACEMENT
SECTION NO. 20–00016–00–RS
PROJECT NO. 6YP7(599)

VILLAGE OF JOHNSBURG
MCHENRY COUNTY



JEFFREY J. STRZALKA, P. T/11/2023

N.T.S.

PROJECT_LENGTH

NET AND GROSS LENGTH OF PROJECT = 5,448 FT. = 1.03 MILES

CONTRACT 61J68

1-800-892-0123 OR 811





HRGreen.com
Illinois Professional Design Firm

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

APPROVED

PRINTED BY THE AUTHORITY OF THE STATE OF ILLINOIS

FULL SIZE PLANS HAVE BEEN PREPARED USING STANDARD ENGINEERING SCALES. REDUCED SIZED PLANS WILL NOT CONFORM TO STANDARD SCALES. IN MAKING MEASUREMENTS ON REDUCED PLANS, THE ABOVE SCALES MAY BE USED.

J.U.L.I.E.

JOINT UTILITY LOCATION INFORMATION FOR EXCAVATORS

RAM ENGINEER: CARMEN E. RAI

AID

0

0

INDEX OF SHEETS INDEX OF SHEETS STATE STANDARDS DISTRICT ONE DETAILS & GENERAL NOTES GENERAL NOTES - 10 SUMMARY OF QUANTITIES 11 - 12 TYPICAL SECTIONS ALIGNMENT & BENCHMARKS 13 REMOVAL PLANS 19 - 28 PATH PLAN AND PROFILES DETOUR PLAN 29 EROSION CONTROL PLANS 45 DISTRICT ONE DETAILS CONSTRUCTION DETAILS - 51 52 - 62 CULVERT PLANS

STATE STANDARDS

PATH CROSS SECTIONS

- 87

| SIAIL SIAND | טעוור |
|--------------|---|
| STANDARD NO. | LIST OF DESCRIPTION |
| 000001-08 | STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS |
| 280001-07 | TEMPORARY EROSION CONTROL SYSTEM |
| 442201-03 | CLASS C AND D PATCHES |
| 482011-03 | HMA SHLD. STRIPS/SHLDS. WITH RESURFACING OR WIDENING |
| | & RESURFACING PROJECTS |
| 542301-03 | PRECAST REINFORCED CONCRETE FLARED END SECTION |
| 542306-03 | PRECAST REINFORCED CONCRETE ELLIPTICAL FLARED END SECTION |
| 602001-02 | CATCH BASIN, TYPE A |
| 602306-03 | INLET - TYPE B |
| 602601-06 | PRECAST REINFORCED CONCRETE FLAT SLAB TOP |
| 602701-02 | MANHOLE STEPS |
| 604036-03 | GRATE TYPE 8 |
| 606001-08 | CONCRETE CURB TYPE B AND COMBINATION CONCRETE CURB AND GUTTER |
| 606101-05 | TYPE A GUTTER (INLET, OUTLET & ENTRANCE) |
| 606201-04 | TYPE B GUTTER (INLET, OUTLET & ENTRANCE) |
| 630001-12 | STEEL PLATE BEAM GUARDRAIL |
| 630116 | BACK SIDE PROTECTION OF GUARDRAIL |
| 630301-09 | SHOULDER WIDENING FOR TYPE 1 (SPECIAL) GUARDRAIL TERMINALS |
| 642006-01 | SHOULDER RUMBLE STRIPS, 8 IN. |
| 701001-02 | OFF-RD OPERATIONS, 2L, 2W, MORE THAN 15' AWAY |
| 701006-05 | OFF-RD OPERATIONS, 2L, 2W, 15' TO 24" FROM PAVEMENT EDGE |
| 701011-04 | OFF-RD MOVING OPERATIONS, 2L, 2W, DAY ONLY |
| 701301-04 | LANE CLOSURE, 2L, 2W, SHORT TIME OPERATIONS |
| 701306-04 | LANE CLOSURE, 2L, 2W, SLOW MOVING OPERATIONS DAY ONLY, |
| | FOR SPEEDS GREATER THAN OR EQUAL TO 45 MPH |
| 701311-03 | LANE CLOSURE, 2L, 2W, MOVING OPERATIONS-DAY ONLY |
| 701336-07 | LANE CLOSURE, 2L, 2W, WORK IN SERIES, FOR SPEEDS GREATER |
| | THAN OR EQUAL TO 45 MPH |
| 701501-06 | URBAN LANE CLOSURE, 2L, 2W, UNDIVIDED |
| 701701-10 | URBAN LANE CLOSURE, MULTILANE INTERSECTION |
| 701901-08 | TRAFFIC CONTROL DEVICES |
| 720001-01 | SIGN PANEL MOUNT DETAILS |
| 720006-04 | SIGN PANEL ERECTION DETAILS |
| 780001-05 | TYPICAL PAVEMENT MARKINGS |
| 728001-04 | TELESCOPING STEEL SIGN SUPPORT |
| 781001-04 | TYPICAL APPLICATIONS RAISED REFLECTIVE PAVEMENT MARKERS |

DISTRICT ONE DETAILS

| STANDARD NO. | LIST OF DESCRIPTION |
|----------------|---|
| BD - 07 | DETAIL OF STORM SEWER CONNECTION TO EXISTING SEWER |
| BD-22 | PAVEMENT PATCHING FOR HMA SURFACED PAVEMENT |
| BD-24 | CURB OR CURB AND GUTTER REMOVAL AND REPLACEMENT |
| BD-32 | BUTT JOINT AND HMA TAPER DETAILS |
| BD-34 | DETAILS FOR DEPRESSED CURB & GUTTER AND SHOULDER TREATMENT AT TBT TY. 1 SPL |
| BD-51 | BENCHING DETAIL FOR EMBANKMENT WIDENING |
| TC-10 | TRAFFIC CONTROL AND PROTECTION FOR SIDE ROADS, INTERSECTIONS, AND DRIVEWAYS |
| TC-11 | TYPICAL APPLICATIONS RAISED REFLECTIVE PAVEMENT MARKERS (SNOW-PLOW RESISTANT) |
| TC-13 | DISTRICT ONE TYPICAL PAVEMENT MARKINGS |
| TC-16 | SHORT TERM PAVEMENT MARKING LETTERS AND SYMBOLS |
| TC-21 | DETOUR SIGNING FOR CLOSING STATE HIGHWAYS |
| | |

GENERAL NOTES

- ALL REFERENCES TO "STANDARD SPECIFICATIONS" IN THESE GENERAL NOTES SHALL BE INTERPRETED TO MEAN "STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION" ADOPTED BY THE ILLINOIS DEPARTMENT OF TRANSPORTATION, JANUARY 1, 2022. ALL WORK TO BE COMPLETED IN ACCORDANCE WITH
- PRIOR TO COMMENCEMENT OF CONSTRUCTION, THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND CONDITIONS AFFECTING THEIR WORK WITH THE ACTUAL CONDITIONS AT THE JOB SITE. IF THERE ARE ANY DISCREPANCIES FROM WHAT IS SHOWN ON THE CONSTRUCTION PLANS, HE MUST IMMEDIATELY REPORT THEM TO THE ENGINEER BEFORE DOING ANY WORK, OTHERWISE THE CONTRACTOR ASSUMES FULL RESPONSIBILITY. IN THE EVENT OF DISAGREEMENT BETWEEN THE CONSTRUCTION PLANS, STANDARD SPECIFICATIONS AND/OR SPECIAL DETAILS, THE CONTRACTOR SHALL SECURE WRITTEN INSTRUCTIONS FROM THE ENGINEER PRIOR TO PROCEEDING WITH ANY PART OF THE WORK AFFECTED BY OMISSIONS OR DISCREPANCIES. FAILING TO SECURE SUCH INSTRUCTIONS, THE CONTRACTOR WILL BE CONSIDERED TO HAVE PROCEEDED AT HIS OWN RISK. IN THE EVENT OF ANY DOUBT OR QUESTION ARISING WITH RESPECT TO THE TRUE MEANING OF THE CONSTRUCTION PLANS OR SPECIFICATIONS, THE DECISION OF THE ENGINEER SHALL BE FINAL AND CONCLUSIVE.
- IT IS THE CONTRACTOR'S RESPONSIBILITY TO ASCERTAIN EXISTING FIELD CONDITIONS PRIOR TO BIDDING ON
- BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "JULIE" (JOINT UTILITY LOCATION INFORMATION FOR EXCAVATION) AT 8-1-1 FOR FIELD LOCATIONS OF BURIED UTILITIES (48 HOURS
- ALL ELEVATIONS SHOWN ON THE PLANS ARE ON THE NAVD88 DATUM
- THE CONTRACTOR SHALL PROTECT AND CAREFULLY PRESERVE ALL SECTION OR SUBSECTION MONUMENTS, PROPERTY CORNERS, AND REFERENCE MARKERS UNTIL THE OWNER, HIS AGENT, OR AN AUTHORIZED SURVEYOR HAS WITNESSED OR OTHERWISE REFERENCED THEIR LOCATIONS.
- SAW CUTTING WILL BE REQUIRED FOR ALL REMOVAL ITEMS AND SHALL BE TO FULL DEPTH AND SHALL RESULT IN A CLEAN STRAIGHT EDGE IN THE PORTION REMAINING.
- ABANDONED UNDERGROUND UTILITIES THAT CONFLICT WITH CONSTRUCTION SHALL BE DISPOSED OF OUTSIDE THE LIMITS OF THE RIGHT OF WAY ACCORDING TO ARTICLE 202.03 OF THE STANDARD SPECIFICATIONS AND AS DIRECTED BY THE ENGINEER.
- THE ELEVATIONS SHOWN ON THE PLANS ARE FINISHED GRADES OF PROPOSED PAVEMENT, UNLESS
- THE CONTRACTOR WILL NOT BE ALLOWED TO SET UP A YARD OR FIELD OFFICE ON VILLAGE PROPERTY WITHOUT WRITTEN CONSENT FROM THE VILLAGE OF JOHNSBURG.
- CONSTRUCTION WORK MAY BE PERFORMED MONDAY THRU FRIDAY DURING THE HOURS OF 7:00 A.M. TO 5 :00 P.M. AND ON SATURDAYS FROM 8:00 A.M. TO 5:00 P.M. NO WORK MAY BE PERFORMED PRIOR OR BEYOND THIS PERIOD WITHOUT PRIOR WRITTEN APPROVAL FROM THE VILLAGE. NO COMPENSATION WILL BE PAID FOR ANY INCONVENIENCE, DELAY, OR LOSS EXPERIENCE BY THE CONTRACTOR BECAUSE OF ADJUSTMENTS TO THEIR NORMAL SCHEDULE.
- WHEN CONDITIONS ARE ENCOUNTERED WHERE THE EXCAVATION FOR STRUCTURE OR PIPE CANNOT BE KEPT FREE OF WATER FOR PROSECUTING THE WORK THE CONTRACTOR SHALL PUMP AND/OR DIVERT WATER TO ACCOMMODATE CONSTRUCTION ACTIVITIES.
- STATE OF ILLINOIS PUBLIC ACT 094-0042 (CONSTRUCTION SITE TEMPORARY RESTROOM FACILITY ACT) STATE OF ILLINOIS PUBLIC ACT 094-0042 (CONSTRUCTION SITE TEMPORARY RESTROOM FACILITY ACT) STIPULATES THAT THE CONTRACTOR MUST PROVIDE AND MAINTAIN, FOR THEIR WORK FORCE, TEMPORARY RESTROOM FACILITIES. PLEASE REVIEW THIS ACT OR THE MOST RECENT UPDATE TO THE LEGISLATION IN ORDER TO HAVE A CLEAR UNDERSTANDING OF THE PROVISIONS OF THE ACT SUCH AS THE QUANTITY, TYPE AND APPURTENANCES NECESSARY FOR THE PROVISIONS OF THE ACT SUCH ACT THE VILLAGE HAS THE AUTHORITY TO PENALIZE THE CONTRACTOR IF THE PROVISIONS OF THE ACT THE VILLAGE HAS
- THE CONTRACTOR SHALL CONTACT KALPANA KANNAN-HOSADURGA, THE DISTRICT ONE TRAFFIC CONTROL SUPERVISOR, AT KALPANA.KANNAN-HOSADURGA@ILLINOIS.GOV A MINIMUM OF 72 HOURS IN ADVANCE OF BEGINNING WORK

COORDINATION WITH BUSINESSES AND DRVIEWAY CONSTRUCTION PROCEDURES

- THE CONTRACTOR SHALL PERFORM HIS WORK IN A MANNER CAUSING MINIMAL INCONVENIENCE TO THE RESIDENTS AND MOTORING PUBLIC. ON STREETS WHERE CURB AND GUTTER IS TO BE CONSTRUCTED OR STORM SEWER INSTALLED, THE CONTRACTOR SHALL LIMIT HIS OPERATIONS TO ONE SIDE OF THE STREET ONLY. ONCE THE CURB AND GUTTER AND/OR STORM SEWER IS COMPLETE, THE CONTRACTOR MAY MOVE TO THE OTHER SIDE OF THE STREET TO START THE CURB AND GUTTER AND STORM SEWER CONSTRUCTION.
- IT WILL BE THE CONTRACTOR'S RESPONSIBILITY TO NOTIFY RESIDENTS AND THE VILLAGE WHEN ACCESS TO THEIR DRIVEWAYS WILL BE TEMPORARILY AFFECTED DUE TO CONCRETE CURB AND GUTTER CONSTRUCTION OR STORM SEWER IS TO BE INSTALLED ACROSS A DRIVEWAY. THE CONTRACTOR SHALL CONTACT THE OWNER 48 HOURS PRIOR TO REMOVING THE PAVEMENT. THE CONTRACTOR SHALL DISTRIBUTE NOTICES PROVIDED BY THE VILLAGE TO RESIDENTS. EVERY EFFORT SHALL BE MADE TO ACCOMMODATE ACCESS TO THESE PROPERTIES (KNOCK ON DOORS WHEN A DRIVEWAY IS ABOUT TO BE CLOSED).
- THE CONTRACTOR SHALL NOT BE ALLOWED TO CLOSE ANY DRIVEWAY ENTRANCE WITHIN THE PROJECT LIMITS UNDER ANY CIRCUMSTANCES. CURB AND GUTTER CONSTRUCTION, PIPE INSTALLATION, DRIVEWAY PAVEMENT CONSTRUCTION, ETC. MUST BE COMPLETED AT NO MORE THAN 50% AT A TIME IN ORDER TO PROVIDE ACCESS INTO THE PROPERTY. UPON CONSTRUCTION OF THE INITIAL 50% OF THE CURB, PIPE, AND OR DRIVEWAY PAVEMENT, THE OTHER 50% OF THE DRIVEWAY CAN COMMENCE. THE CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING BARRICADES TO PREVENT TRAFFIC FROM USING THE PORTIONS OF DRIVEWAYS UNDER CONSTRUCTION DURING THIS PERIOD.
- THE CONTRACTOR SHALL FILL HOLES CREATED BY THE REMOVAL OF DRIVEWAY PAVEMENT WHERE NEW GUTTER OR UTILITY HAS BEEN CONSTRUCTED WITH AGGREGATE BASE COURSE (CA-6 CRUSHED) SO THAT BUSINESSES AND RESIDENTS CAN USE THEIR DRIVEWAYS UNTIL THE START OF INSTALLATION OF THE CONCRETE GUTTER AND/OR DRIVEWAY PAVEMENT.
- THE CONTRACTOR'S SUPERINTENDENT AND THE RESIDENT ENGINEER WILL BE REQUIRED TO WORK TOGETHER WITH THE AFFECTED RESIDENTS IN PLANNING THEIR CONSTRUCTION SCHEDULE SO AS TO MINIMIZE THE INCONVENIENCE AND MAINTAIN A REASONABLE LEVEL OF CONSTRUCTION EFFICIENCY. T RESIDENT ENGINEER AND/OR THE VILLAGE RESERVE THE RIGHT TO RESTRICT WORK ON A PAVEMENT SEGMENT IF CONSTRUCTION OPERATIONS IN OTHER CONSTRUCTION ZONES ARE UNACCEPTABLE.

STORM SEWERS, WATER MAINS, AND UTILITIES

- THE LOCATION OF EXISTING DRAINAGE STRUCTURES, STORM SEWERS, WATER MAINS, SANITARY SEWERS, AND ANY OTHER PUBLIC OR PRIVATE UTILITIES AS SHOWN ON THE PLANS IS APPROXIMATE AND THEIR EXACT LOCATION IS TO BE DETERMINED IN THE FIELD BY THE CONTRACTOR.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROTECTION OF ALL LINDERGROUND AND SURFACE UTILITIES EVEN THOUGH THEY MIGHT NOT BE SHOWN ON THE PLANS. ANY UTILITY PROPERTY DAMAGED DURING CONSTRUCTION SHALL BE REPAIRED OR REPLACED TO THE SATISFACTION OF THE OWNER.
- THE CONTRACTOR SHALL COOPERATE WITH THE VILLAGE OF JOHNSBURG IF ANY UTILITY IMPROVEMENTS ARE REQUIRED BY THE VILLAGE WITHIN THE DURATION OF THE CONTRACT.
- FRAME ELEVATIONS GIVEN ON THE PLANS ARE ONLY TO ASSIST THE CONTRACTOR IN DETERMINING THE APPROXIMATE OVERALL HEIGHT OF THE STRUCTURE. FRAMES ON ALL NEW, ADJUSTED OR RECONSTRUCTED STRUCTURES WILL BE ADJUSTED TO THE FINAL ELEVATION OF THE AREA IN WHICH THEY ARE LOCATED AS PART OF THE STRUCTURE INSTALLATION, ADJUSTMENT OR RECONSTRUCTION.
- ANY LOOSE MATERIAL DEPOSITED IN THE FLOW LINE OF DRAINAGE STRUCTURES, WHICH OBSTRUCTS THE NATURAL FLOW OF WATER, SHALL BE REMOVED AT THE CLOSE OF EACH WORKING DAY. PRIOR TO ACCEPTANCE OF THE IMPROVEMENT, ALL DRAINAGE STRUCTURES SHALL BE FREE OF DIRT AND DEBRIS AS PART OF THE STRUCTURE INSTALLATION, ADJUSTMENT OR RECONSTRUCTION
- ALL FRAMES WITH CLOSED LIDS TO BE FURNISHED AS PART OF THE CONTRACT FOR CONSTRUCTION, ADJUSTMENT OR RECONSTRUCTION OF ANY MANHOLE, CATCH BASIN, OR INLET SHALL HAVE CAST INTO THE LID ONE OF THE FOLLOWING WORDS: ALL LIDS TO BE USED ON STORM SEWER STRUCTURES SHALL BEAR THE WORD STORM."
- THE INDISCRIMINATE LISE OF FIRE HYDRANTS EXISTING STREAMS CREEKS WETLANDS OR PONDS IS STRICTLY PROHIBITED. THE CONTRACTOR SHALL PROVIDE A WATER TRUCK AND DRIVER AS REQUIRED TO OBTAIN AND TRANSPORT THIS WATER. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING WATER FROM AN APPROVED SOURCE. IF THIS WATER IS FROM A SOURCE OTHER THAN HIS YARD, WRITTEN APPROVAL FROM THE AGENCY HAVING JURISDICTION FOR THE SOURCE OF THE WATER MUST BE RECEIVED BY THE CONTRACTOR PRIOR TO THE USE OF THE WATER.
- THE CONTRACTOR MUST CONTACT THE VILLAGE OF JOHNSBURG'S WATER OPERATOR TO USE WATER FOR DUST CONTROL, MIXING MORTAR, EQUIPMENT, ETC.
- ALL FRAMES, GRATES, LIDS, AND BOXES SCHEDULED TO BE REMOVED FROM EXISTING STRUCTURES SHALL REMAIN THE PROPERTY OF THE VILLAGE OF JOHNSBURG AND BE DELIVERED TO THE PUBLIC WORKS FACILITY

BACKFILL

SCALE: N.T.S.

- STORM SEWERS AND PIPE CULVERTS SHALL BE BACKFILLED IN ACCORDANCE WITH ARTICLE 550.07, METHOD 1.
- TRENCH BACKFILL MATERIAL SHALL CONSIST OF CA-6 CRUSHED STONE OR CRUSHED AGGREGATE.
- TRENCH BACKFILL IS REQUIRED TO FILL AREAS OF STORM SEWER OR PIPE CULVERT REMOVAL WHERE THERE IS NO REPLACEMENT.
- AT STORM SEWER OR PIPE CUI VERT CROSSINGS, TRENCH BACKETLL SHALL BE PLACED TO THE TOP OF TRENCH AS A TEMPORARY CONDITION UNTIL STABILIZED BASE COURSE IS CONSTRUCTED. THE MAINTENANCE OF THE TRENCH BACKFILL SURFACE IN THE TEMPORARY CONDITION WILL BE THE RESPO

| USER NAME = jstrzal | DESIGNED - JJS | REVISED - |
|-----------------------------|----------------|-----------|
| | DRAWN - DMS | REVISED - |
| PLOT SCALE = 2.0000 ' / in. | CHECKED - JJS | REVISED - |
| PLOT DATE = 7/10/2023 | DATE - | REVISED - |
| | | |

| STATE STANDARDS & GENERAL NOTES | F.A. RTE | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|---------------------------------|-------------|-----------------|------------|-----------------|--------------|
| RIVERSIDE DRIVE | 156 | 20-00016-00-RS | McHENRY | 87 | 2 |
| HIVERSIDE DRIVE | | | CONTRACT | NO. | 61J68 |
| SHEET 1 OF 2 SHEETS STA TO STA | | TILLINOIS FED A | ID PROJECT | | |

GENERAL NOTES CONTINUED...

COIND CIMP COLLE

- 1. ALL RADII FOR PROPOSED CURB AND GUTTER ARE TO THE EDGE OF PAVEMENT, UNLESS OTHERWISE NOTED. CURB AND GUTTER ELEVATIONS SHOWN ALONG RETURNS AND AT POINTS OF CURVATURE, ETC. ARE TO THE EDGE OF PAVEMENT UNLESS OTHERWISE NOTED.
- THE MINIMUM GUTTER FLAG DEPTH OF THE NEW GUTTER WILL BE TEN INCHES (10") REGARDLESS OF THE SIZE AND TYPE OF THE EXISTING CURB AND GUTTER.
- CONCRETE CURB AND GUTTER SHALL BE DEPRESSED AT EACH DRIVEWAY ENTRANCE. THE V-SHAPE OF THE
 GUTTER WILL BE MAINTAINED THROUGH THE DRIVEWAY, BUT THE BACK OF GUTTER SHALL BE LOWERED TO
 MATCH THE GUTTER FLAG ELEVATION.
- 4. ALL REINFORCING BARS SHALL BE EPOXY COATED.
- 5. WHERE NEW CURB AND GUTTER MEETS EXISTING CURB AND GUTTER TO REMAIN, THE GUTTERS SHALL BE CONNECTED WITH TWO 5/8" DIAMETER REINFORCING BARS, TWELVE INCHES (12") LONG. HOLES 5/8" IN DIAMETER SHALL BE DRILLED SIX INCHES (6") INTO THE EXISTING CONCRETE CURB AND GUTTER PRIOR TO DRIVING REINFORCING BARS INTO PLACE.
- CONSTRUCTION JOINTS SHALL BE SAWCUT EVERY FIFTEEN FEET (15') MAXIMUM, TO A DEPTH OF A HALF INCH.
- TWO (2) #5 REINFORCEMENT BARS SHALL BE PROVIDED IN THE CONCRETE GUTTER CENTERED ABOVE UTILITY TRENCHES. CONSTRUCTION JOINTS WITH DOWEL BARS SHALL BE PROVIDED AT THE END OF A DAY'S POUR. EXPANSION JOINTS SHALL BE CONSTRUCTED AT INTERVALS NOT TO EXCEED SIXTY FEET (60'), AND AT POINTS OF TANGENCY TO RADII, OR AS DETERMINED BY THE ENGINEER AND SHALL CONSIST OF A MINIMUM OF ONE INCH (1") THICK PREFORMED EXPANSION JOINT FILLER CONFORMING TO THE CROSS-SECTION OF THE CURB AND GUTTER AND SHALL BE PROVIDED WITH TWO (2) NO. 6 (#6) BY EIGHTEEN INCH (18") EPOXY COATED DOWEL BARS CONFORMING TO ARTICLE 1006.11(B) OF THE STANDARD SPECIFICATIONS. THE DOWEL BARS SHALL BE FITTED WITH A CAP HAVING A PINCHED STOP THAT WILL PROVIDE A MINIMUM OF ONE INCH (1") OF EXPANSION.
- VISUAL INSPECTION OF STRING LINE OR FORMS SHALL BE CONDUCTED PRIOR TO THE INSTALLATION OF ANY CONCRETE UPON TWENTY-FOUR (24) HOURS NOTICE FROM THE CONTRACTOR. THE CONTRACTOR WILL NOT BE PERMITTED TO COVER THE LAYER BEING REVIEWED UNTIL WRITTEN NOTICE HAS BEEN RECEIVED FROM THE ENGINEER. SEGMENTS OF CURB CONSTRUCTION MAY BE SEQUENCED APPROPRIATELY TO PERMIT CONTINUOUS CONSTRUCTION OPERATIONS.

PAVING

- . LONGITUNDINAL CONSTRUCTION JOINTS WILL NOT BE PERMITTED.
- TRANSVERSE CONSTRUCTION JOINTS WILL BE ALLOWED DURING PAVING PROVIDED THE CONTRACTOR
 COMPLETE A SAWCUT AT LEAST SIX INCHES INTO THE ADJACENT MAT AT THE START OF PAVING THE
 FOLLOWING DAY
- CONSTRUCTION JOINTS THAT SIT OVERNIGHT WILL REQUIRE CRACK ROUTING AND SEALING UPON COMPLETION OF SURFACE COURSE CONSTRUCTION. JOINT SEALANT SHALL MEET THE REQUIREMENTS OF ARTICLE 1050.02 OF THE STANDARD SPECIFICATIONS.

<u>SIGNING</u>

- 1. SIGNS SHALL NOT BE MOVED OR COVERED UNTIL PROGRESS OF WORK NECESSITATES IT.
- 2. ALL SIGNS TO BE REMOVED ALONG THE PROJECT SHALL REMAIN THE PROPERTY OF THE VILLAGE OF JOHNSBURG AND SHALL BE RETURNED TO THE VILLAGE UPON REMOVAL.
- 3. THE CONTRACTOR WILL BE REQUIRED TO TEMPORARILY RESET ALL SUCH SIGNS THAT INTERFERE WITH HIS CONSTRUCTION OPERATIONS. ALL SUCH SIGNS MUST BE MAINTAINED STRAIGHT AND CLEAN FOR THE DURATION OF THE TEMPORARY SETTING AND MUST BE RE-ERECTED AT A TEMPORARY LOCATION IN A WORKMANLIKE MANNER AND BE VISIBLE TO THE TRAFFIC FOR WHICH IT IS INTENDED.
- LONGER POSTS MAY BE REQUIRED AT SOME TEMPORARY OR PERMANENT SIGN LOCATIONS TO MAINTAIN PROPER SIGN ELEVATIONS. THIS WORK SHALL BE COMPLETED IN ACCORDANCE WITH SECTION 729 OF THE STANDARD SPECIFICATIONS.

SEDIMENTATION AND EROSION CONTROL

- . SOIL DISTURBANCE SHALL BE CONDUCTED IN SUCH A MANNER AS TO MINIMIZE EROSION. AREAS OF THE DEVELOPMENT SITE THAT ARE NOT TO BE GRADED SHALL BE PROTECTED FROM CONSTRUCTION TRAFFIC OR OTHER DISTURBANCE UNTIL FINAL SEEDING IS PERFORMED.
- SOIL STABILIZATION MEASURES SHALL CONSIDER THE TIME OF YEAR. DEVELOPMENT SITE CONDITIONS AND THE USE OF TEMPORARY OR PERMANENT MEASURES.
- 3. STABILIZATION BY SEEDING SHALL INCLUDE TOPSOIL PLACEMENT AND FERTILIZATION, AS NECESSARY.
- NATIVE SEED MIXTURES SHALL INCLUDE RAPID-GROWING ANNUAL GRASSES OR SMALL GRAINS TO PROVIDE I NITIAL, TEMPORARY SOIL STABILIZATION.
- 5. OFFSITE PROPERTY SHALL BE PROTECTED FROM EROSION AND SEDIMENTATION. VELOCITY DISSIPATION DEVICES SHALL BE PLACED AT CONCENTRATED DISCHARGE LOCATIONS ALONG THE LENGTH OF ANY OUTFALL CHANNEL, AS NECESSARY TO PREVENT EROSION.
- 6. SEDIMENT CONTROL MEASURES SHALL BE INSTALLED PRIOR TO THE DISTURBANCE OF TRIBUTARY AREAS.
- STABILIZATION OF DISTURBED AREAS SHALL BE INITIATED IMMEDIATELY WHENEVER ANY CLEARING, GRADING, EXCAVATING OR OTHER EARTH DISTURBING ACTIVITIES HAVE PERMANENTLY CEASED ON ANY PORTION OF THE DEVELOPMENT SITE, OR TEMPORARY CEASED ON ANY PORTION OF THE DEVELOPMENT SITE AND WILL NOT RESUME FOR A PERIOD EXCEEDING 14 CALENDAR DAYS. STABILIZATION OF DISTURBED AREAS SHALL BE INITIATED WITHIN 1 WORKING DAY OF PERMANENT OR TEMPORARY CESSATION OF EARTH DISTURBING ACTIVITIES AND SHALL BE COMPLETED AS SOON AS POSSIBLE, BUT NO LATER THAN 14 CALENDAR DAYS FROM THE INITIATION OF STABILIZATION WORK IN THE AREA. EXCEPTIONS TO THESE TIME FRAMES ARE SPECIFIED AS INSTANCES WHEN THE INITIATION OF STABILIZATION MEASURES IS PRECLUDED BY SNOW COVER. STABILIZATION MEASURES SHALL BE INITIATED AS SOON AS PRACTICABLE AND IN AREAS WHERE CONSTRUCTION ACTIVITY HAS TEMPORARILY CEASED AND WILL RESUME AFTER 14 DAYS, A TEMPORARY STABILIZATION MEASURE USEN.
- DISTURBANCE OF STEEP SLOPES SHALL BE MINIMIZED. AREAS OR EMBANKMENTS HAVING SLOPES STEEPER THAN 3:1 SHALL BE STABILIZED WITH STAKING IN PLACE SOD, EROSION CONTROL BLANKET IN COMBINATION WITH SEEDING, OR EQUIVALENT CONTROL MEASURE.

- PERIMETER CONTROL MEASURES SHALL BE PROVIDED DOWNSLOPE AND PERPENDICULAR TO THE FLOW OF RUNOFF FROM DISTURBED AREAS, WHERE THE TRIBUTARY AREA IS GREATER THAN 5,000 SQUARE FEET, AND WHERE RUNOFF WILL FLOW IN A SHEET FLOW MANNER. PERIMETER EROSION CONTROL SHALL ALSO BE PROVIDED AT THE BASE OF SOIL STOCKPILES.
- 10. THE DRAINAGE SYSTEM SHALL BE PROTECTED FROM EROSION AND SEDIMENTATION DOWNSLOPE FROM DISTURBED AREAS. INLET PROTECTION THAT REDUCES SEDIMENT LOADING, WHILE ALLOWING RUNOFF TO ENTER THE INLET SHALL BE REQUIRED FOR ALL STORM SEWER. CHECK DAMS, OR AN EQUIVALENT CONTROL MEASURE, SHALL BE REQUIRED FOR ALL CHANNELS. FILTER FABRIC INLET PROTECTION AND STRAW BALE DITCH CHECKS ARE NOT ACCEPTABLE CONTROL MEASURES.
- 11. IF DEWATERING SERVICES ARE USED, ADJOINING PROPERTIES AND DISCHARGE LOCATIONS SHALL BE PROTECTED FROM EROSION. DISCHARGES SHALL BE ROUTED THROUGH AN EFFECTIVE SEDIMENT CONTROL MEASURE (E.G., SEDIMENT TRAP, SEDIMENT BASIN, OR OTHER APPROPRIATE MEASURES). THE ENGINEER AND THE WILL COUNTY SOIL AND WATER CONSERVATION DISTRICT SHALL BE NOTIFIED PRIOR TO THE COMMENCEMENT OF DEWATERING ACTIVITIES.
- 12. ALL TEMPORARY SOIL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE REMOVED WITHIN THIRTY (30) DAYS AFTER FINAL SITE STABILIZATION IS ACHIEVED OR AFTER THE TEMPORARY MEASURES ARE NO LONGER NEEDED. TRAPPED SEDIMENT AND OTHER DISTURBED SOIL AREAS SHALL BE PERMANENTLY STABILIZED.
- 13. STOCKPILED SOIL AND MATERIALS SHALL BE REMOVED FROM FLOOD HAZARD AREAS AT THE END OF EACH WORK DAY. SOIL AND MATERIALS STOCKPILED IN IWMC OR BUFFER AREAS SHALL BE PLACED ON TIMBER MATS. OR AN FOLIVALIENT CONTROL MEASURE.
- 14. EFFECTIVE CONTROL MEASURES SHALL BE UTILIZED TO MINIMIZE THE DISCHARGE OF POLLUTANTS FROM THE DEVELOPMENT SITE. AT A MINIMUM, CONTROL MEASURES SHALL BE IMPLEMENTED IN ORDER TO MINIMIZE THE DISCHARGE OF POLLUTANTS FROM EQUIPMENT AND VEHICLE WASHING, WHEEL WASH WATER, AND OTHER WASH WATER. MINIMIZE THE EXPOSURE OF BUILDING MATERIALS, BUILDING PRODUCTS, CONSTRUCTION WASTES, TRASH, LANDSCAPE MATERIALS, FERTILIZERS, PESTICIDES, HERBICIDES, DETERGENTS, VEHICLE FLUIDS, SANITARY WASTE, AND OTHER MATERIALS PRESENT ON THE DEVELOPMENT SITE TO PRECIPITATION AND TO STORMWATER.
- 5. ADEQUATE RECEPTACLES SHALL BE PROVIDED FOR THE DEPOSITION OF ALL CONSTRUCTION MATERIAL DEBRIS GENERATED DURING THE DEVELOPMENT PROCESS. THE CONTRACTOR SHALL NOT CAUSE OR PERMIT THE DUMPING, DEPOSITING, DROPPING, THROWING, DISCARDING OR LEAVING OR CONSTRUCTION MATERIAL DEBRIS UPON OR INTO ANY DEVELOPMENT SITE, CHANNEL OR IWMC. THE DEVELOPMENT SITE SHALL BE MAINTAINED FREE OF CONSTRUCTION MATERIAL DEBRIS.
- 16. A STABILIZED MAT OF AGGREGATE UNDERLAIN WITH FILTER CLOTH (OR OTHER APPROPRIATE MEASURES) SHALL BE LOCATED AT ANY POINT WHERE TRAFFIC WILL BE ENTERING OR LEAVING A CONSTRUCTION-SITE OF A MAJOR DEVELOPMENT TO OR FROM A PUBLIC RIGHT-OF-WAY, STREET ALLEY, OR PARKING AREA. ANY SEDIMENT OR SOIL REACHING AN IMPROVED PUBLIC RIGHT-OF-WAY, STREET, ALLEY OR PARKING AREA SHALL BE SCRAPED OR STREET CLEANED AS ACCUMULATIONS WARRANT AND TRANSPORTED TO A CONTROLLED SEDIMENT DISPOSAL AREA.
- 17. ALL TEMPORARY AND PERMANENT EROSION AND SEDIMENT CONTROL MEASURES SHALL BE MAINTAINED IN AN EFFECTIVE WORKING CONDITION.
- DRAIN TILE SYSTEMS DISTURBED DURING DEVELOPMENT MUST BE RECONNECTED BY THOSE RESPONSIBLE
 FOR THEIR DISTURBANCE UNLESS THE APPROVED ENGINEERING PLANS INDICATE HOW THE DRAIN TILE
 SYSTEM IS TO BE CONNECTED TO THE PROPOSED STORMWATER MANAGEMENT SYSTEM.
- 19. ALL ABANDONED DRAIN TILES SHALL BE REMOVED IN THEIR ENTIRETY WITHIN THE EXISTING ROW AND/OR EASEMENT.
- 20. DRAIN TILES WITHIN THE DISTURBED AREA OF THE DEVELOPMENT SHALL BE REPLACED, BYPASSED AROUND THE DEVELOPMENT OR INTERCEPTED AND CONNECTED TO THE DRAINAGE SYSTEM FOR THE DEVELOPMENT. THE SIZE OF THE REPLACED OR BYPASSED DRAIN TILE SHALL BE EQUIVALENT TO THE EXISTING DRAIN TILE.

LANDSCAPING

- TREES TO BE PROTECTED DURING CONSTRUCTION WILL BE IDENTIFIED BY THE ENGINEER AND RECEIVE PROTECTION IN ACCORDANCE WITH THE DETAILS PROVIDED IN THE PLANS.
- THE CONTRACTOR SHALL TAKE EXTRA CARE IN GRADING AND EXCAVATING NEAR TREES WHICH ARE NOT MARKED FOR REMOVAL SO AS NOT TO CAUSE INJURY TO THE ROOT SYSTEM OR TRUNKS. ANY DAMAGE DONE TO EXISTING ITEMS BY THE CONTRACTOR SHALL BE REPAIRED BY THE CONTRACTOR AT THE CONTRACTOR'S OWN EXPENSE.
 THE CONTRACTOR SHALL COORDINATE INSTALLATION OF ALL PLANT MATERIAL WITH THE INSTALLATION OF
- OTHER IMPROVEMENTS SUCH AS HARDSCAPE ELEMENTS AND RELATED STRUCTURES. ANY DAMAGE TO EXISTING IMPROVEMENTS IS THE RESPONSIBILITY OF THE CONTRACTOR.
- PHOSPHORUS FERTILIZER HAS BEEN INTENTIONALLY OMITTED FROM THE CONTRACT DUE TO THE PROXIMITY TO THE EXISTING WETLANDS. A PHOSPHORUS-FREE FERTILIZER SHALL BE USED (MIDDLE NUMBER SHOULD

CULVERT CONSTRUCTION

 THE CONTRACTOR SHOULD CONSIDER OPTIMUM CONDITIONS FOR THE CULVERT REPLACEMENT WORK AT DUTCH CREEK MAY BE DURING THE WINTER MONTHS. THE UPPER FOX RIVER IS DRAWN DOWN APPROXIMATELY TWO FEET (2) ANNUALLY FROM BETWEEN NOVEMBER AND APRIL.

ADDITIONALLY FROZEN CONDITIONS MAY PROVIDE THE CONTRACTOR AN IMPROVED WORK PLATFORM. PLEASE CONSULT THE GEOTECHNICAL REPORT FOR SOIL TYPES.

COMMITMENTS

- THE NEW CULVERT SHOULD BE CONSTRUCTED FROM THE ROADWAY PAVEMENT. CONTRACTOR SHALL NOT
 DISTRURB THE CREEK OUTSIDE OF THE RIVERSIDE DRIVE RIGHT-OF-WAY.
- TREE REMOVAL WILL BE RESTRICTED BETWEEN APRIL 1 AND SEPTEMBER 30.
- 3. ONSITE PERSONNEL SHALL BE PROVIDED WITH EDUCATIONAL FLIERS ABOUT BLANDING'S TURTLES AND INFORMED OF THEIR POTENTIAL OCCURRENCE IN THE AREA.
- 4. EXCAVATIONS AND TRENCHES MUST BE COVERED AT THE END OF EACH WORKDAY AND INSPECTED AT THI BEGINNING OF EACH WORKDAY TO ENSURE THAT NO TURTLES OR OTHER NATIVE WILDLIFE HAVE BECOME TRAPPED.
- 5. NO EQUIPMENT SHALL BE STORED OR FUELED IN THE VICINITY OF DUTCH CREEK.
- 6. IN BLANDING'S TURTLES ARE ENCOUNTERED, WORK SHOULD CEASE IMMEDIATELY TO ALLOW THE TURTLE TO MOVE OUT OF THE WAY AND THE DEPARTMENT SHOULD BE CONTACTED (BRAD SEMEL, NATURAL HERITAGE DIVISION, 815-675-2386 EXT. 216).

EARTHWORK SUMMARY

SCALE: N.T.S.

SHEET 2

| | | | CROSS SEC | TION BASED |
|----------|----------|---|----------------------|------------|
| ITEM NO. | CODE | DESCRIPTION | RIVERSIDE DR PATH | TOTAL |
| 1 | 20200100 | EARTH EXCAVATION | 3,408.5 | 3,408.5 |
| 2 | 20201200 | REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL | 1,996.8 | 1,996.8 |
| 3 | 20400800 | FURNISHED EXCAVATION | 0.0 | 0.0 |
| 4 | 30300001 | AGGREGATE SUBGRADE IMPROVEMENT | 0.0 | 0.0 |

HRGreen.com
#inots Professional Design F
HRGreen®

| USER NAME = jstrzal | DESIGNED - JJS | REVISED - |
|---------------------------|----------------|-----------|
| | DRAWN - DMS | REVISED - |
| PLOT SCALE = 2.0000 / in. | CHECKED - JJS | REVISED - |
| PLOT DATE = 8/15/2023 | DATE - | REVISED - |

| G | ENE | RAL NO | TES | | | F.A. RTE | SECT | ION | | COUNTY | TOTAL SHEETS | SHEET NO. |
|-----------------|-----|--------|------|----------------|------|-------------|---------|----------|--------|------------|-----------------|--------------|
| RIVERSIDE DRIVE | | | 156 | 20-00016-00-RS | | ; | McHENRY | 87 | 3 | | | |
| NIVERSIDE DRIVE | | | | | | | | CONTRACT | NO. | 61J68 | | |
| OF | 2 | SHEETS | STA. | TO | STA. | | | ILLINOIS | FED. A | ID PROJECT | | |

| | CODE NO. | ITEM DESCRIPTION | UNIT | TOTAL | STU 80% FEDERAL 0005 |
|---|----------|---|-------|--------|----------------------------|
| + | 20100110 | TREE REMOVAL (6 TO 15 UNITS DIAMETER) | UNIT | 1,230 | 1,230 |
| + | 20100210 | TREE REMOVAL (OVER 15 UNITS DIAMETER) | UNIT | 737 | 737 |
| + | 20101100 | TREE TRUNK PROTECTION | EACH | 15 | 15 |
| + | 20101200 | TREE ROOT PRUNING | EACH | 15 | 15 |
| | 20200100 | EARTH EXCAVATION | CU YD | 3,409 | 3,409 |
| | 20200600 | EXCAVATING AND GRADING EXISTING SHOULDER | UNIT | 9 | 9 |
| | 20201200 | REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL | CU YD | 1,997 | 1,997 |
| | 20700220 | POROUS GRANULAR EMBANKMENT | CU YD | 74 | 74 |
| | 20800150 | TRENCH BACKFILL | CU YD | 675 | 675 |
| | 21101615 | TOPSOIL FURNISH AND PLACE, 4" | SQ YD | 13,315 | 13,315 |
| + | 25000210 | SEEDING, CLASS 2A | ACRE | 2.50 | 2.50 |
| + | 25000314 | SEEDING, CLASS 4B | ACRE | 0.50 | 0.50 |
| + | 25000400 | NITROGEN FERTILIZER NUTRIENT | POUND | 252 | 252 |
| + | 25000600 | POTASSIUM FERTILIZER NUTRIENT | POUND | 252 | 252 |

+ SPECIALTY ITEM

HRGreen.

| USER NAME = jstrzal | DESIGNED - JJS | REVISED - XX/XX/XXXX |
|-----------------------------|----------------|----------------------|
| | DRAWN - DMS | REVISED _ XX/XX/XXXX |
| PLOT SCALE = 2,0000 ' / in. | CHECKED - JJS | REVISED _ XX/XX/XXXX |
| PLOT DATE = 7/18/2023 | DATE - | REVISED - XX/XX/XXXX |

| | | | | SU | MM/ | ARY | OF QU | ANTITIES | 3 | |
|---|--------|--------|-------|----|-----|-----|---------|----------|----|----|
| | | | | | RI | VER | SIDE DI | RIVE | | |
| ı | SCALE: | N.T.S. | SHEET | 1 | OF | 7 | SHEETS | STA. | TO | ST |

| F.A. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEE NO |
|--------------|--------------------|------------|-----------------|------------|
| 156 | 20-00016-00-RS | McHENRY | 87 | 4 |
| | | CONTRACT | NO. 6 | 51J68 |
| | ILLINOIS FED. AI | ID PROJECT | | |

| CODE NO. | ITEM DESCRIPTION | UNIT | TOTAL QUANTITY | STU 80% FEDERAL 0005 |
|----------|---|-------|-------------------|----------------------------|
| 28000305 | TEMPORARY DITCH CHECKS | FOOT | 100.0 | 100.0 |
| 28000400 | PERIMETER EROSION BARRIER | FOOT | 4,360.0 | 4,360.0 |
| 28000510 | INLET FILTERS | EACH | 16 | 16 |
| 28100107 | STONE RIPRAP, CLASS A4 | SQ YD | 44 | 44 |
| 28200200 | FILTER FABRIC | SQ YD | 45 | 45 |
| 40600290 | BITUMINOUS MATERIALS (TACK COAT) | POUND | 13,094 | 13,094 |
| 40600370 | LONGITUDINAL JOINT SEALANT | FOOT | 7,824.0 | 7,824.0 |
| 40600400 | MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS | TON | 5 | 5 |
| 40600982 | HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT | SQ YD | 158 | 158 |
| 40603080 | HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50 | TON | 40 | 40 |
| 40603200 | POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-4.75, N50 | TON | 1,185 | 1,185 |
| 40604060 | HOT-MIX ASPHALT SURFACE COURSE, IL-9.5, MIX "D", N50 | TON | 2,415 | 2,415 |
| 40800050 | INCIDENTAL HOT-MIX ASPHALT SURFACING | TON | 69 | 69 |
| 44000160 | HOT-MIX ASPHALT SURFACE REMOVAL, 2 3/4" | SQ YD | 19,980 | 19,980 |

+ SPECIALTY ITEM

| USER NAME = jstrzal | DESIGNED | - | JJS | REVISED | - | XX/XX/XXXX |
|-----------------------------|----------|---|-----|---------|---|------------|
| | DRAWN | - | DMS | REVISED | - | XX/XX/XXXX |
| PLOT SCALE = 2,0000 ' / in. | CHECKED | - | JJS | REVISED | - | XX/XX/XXXX |
| PLOT DATE = 7/18/2023 | DATE | - | | REVISED | - | XX/XX/XXXX |

| SUMMARY OF QUANTITIES | | RTE. SECT | TION | COUNTY | TOTAL SHEETS | SHEET NO. |
|---|------|-------------|-------------------|------------|-----------------|--------------|
| RIVERSIDE DRIVE | 1 | 156 20-0001 | 6-00-RS | McHENRY | 87 | 5 |
| IIIVEIIOIDE DIIIVE | | | | CONTRACT | NO. | 61J68 |
| SCALE: N.T.S. SHEET 2 OF 7 SHEETS STA. TO | STA. | | ILLINOIS FED. A | ID PROJECT | | |

| | CODE NO. | ITEM DESCRIPTION | UNIT | TOTAL | STU 80% FEDERAL 0005 |
|---|----------|--|-------|--------|----------------------------|
| | 44000400 | GUTTER REMOVAL | FOOT | 204.0 | 204.0 |
| | 44201717 | CLASS D PATCHES, TYPE II, 6 INCH | SQ YD | 335 | 335 |
| | | | | | |
| | 44201721 | CLASS D PATCHES, TYPE III, 6 INCH | SQ YD | 335 | 335 |
| | 44201723 | CLASS D PATCHES, TYPE IV, 6 INCH | SQ YD | 335 | 335 |
| | 48101200 | AGGREGATE SHOULDERS, TYPE B | TON | 420 | 420 |
| | 48203029 | HOT-MIX ASPHALT SHOULDERS, 8 INCH | SQ YD | 490 | 490 |
| | 50105220 | PIPE CULVERT REMOVAL | FOOT | 328.0 | 328.0 |
| | 50200450 | REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL FOR STRUCTURES | CU YD | 189 | 189 |
| | 50800105 | REINFORCEMENT BARS | POUND | 39,000 | 39,000 |
| + | 50901720 | BICYCLE RAILING | FOOT | 31.0 | 31.0 |
| | 51500100 | NAME PLATES | EACH | 1 | 1 |
| | 54003000 | CONCRETE BOX CULVERTS | CU YD | 210 | 210 |
| | 542A0217 | PIPE CULVERTS, CLASS A, TYPE 1 12" | FOOT | 17.0 | 17.0 |
| | 542A8215 | PIPE CULVERTS, CLASS A, TYPE 2 EQUIVALENT ROUND-SIZE 30" | FOOT | 37.0 | 37.0 |

+ SPECIALTY ITEM

HRGreen.com
Illinois Professional Design Firm
184-001322
HRGreen.

| | USER NAME = jstrzal | DESIGNED - | 115 | 5 | REVISED | - | XX/XX/XXXX |
|---|-----------------------------|------------|-----|----|---------|---|------------|
| ĺ | | DRAWN - | DN | мs | REVISED | - | XX/XX/XXXX |
| | PLOT SCALE = 2,0000 ' / in. | CHECKED - | 115 | 5 | REVISED | - | XX/XX/XXXX |
| | PLOT DATE = 7/18/2023 | DATE - | | | REVISED | - | XX/XX/XXXX |

STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION

| | | su | ЈММ | ARY | OF QU | ANTITII | ES | F.A. RTE. | SECTIO | | | |
|---------------|-----------------|----|------------|-----|--------|---------|---------|--------------|--------|--|--|--|
| | RIVERSIDE DRIVE | | | | | | | | | | | |
| | NIVENSIDE DRIVE | | | | | | | | | | | |
| SCALE: N.T.S. | SHEET | 3 | OF | 7 | SHEETS | STA. | TO STA. | i | (ILL | | | |

| | CODE NO. | ITEM DESCRIPTION | UNIT | TOTAL | STU 80% FEDERAL 0005 |
|---|----------|--|-------|-------|----------------------------|
| | 54213657 | PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12" | EACH | 4 | 4 |
| | | | | | |
| | 54213660 | PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15" | EACH | 1 | 1 |
| | | | | | |
| | 54214515 | PRECAST REINFORCED CONCRETE FLARED END SECTIONS, EQUIVALENT ROUND-SIZE 30" | EACH | 2 | 2 |
| | | | | | |
| | 550A0050 | STORM SEWERS, CLASS A, TYPE 1 12" | FOOT | 209.0 | 209.0 |
| | | | | | |
| | 550A0340 | STORM SEWERS, CLASS A, TYPE 2 12" | FOOT | 844.0 | 844.0 |
| | | | | | |
| | 550A0360 | STORM SEWERS, CLASS A, TYPE 2 15" | FOOT | 255.0 | 255.0 |
| | | | | | |
| | 59100100 | GEOCOMPOSITE WALL DRAIN | SQ YD | 216 | 216 |
| | | | | | |
| | 59300100 | CONTROLLED LOW-STRENGTH MATERIAL | CU YD | 155 | 155 |
| | | | | | |
| | 60200805 | CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 8 GRATE | EACH | 1 | 1 |
| | | | | | |
| | 60240301 | INLETS, TYPE B, TYPE 8 GRATE | EACH | 6 | 6 |
| | | | | | |
| | 60602500 | CONCRETE GUTTER, TYPE A | FOOT | 105.0 | 105.0 |
| | | | | | |
| + | 63000001 | STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS | FOOT | 560.0 | 560.0 |
| | | | | | |
| + | 63000035 | BACK SIDE PROTECTION OF GUARDRAIL | FOOT | 365.0 | 365.0 |
| | | | | | |
| + | 63100167 | TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT | EACH | 4 | 4 |

+ SPECIALTY ITEM

| | USER NAME = jstrzal | DESIGNED . | - | JJS | REVISED | - | XX/XX/XXXX |
|---|-----------------------------|------------|---|-----|---------|---|------------|
| ĺ | | DRAWN . | - | DMS | REVISED | - | XX/XX/XXXX |
| | PLOT SCALE = 2,0000 ' / in. | CHECKED . | - | JJS | REVISED | - | XX/XX/XXXX |
| | PLOT DATE = 7/18/2023 | DATE . | - | | REVISED | - | XX/XX/XXXX |

| STATE OF ILLINOIS |
|------------------------------|
| DEPARTMENT OF TRANSPORTATION |

SCALE: N.T.S.

| SUMMARY | OF QU | ANTITIES | | F.A. RTE. | SECTION | COUNTY | TOTAL SHEET SHEETS NO. | | |
|---|---------|----------|--------------------|--------------|----------|--------|---------------------------|-----|--|
| RIVER | SIDE DE | IVE | 156 20-00016-00-RS | | McHENRY | 87 | 7 | | |
| | OIDE DI | 11 V L | | | CONTRACT | NO. | 61J68 | | |
| SHEET 4 OF 7 SHEETS STA. TO STA. (ILLINOIS FED. AID PROJECT | | | | | | | | T i | |

| | CODE NO. | ITEM DESCRIPTION | UNIT | TOTAL QUANTITY | STU 80% FEDERAL 0005 |
|---|----------|--|-------|-------------------|----------------------------|
| | 63200310 | GUARDRAIL REMOVAL | FOOT | 410.0 | 410.0 |
| | | | | | |
| | 64200108 | SHOULDER RUMBLE STRIPS, 8 INCH | FOOT | 2,760.0 | 2,760.0 |
| | | | | | |
| | 67100100 | MOBILIZATION | L SUM | 1 | 1 |
| | | | | | |
| | 70300100 | SHORT TERM PAVEMENT MARKING | FOOT | 5,931.0 | 5,931.0 |
| | 70200150 | CHORT TERM RAYEMENT MARKING REMOVAL | 60.57 | 2 027 0 | 2 027 0 |
| | 70300150 | SHORT TERM PAVEMENT MARKING REMOVAL | SQ FT | 3,037.0 | 3,037.0 |
| | 72400100 | REMOVE SIGN PANEL ASSEMBLY - TYPE A | EACH | 2 | 2 |
| | | | | | |
| + | 72501000 | TERMINAL MARKER-DIRECT APPLIED | EACH | 4 | 4 |
| | | | | | |
| + | 78000100 | THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS | SQ FT | 146.0 | 146.0 |
| | | | | | |
| + | 78000200 | THERMOPLASTIC PAVEMENT MARKING - LINE 4" | FOOT | 22,984.0 | 22,984.0 |
| | | | | | |
| + | 78000400 | THERMOPLASTIC PAVEMENT MARKING - LINE 6" | FOOT | 582.0 | 582.0 |
| | | | | | |
| + | 78000600 | THERMOPLASTIC PAVEMENT MARKING - LINE 12" | FOOT | 478.0 | 478.0 |
| | | | | | |
| + | 78000650 | THERMOPLASTIC PAVEMENT MARKING - LINE 24" | FOOT | 26.0 | 26.0 |
| + | 78011000 | GROOVING FOR RECESSED PAVEMENT MARKING LETTERS AND SYMBOLS | SQ FT | 146.0 | 146.0 |
| | | | | | 2.0.0 |
| + | 78011025 | GROOVING FOR RECESSED PAVEMENT MARKING 5" | FOOT | 22,984.0 | 22,984.0 |

+ SPECIALTY ITEM

HRGreen.com
||llinois Protessional Design Firm #184-001322

| USER NAME = jstrzal | DESIGNED . | - | JJS | REVISED | - | XX/XX/XXXX |
|-----------------------------|------------|---|-----|---------|---|------------|
| | DRAWN . | - | DMS | REVISED | - | XX/XX/XXXX |
| PLOT SCALE = 2,0000 ' / in. | CHECKED . | - | JJS | REVISED | - | XX/XX/XXXX |
| PLOT DATE = 7/18/2023 | DATE . | - | | REVISED | | XX/XX/XXXX |

| SUMMARY OF QUANTITIES RIVERSIDE DRIVE | | | | | | | | | | | | | |
|---------------------------------------|-------|---|----|---|--------|------|----|------|--|--|--|--|--|
| SCALE: N.T.S. | SHEET | 5 | OF | 7 | SHEETS | STA. | TO | STA. | | | | | |

| | F.A. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHE |
|---|--------------|-------------------|------------|-----------------|------|
| | 156 | 20-00016-00-RS | McHENRY | 87 | 8 |
| _ | | | CONTRACT | NO. | 51J6 |
| Ī | | (ILLINOIS (FED. A | ID PROJECT | | |

| | CODE NO. | ITEM DESCRIPTION | UNIT | TOTAL | STU 80% FEDERAL 0005 |
|---|----------|---|-------|--------|----------------------------|
| + | 78011035 | GROOVING FOR RECESSED PAVEMENT MARKING 7" | FOOT | 582.0 | 582.0 |
| + | 78011065 | GROOVING FOR RECESSED PAVEMENT MARKING 13" | FOOT | 478.0 | 478.0 |
| + | 78011125 | GROOVING FOR RECESSED PAVEMENT MARKING 25" | FOOT | 26.0 | 26.0 |
| + | 78200005 | GUARDRAIL REFLECTORS, TYPE A | EACH | 10 | 10 |
| | X0326806 | WASHOUT BASIN | L SUM | 1 | 1 |
| | X0900064 | MEMBRANE WATERPROOFING SYSTEM FOR BURIED STRUCTURES | SQ YD | 216 | 216 |
| | X1200274 | TEMPORARY BYPASS PUMPING SYSTEM | L SUM | 1 | 1 |
| | X2130010 | EXPLORATION TRENCH, SPECIAL | FOOT | 100.0 | 100.0 |
| + | X2200020 | FENCE REMOVAL AND REINSTALLATION | FOOT | 317.0 | 317.0 |
| + | X2511630 | EROSION CONTROL BLANKET (SPECIAL) | SQ YD | 13,315 | 13,315 |
| | X4021000 | TEMPORARY ACCESS (PRIVATE ENTRANCE) | EACH | 9 | 9 |
| | X4400196 | HOT-MIX ASPHALT SURFACE REMOVAL, SPECIAL | SQ YD | 81 | 81 |
| | X4420210 | TEMPORARY PATCHING | SQ YD | 135 | 135 |
| | X7010216 | TRAFFIC CONTROL AND PROTECTION, (SPECIAL) | L SUM | 1 | 1 |

SPECIALTY ITEM

HRGreen.com Illinois Professional Design Firm # 184-001322

| | USER NAME = jstrzal | DESIGNED _ | JJS | REVISED | - | XX/XX/XXXX |
|---|-----------------------------|------------|-----|---------|---|------------|
| Ì | | DRAWN - | DMS | REVISED | - | XX/XX/XXXX |
| | PLOT SCALE = 2,0000 ' / in. | CHECKED _ | JJS | REVISED | - | XX/XX/XXXX |
| ı | PLOT DATE = 7/18/2023 | DATE _ | | REVISED | - | XX/XX/XXXX |

| | | SU | ММ | ARY | OF QU | ANTITIE | S | | | | F.A. RTE. | SECTION | | COUNTY | TOTAL SHEETS | |
|---------------|-----------------|----|----|-----|---------|---------|----|---|------|--|----------------|----------------|---------|-----------|-----------------|---|
| | | | RI | VFR | CIDE DE | IVE | | | | | 156 | 20-00016-00-RS | | McHENRY | 87 | 9 |
| | RIVERSIDE DRIVE | | | | | | | | | | | CONTRACT | NO. | 61J68 | | |
| SCALE: N.T.S. | SHEET | 6 | OF | 7 | SHEETS | STA. | TO |) | STA. | | i | ILLINOIS | FED. AI | D PROJECT | | |

| | | CODE NO. | ITEM DESCRIPTION | UNIT | TOTAL QUANTITY | STU 80% FEDERAL 0005 |
|---|---|----------|-------------------------------------|-------|-------------------|----------------------------|
| | + | X7810300 | RECESSED REFLECTIVE PAVEMENT MARKER | EACH | 270 | 270 |
| | | | | | | |
| | | XX008916 | CONTROLLED STIFFNESS COLUMNS | L SUM | 1 | 1 |
| | | | | | | |
| | | Z0013798 | CONSTRUCTION LAYOUT | L SUM | 1 | 1 |
| | | | | | | |
| • | | Z0076600 | TRAINEES | HOUR | 500 | 500 |
| | | | | | | |
| • | | Z0076604 | TRAINEES TRAINING PROGRAM GRADUATE | HOUR | 500 | 500 |
| | | | | | | |
| | | | | | | |

SPECIALTY ITEM

HRGreen.com

HRGreen.com

July 200

HRGreen.com


Illinois Protessional Design Firm

184-001322

| USER NAME = jstrzal | DESIGNED - JJS | REVISED - XX/XX/XXXX |
|-----------------------------|----------------|----------------------|
| | DRAWN - DMS | REVISED _ XX/XX/XXXX |
| PLOT SCALE = 2,0000 ' / in. | CHECKED - JJS | REVISED - XX/XX/XXXX |
| PLOT DATE = 7/18/2023 | DATE - | REVISED _ XX/XX/XXXX |


| STATE OF ILLINOIS |
|------------------------------|
| DEPARTMENT OF TRANSPORTATION |

| | | | | | | | | | | F.A. RTE. | SECTION | COUNTY TOTAL SHEETS | | SHEET NO. | |
|--|---------------|-------|---|-----|--------|---------|------|----|---|--------------|----------------|---------------------|------------|--------------|-------|
| | | | | | | | | | | 156 | 20-00016-00-RS | McHENRY | 87 | 10 | |
| | | | | 111 | A FIII | JIDE DI | IIVL | | | | | | CONTRACT | NO. | 61J68 |
| | SCALE: N.T.S. | SHEET | 7 | OF | 7 | SHEETS | STA. | TO |) | STA. | ĺ | (ILLINOIS (FED. A | ID PROJECT | | T i |



EXISTING TYPICAL SECTION RIVERSIDE DRIVE

STA. 10+29 TO STA. 18+00 STA. 19+92 TO STA. 26+86 STA. 46+00 TO STA. 52+26 STA. 53+17 TO STA. 59+51



EXISTING TYPICAL SECTION RIVERSIDE DRIVE


STA. 18+00 TO STA. 19+92 STA. 26+86 TO STA. 30+55 STA. 52+26 TO STA. 59+51 (GUTTER ON THE SB LN)

EXISTING LEGEND

- A HMA SURFACE COURSE; 1½" 3¾"
- B) HMA BINDER COURSE; 1¼" 3¾"
- C AGGREGATE BASE COURSE; +/- 12"
- D HOT-MIX ASPHAL SURFACE REMOVAL, 2¾"
- (E) OMITTED
- F AGGREGATE SHOULDER
- G EXISTING GROUND
- H COMBINATION CONCRETE CURB AND GUTTER TYPE B6.12
- CONCRETE GUTTER TYPE A
 (SPOT REMOVAL AND REPLACEMENT AS
 DIRECTED BY THE ENGINEER)
- D PCC SIDEWALK


PROPOSED LEGEND

- 1 OMITTED
- OMITTED
- 3 SEEDING CLASS 2A / EROSION CONTROL BLANKET (SPECIAL)
- 4 TOPSOIL FURNISH & PLACE, 4"
- 5 HOT-MIX ASPHALT SURFACE COURSE, MIX "D", IL-9.5, N50, 2"
- 6) POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-4.75, N50, 1"
- 7 SHOULDER RUMBLE STRIPS, 8"
- 8 OMITTED
- AGGREGATE SHOULDERS, TYPE B (9% MAX SLOPE)
 (CA-6 CRUSHED AGG OR CRUSHED STONE)
- (10) CONCRETE GUTTER, TYPE A (SPOT REMOVAL & REPLACEMENT AS DIRECTED BY THE ENGINEER)



PROPOSED TYPICAL SECTION RIVERSIDE DRIVE

STA. 10+29 TO STA. 18+00 STA. 19+92 TO STA. 26+86 STA. 46+00 TO STA. 52+26



PROPOSED TYPICAL SECTION RIVERSIDE DRIVE

STA. 18+00 TO STA. 19+92 STA. 52+26 TO STA. 59+51 (GUTTER ON THE SB LN)

STA. 26+86 TO STA. 30+55

STA. 59+51 TO STA. 64+76 (GUTTER ON THE SB LN)

HOT-MIX ASPHALT MIXTURE REQUIREMENTS

| MIXTURE TYPE | AIR VOIDS @ Ndes | QMP |
|--|------------------|-----------|
| | | |
| PAVEMENT RESURFACING | | |
| HOT-MIX ASPHALT SURFACE COURSE, MIX "D", IL-9.5, N50; 2" | 4% @ 50 GYR | LR 1030-2 |
| POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-4.75, N50: 1" | 4% @ 50 GYR | LR 1030-2 |
| MULTI-USE PATH | | |
| HOT-MIX ASPHALT SURFACE COURSE, MIX "D", IL-9.5, N50; 3" (2 LIFTS) | 4% @ 50 GYR | LR 1030-2 |
| PAVEMENT PATCHING | | |
| CLASS D PATCHES, (HMA BINDER IL-19mm); 6" | 4% @ 70 GYR | LR 1030-2 |
| INCIDENTAL HMA SURFACING (DRIVEWAYS) | | |
| HOT-MIX ASPHALT SURFACE COURSE, MIX "D", IL-9.5, N50; 2" | 4% @ 50 GYR | LR 1030-2 |
| HMA SHOULDERS | | |
| HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50, 8" | 4% @ 50 GYR | LR 1030-2 |

QMP DESIGNATION: QUALITY CONTROL/QUALITY ASSURANCE (QC/QA) PER 1030-2

THE UNIT WEIGHT USED TO CALCULATE ALL HMA SURFACE MIXTURE QUANTITIES IS 112 LBS/SQ YD/IN.

THE "AC TYPE" FOR POLYMERIZED HMA MIXES SHALL BE "SBS/SBR PG 76-22" AND FOR NON-POLYMERIZED HMA THE "AC TYPE" SHALL BE "PG 64-22" UNLESS MODIFIED BY RECLAIMED MATERIALS SPECIFICATIONS.


PATCHING LOCATIONS TO BE DETERMINED AFTER MILLING OPERATIONS.

LONGITUDINAL JOINT SEALANT SHALL BE PLACED OVER THE HMA POLY BC IL-4.75 N50 FOR RESURFACING AREAS.

| USER NAME = jstrzal | DESIGNED - JJS | REVISED - XX/XX/XXXX |
|------------------------------|----------------|----------------------|
| | DRAWN - DMS | REVISED - XX/XX/XXXX |
| PLOT SCALE = 20.0000 ' / in. | CHECKED - JJS | REVISED - XX/XX/XXXX |
| PLOT DATE = 8/21/2023 | DATE - | REVISED - XX/XX/XXXX |


SCALE: N.T.S.

| EXISTING & PROPOSED TYPICAL SECTIONS | F.A. RTE | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|--------------------------------------|-------------|----------------|-----------|-----------------|--------------|
| RIVERSIDE DRIVE | 156 | 20-00016-00-RS | McHENRY | 87 | 11 |
| IIIVEIISIDE DIIIVE | | | CONTRACT | NO. | 61J68 |
| SHEET 1 OF 2 SHEETS STA. TO STA. | | ILLINOIS FED A | D PROJECT | | - |



EXISTING TYPICAL SECTION RIVERSIDE DRIVE

STA. 30+55 TO STA. 36+88



EXISTING TYPICAL SECTION RIVERSIDE DRIVE


STA. 36+88 TO STA. 46+00

EXISTING LEGEND

- A HMA SURFACE COURSE; 1½" 3¾"
- B HMA BINDER COURSE; 1½" 3¾"
- C AGGREGATE BASE COURSE; +/- 12"
- D HOT-MIX ASPHAL SURFACE REMOVAL, 2¾
- E OMITTED
- F AGGREGATE/EARTH SHOULDER
- G EXISTING GROUND
- H COMBINATION CONCRETE CURB AND GUTTER TYPE B6.12
- CONCRETE GUTTER, TYPE A
 (SPOT REMOVAL AND REPLACEMENT AS DIRECTED
 BY THE ENGINEER)
- (J) PCC SIDEWALK


PROPOSED LEGEND

- 1 OMITTED
- 2 OMITTED
- 3 SEEDING CLASS 2A / EROSION CONTROL BLANKET (SPECIAL)
- 4 TOPSOIL FURNISH & PLACE, 4"
- (5) HOT-MIX ASPHALT SURFACE COURSE, MIX "D", IL-9.5, N50, 2"
- 6 POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-4.75, N50, 1"
- 7 SHOULDER RUMBLE STRIPS, 8"
- 8 OMITTED
- 9 AGGREGATE SHOULDERS, TYPE B (9% MAX SLOPE) (CA-6 CRUSHED AGG OR CRUSHED STONE)
- CONCRETE GUTTER, TYPE A
 (SPOT REMOVAL & REPLACEMENT)



PROPOSED TYPICAL SECTION RIVERSIDE DRIVE

STA. 30+55 TO STA. 36+88



PROPOSED TYPICAL SECTION RIVERSIDE DRIVE

STA. 36+88 TO STA. 46+00

| CT NO.: 2//7C CONTACT: 2//7CO-sht- R: //_pdf_b | |
|---|---------|
| HRG PROJECT I HRG PROJ. CON FILE NAME: 2//7 PLOT DRIVER: A | HRGreen |


HRGreen.com Illinois Professional Design Firm # 184-001322

| USER NAME = jstrzal | DESIGNED - JJS | REVISED - XX/XX/XXXX |
|------------------------------|----------------|----------------------|
| | DRAWN - DMS | REVISED - XX/XX/XXXX |
| PLOT SCALE = 20.0000 ' / in. | CHECKED - JJS | REVISED - XX/XX/XXXX |
| PLOT DATE = 8/21/2023 | DATE - | REVISED - XX/XX/XXXX |

| STATE | OF | ILLINOIS |
|------------|----|----------------|
| DEPARTMENT | 0F | TRANSPORTATION |

SCALE: N.T.S.

| ı | EXISTING & PROPOSED TYPICAL SECTIONS | | | | | | | F.A. RTE | SEC ⁻ | ΠΟN | | COUNTY | TOTAL SHEETS | SHEET NO. | |
|---|--------------------------------------|---|----|---|--------|------|-----|----------------|------------------|-----|----------|----------|-----------------|--------------|--|
| | RIVERSIDE DRIVE | | | | | | 156 | 20-00016-00-RS | | | McHENRY | 87 | 12 | | |
| | UIACUSINE DUIAC | | | | | | | | | | | CONTRACT | NO. | 61J68 | |
| | SHEET | 2 | OF | 2 | SHEETS | STA. | TO | STA. | | | ILLINOIS | FED. AI | D PROJECT | | |



BENCHMARKS:

SOURCE BENCHMARK: CUT SQUARE ON THE NORTHWEST CORNER OF THE NORTH HEADWALL OF BRIDGE OVER CREEK AT THE NORTHEAST CORNER OF JOHNSBURG ROAD AND RIVERSIDE DRIVE ELEVATION = 752.55' (NAVD88)

SITE BM50:

ARROW BOLT IN FIRE HYDRANT LOCATED AT THE NORTHWEST CORNER OF RUNNING BROOK FARM BOULEVARD AND RIVERSIDE DRIVE. ELEVATION = 773.40' (NAVD88)

SITE BM51:

SPIKE IN UTILITY POLE AT THE NORTHEAST CORNER OF PLEASANT DRIVE AND RIVERSIDE DRIVE.

ELEVATION = 777.53' (NAVD88)

SITE BM52:

CUT CROSS IN CONCRETE CURB AT THE NORTHEAST CORNER OF JOHNSBURG ROAD AND RIVERSIDE DRIVE LOCATED APPROXIMATELY 29 FEET NORTHEAST OF TRAFFIC SIGNAL.

ELEVATION = 755.81' (NAVD88)

SITE BM53:

SPIKE IN SECOND UTILITY POLE SOUTH OF DUTCH CREEK LOCATED ON THE EAST SIDE OF RIVERSIDE DRIVE.
ELEVATION = 748.68' (NAVD88)

| PROP. CURVE PRBL_PATH_1 PI STA. = $18+76.53$ $\Delta = 42^{\circ} 49^{\circ} 17^{\circ} (LT)$ $D = 85^{\circ} 38^{\circ} 33^{\circ}$ $R = 66.90^{\circ}$ $T = 26.23^{\circ}$ $L = 50.00^{\circ}$ $E = 4.96^{\circ}$ P.C. STA. = $18+50.30$ P.T. STA. = $19+00.30$ | PROP. CURVE PRBL_PATH_4 PI STA. = 19+18.18 \[\Delta = 16^\circ 33' \ 20'' \ (LT) \] \[D = 62^\circ 16' \ 41'' \] \[R = 92.00' \] \[T = 13.38' \] \[L = 26.58' \] \[E = 0.97' \] P.C. STA. = 19+04.79 P.T. STA. = 19+31.38 | PROP. CURVE PRBL_PATH_5 PI STA. = 19+68.29 \[\times = 26^\circ 17' 54'' (RT) \] \[D = 36^\circ 15' 47'' \] \[R = 158.00' \] \[T = 36.91' \] \[L = 72.52' \] \[E = 4.25' \] \[P.C. STA. = 19+31.38 \] \[P.T. STA. = 20+03.90 \] | PROP. CURVE PRBL_PATH_8 PI STA. = 21+53.02 \[\Delta = 9^\circ 34^\circ 39^\circ (LT) \] \[D = 40^\circ 20^\circ 57^\circ \] \[R = 142.00^\circ \] \[T = 11.90^\circ \] \[L = 23.74^\circ \] \[E = 0.50^\circ \] P.C. STA. = 21+41.13 P.T. STA. = 21+64.86 | PROP. CURVE PRBL_PATH_11 PI STA. = 23+61.80 \[\Delta = 5^\circ 36^\circ 54^\circ (LT) \] \[D = 28^\circ 38^\circ 52^\circ R = 200.00^\circ T = 9.81^\circ L = 19.60^\circ E = 0.24^\circ P.C. STA. = 23+51.99 P.T. STA. = 23+71.59 | PROP. CURVE PRBL PATH_14 PI STA. = 24+33.25 Δ = 5° 36′ 37" (RT) D = 28° 38′ 52" R = 200.00' T = 9.80' L = 19.58' E = 0.24' P.C. STA. = 24+23.45 P.T. STA. = 24+43.04 |
|---|--|---|---|--|---|
| | PROP. CURVE PRBL_PATH_24 PI STA. = $37+59.00$ $\Delta = 14^{\circ} 59' 52'' (RT)$ $D = 52^{\circ} 05' 13''$ R = 110.00' T = 14.48' L = 28.79' E = 0.95' P.C. STA. = $37+44.52$ P.T. STA. = $37+73.32$ | PROP. CURVE PRBL_PATH_27 PI STA. = $38+11.67$ $\Delta = 15^{\circ} 45' 57'' (LT)$ $D = 57^{\circ} 17' 45''$ R = 100.00' T = 13.85' L = 27.52' E = 0.95' P.C. STA. = $37+97.83$ P.T. STA. = $38+25.34$ | PROP. CURVE PRBL_PATH_30 PI STA. = $41+47.04$ $\Delta = 37^{\circ} 38' 28" (RT)$ $D = 7^{\circ} 19' 37"$ R = 782.00' T = 266.53' L = 513.75' E = 44.17' P.C. STA. = $38+80.51$ P.T. STA. = $43+94.26$ | PI STA. = 57+83.52 | PROP. CURVE PRBL_PATH_42 PI STA. = $58+86.82$ $\Delta = 8^{\circ} 20' 11'' (RT)$ $D = 18^{\circ} 11' 21''$ R = 315.00' T = 22.96' L = 45.83' E = 0.84' P.C. STA. = $58+63.87$ P.T. STA. = $59+09.70$ |
| PROP. CURVE PRBL_PATH_55 PI STA. = $64+13.15$ Δ = 34° 54' 26" (LT) | PROP. CURVE PRBL_PATH_58 PI STA. = 64+56.96 Δ = 24° 00' 48" (RT) | | | | |

| ALIG | NMENT COORDINA | TES - RIVERSIDE DE | RIVE PATH |
|-------------|----------------|--------------------|------------|
| DESCRIPTION | STATION | N | E |
| POB/PC | 18+50.30 | 2076309.06 | 1004680.11 |
| PI | 18+76.53 | 2076319.93 | 1004703.98 |
| PT | 19+00.30 | 2076344.14 | 1004714.10 |
| PC | 19+04.79 | 2076348.63 | 1004714.10 |
| PI | 19+18.18 | 2076362.01 | 1004714.10 |
| PCC | 19+31.38 | 2076374.84 | 1004710.29 |
| PI | 19+68.29 | 2076410.22 | 1004699.77 |
| PT | 20+03.90 | 2076446.60 | 1004706.02 |
| PC | 21+41.13 | 2076581.85 | 1004729.24 |
| PI | 21+53.02 | 2076593.58 | 1004731.25 |
| PT | 21+64.86 | 2076605.48 | 1004731.29 |
| PC | 23+51.99 | 2076792.60 | 1004731.83 |
| PI | 23+61.80 | 2076802.41 | 1004731.85 |
| PT | 23+71.59 | 2076812.17 | 1004730.92 |
| PC | 24+23.45 | 2076863.80 | 1004726.00 |
| PI | 24+33.25 | 2076873.56 | 1004725.07 |
| PT | 24+43.04 | 2076883.35 | 1004725.09 |
| PI | 25+57.82 | 2076998.14 | 1004725.41 |
| PI | 26+52.62 | 2077092.94 | 1004725.69 |
| PC | 30+25.74 | 2077466.05 | 1004726.77 |
| PI | 32+72.76 | 2077713.07 | 1004727.48 |
| PT | 35+04.27 | 2077915.68 | 1004586.16 |
| PC | 37+44.52 | 2078112.74 | 1004448.71 |
| PI | 37+59.00 | 2078124.61 | 1004440.43 |
| PT | 37+73.32 | 2078138.23 | 1004435.50 |

| VATION = 748. | 68' (NAVD88) | | |
|---------------|----------------|---------------------|------------|
| ALIG | NMENT COORDINA | ATES - RIVERSIDE DR | IVE PATH |
| DESCRIPTION | STATION | N | E |
| PC | 37+97.83 | 2078161.27 | 1004427.16 |
| PI | 38+11.67 | 2078174.29 | 1004422.45 |
| PT | 38+25.34 | 2078185.54 | 1004414.38 |
| PC | 38+80.51 | 2078230.36 | 1004382.21 |
| PI | 41+47.04 | 2078446.91 | 1004226.82 |
| PT | 43+94.26 | 2078713.27 | 1004236.01 |
| PI | 44+90.24 | 2078809.20 | 1004239.32 |
| PI | 45+74.08 | 2078893.01 | 1004241.66 |
| PI | 50+94.97 | 2079413.13 | 1004269.96 |
| PI | 56+01.99 | 2079920.14 | 1004271.76 |
| PC | 57+01.42 | 2080019.53 | 1004274.73 |
| PI | 57+83.52 | 2080101.59 | 1004277.18 |
| PCC | 58+63.87 | 2080177.63 | 1004308.13 |
| PI | 58+86.82 | 2080198.89 | 1004316.78 |
| PT | 59+09.70 | 2080218.68 | 1004328.42 |
| PI | 59+73.00 | 2080273.24 | 1004360.53 |
| PI | 59+98.56 | 2080292.09 | 1004377.78 |
| PI | 60+45.20 | 2080333.18 | 1004399.85 |
| PI | 61+25.65 | 2080403.00 | 1004439.81 |
| PI | 61+51.05 | 2080426.92 | 1004448.36 |
| PC | 63+84.23 | 2080629.97 | 1004562.99 |
| PI | 64+13.15 | 2080655.16 | 1004577.21 |
| PT | 64+40.28 | 2080683.96 | 1004574.46 |
| PC | 64+49.51 | 2080693.17 | 1004573.77 |
| PI | 64+56.96 | 2080700.59 | 1004573.15 |
| PT | 64+64.18 | 2080707.62 | 1004575.61 |
| | | | |

HRGreen.com HRGreen.

P.C. STA. = 63+84.23

P.T. STA. = 64+40.28

D = 62° 16' 41" R = 92.00'

T = 28.93'

L = 56.05'

E = 4.44'

D = 163° 42' 08"

P.C. STA. = 64+49.51

P.T. STA. = 64+64.18

R = 35.00'

T = 7.44'

L = 14.67'


E = 0.78'

| USER NAME = jstrzal | DESIGNED - | JJS | REVISED | - | XX/XX/XXXX |
|-------------------------------|------------|-----|---------|---|------------|
| | DRAWN - | DMS | REVISED | - | XX/XX/XXXX |
| PLOT SCALE = 400.0000 ' / in. | CHECKED - | JJS | REVISED | - | XX/XX/XXXX |
| PLOT DATE = 7/10/2023 | DATE - | | REVISED | - | XX/XX/XXXX |


CP#1-


| | | ALI | GNMI | ENT | & BEN | ICHMARI | (S | | F.A. RTE. | SECTI |
|----------------|-------|-----|------|-----|---------|---------|--------|------|--------------|----------|
| | | | RIV | VFR | SIDE DE | RIVE | | | 156 | 20-00016 |
| | | | •••• | V L | OIDE DI | | | | | |
| SCALE: 1"=200' | SHEET | 1 | OF | 1 | SHEETS | STA. | TO | STA. | | (1 |

| F.A. RTE. | SECTION | | COUNTY | TOTAL SHEETS | SHEE |
|--------------|----------------|---------|-----------|-----------------|-------|
| 156 | 20-00016-00-RS | McHENRY | 87 | 13 | |
| | | | CONTRACT | NO. | 51J68 |
| | ILLINOIS | FED. AI | D PROJECT | | |



HRG PROJECT NO.: 20/700
HRG PROJ. CONTACT:
FILE NAME: 20/700-Arr-rem-0i.dgn
PLOT DRIVER: IL.-poft.bw.pircfg
PEN TABLE: plotiabel.tbl






HRGreen


HECKED -REVISED -XX/XX/XXXX PLOT DATE = 7/18/2023

DEPARTMENT OF TRANSPORTATION

RIVERSIDE DRIVE SCALE: 1"=20" SHEET 3 OF 5 SHEETS STA. 33+61.00 TO STA. 44+50.00

CONTRACT NO. 61J68






HRGreen.


DRAWN -CHECKED -REVISED -PLOT DATE = 7/10/2023 REVISED -


DEPARTMENT OF TRANSPORTATION


RIVERSIDE DRIVE SCALE: 1"=20' SHEET 5 OF 5 SHEETS STA. 56+10.00 TO STA. 64+60.59


MCHENRY 87 18 20-00016-00-RS CONTRACT NO. 61J68































HRG PROJECT NO., 2//700 HRG PROJ. CONTACT: FILE NAME: 2//700-snt-defour.dg PLOT DRIVER: IL.pdf.bw.pitcfg







PLOT DATE = 7/10/2023

REVISED -XX/XX/XXXX


SCALE: 1"=20' SHEET 2 OF 5 SHEETS STA. 21+90.00 TO STA. 33+61.00



SCALE: 1"=20' SHEET 3 OF 5 SHEETS STA. 33+61.00 TO STA. 44+50.00




HRG PROJECT NO.: 21700
HRG PROJ. CONTACT:
FILE NAME: 21700-Sht-Ero
FLOT DRIVER: IL_DOf_Lbw.pl
PEN TABLE SIGNSTONED HAND



HRGreen.com HRGreen.


| USER NAME = jstrzal | DESIGNED - JJS | REVISED - XX/XX/XXXX |
|------------------------------|----------------|----------------------|
| | DRAWN - DMS | REVISED - XX/XX/XXXX |
| PLOT SCALE = 40.0000 ' / in. | CHECKED - JJS | REVISED - XX/XX/XXXX |
| PLOT DATE = 7/10/2023 | DATE - | REVISED - XX/XX/XXXX |


| | EROSION CONTROL PLAN | | | | | | | | | | ION | COUNTY | SHEETS | NO. |
|-----------------|----------------------|---|----|----------|---------------|----|------|----------|---------------------------|---------|---------|----------|--------|-------|
| RIVERSIDE DRIVE | | | | | | | | | 156 | 20-0001 | 6-00-RS | MCHENRY | 87 | 34 |
| | NIVENSIDE DUIVE | | | | | | | | | | | CONTRACT | NO. | 61J68 |
| SCALE: 1"=20" | SHEET | 5 | OF | 5 SHEETS | STA. 56+10.00 | TO | STA. | 64+60.59 | ILLINOIS FED. AID PROJECT | | | | | |




DETAIL "A"

LATERAL CONNECTION TO EXISTING SEWER OF 27" (675) OR SMALLER







METAL BINDING

DETAIL "B"


CLASS SI CONCRETE COLLAR

CONSTRUCTION SEQUENCE

- CUT THE EXISTING END OF THE PIPE SO AS TO PRESENT A FLUSH BUTT JOINT. BRUSH AND CLEAN ALL PIPES.
- APPLY THE MASTIC JOINT SEALANT TO THE FIRST 6" (150) OF EACH PIPE.
- BUTT THE PIPES TOGETHER LEAVING A MINIMUM OF 12' x 6' (300 x 150) DEEP EXCAVATION UNDER AND AROUND EACH PIPE END.
- CUT A PIECE OF SHEET METAL GAGE NO. 19 1.1 (0.0418) 18" (450) WIDE BY THE OUTSIDE CIRCUMFERANCE OF THE PIPE PLUS 3" (75) LONG.
- WRAP THE SHEET METAL AROUND THE PIPES, 9" (225) ON EACH SIDE OF THE JOINT, STARTING AT THE TOP OF THE PIPE.
- LAP THE SHEET METAL AT LEAST 3" (75)
 AT THE TOP OF THE PIPE AND PLACE THE
 MASTIC JOINT SEALANT BETWEEN THE LAP.
- PLACE TWO METAL BANDS AROUND THE SHEET METAL AND TIGHTEN.
- WIPE OFF ANY EXCESS MASTIC JOINT SEALANT THAT OOZES OUT FROM BETWEEN THE SHEET METAL AND THE PIPES.

SCALE: NONE

PLACE CLASS SI CONCRETE AROUND THE JOINT.



DETAIL "C"

PROPOSED LATERAL CONNECTION TO EXISTING SEWER OF 30" (750) OR LARGER

NOTES:

MATERIAL

MATERIAL USED FOR THE TEE OR WYE SECTION SHALL BE COMPATIBLE WITH THE EXISTING STORM SEWER OR THE PROPOSED STORM SEWER.

CONSTRUCTION METHODS

- THIS WORK SHALL BE CONSTRUCTED IN CONFORMANCE WITH THE APPLICABLE PORTIONS OF SECTION 550 OF THE STANDARD SPECIFICATIONS.
- II. CONNECTION TO AN EXISTING STORM SEWER SHALL BE BY EITHER OF THE FOLLOWING METHODS:

 A) PROPOSED STORM SEWER CONNECTION TO EXISTING SEWER OF 27" (675) OR SMALLER SEE DETAIL "A" AND "B".
 - B) PROPOSED STORM SEWER CONNECTION TO EXISTING SEWER OF 30" (750) OR LARGER SEE DETAIL "C".

IF THE EXISTING SEWER PIPE IS CRACKED, BROKEN OR OTHERWISE DAMAGED BY THE CONTRACTOR IN MAKING THE CIRCULAR OPENING, THE CONTRACTOR SHALL REPLACE THAT SECTION OF PIPE WITH PIPE EQUAL AND SIMILAR IN ALL RESPECTS TO THE PIPE IN THE EXISTING SEWER, IN A CAREFUL WORKMANLIKE MANNER, WITHOUT EXTRA COMPENSATION.

GENERAL

- CARE MUST BE TAKEN TO PREVENT DEBRIS FROM ENTERING THE SEWER.
 ALL DEBRIS WHICH ENTERS THE SEWER MUST BE REMOVED. THE SEWER MUST
 BE LEFT CLEAN AND UNOBSTRUCTED UPON COMPLETION OF THE CONTRACT.
- 2. CARE MUST BE TAKEN TO PREVENT ANY PART OF THE NEW PIPE CONNECTION FROM PROJECTING INTO THE EXISTING SEWER.

BASIS OF PAYMENT

- TEE OR WYE CONNECTIONS SHALL BE PAID FOR AT THE CONTRACT UNIT PRICE EACH FOR STORM SEWER TEE OR WYE OF THE TYPE AND SIZE SPECIFIED IN THE PLANS, THIS PRICE SHALL INCLUDE ALL EXCAVATION OF THE TRENCH, REMOVAL OF THE EXISTING STORM SEWER, FURNISHING AND INSTALLING THE SPECIFIED TEE OR WYE SECTION, FURNISHING AND INSTALLING THE REQUIRED CONCRETE COLLAR, AND ALL OTHER MATERIAL NECESSARY TO COMPLETE THIS WORK AS SHOWN AND SPECIFIED.
- REMOVAL AND REINSTALLATION OF EXISTING STORM SEWER ADJACENT TO THE PROPOSED TEE OR WYE SECTION, FOR THE PURPOSE OF FACILITATING THE INSTALLATION OF THE TEE OR WYE SECTION, WILL NOT BE PAID FOR SEPARATELY BUT SHALL BE INCLUDED IN THE UNIT PRICE BID FOR THE WORK.
- TRENCH BACKFILL, EXCAVATION IN ROCK AND REMOVAL AND REPLACEMENT OF UNSUITABLE MATERIAL BELOW PLAN BEDDING GRADE WILL BE PAID FOR SEPARATELY.
- 4. CONCRETE COLLAR FOR CONNECTING A PROPOSED STORM SEWER TO AN EXISTING STORM SEWER WILL NOT BE PAID PAID FOR SEPARATELY BUT SHALL BE INCLUDED IN THE COST OF THE PROPOSED STORM SEWER.

* ALL DIMENSIONS ARE IN INCHES (MILLIMETERS)
UNLESS OTHERWISE SHOWN.

| USER NAME = Lawrence.DeManche | DESIGNED - M. DE YONG | REVISED - R. SHAH 09-09-94 |
|-------------------------------|-----------------------|-----------------------------|
| | DRAWN - | REVISED - R. SHAH 10-25-94 |
| PLOT SCALE = 100,0000 ' / in, | CHECKED - | REVISED - R. SHAH 06-12-96 |
| PLOT DATE = 11/18/2022 | DATE - 07-25-90 | REVISED - K. SMITH 11-18-22 |

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

| DETAIL OF STORM SEWER CONNECTION TO EXISTING SEWER | | | | | | | | | | | | |
|--|-------|---|----|---|--------|------|--|---------|--|--|--|--|
| | SHEET | 1 | OF | 1 | SHEETS | STA. | | TO STA. | | | | |


MODEL: Default

METHOD OF MEASUREMENT

REFER TO SECTION 442 OF THE STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION AND THE RECURRING SPECIAL PROVISION "PATCHING WITH HOT-MIX ASPHALT OVERLAY REMOVAL."

BASIS OF PAYMENT

- 1. REFER TO SECTION 442 OF THE STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION AND THE RECURRING SPECIAL PROVISION "PATCHING WITH HOT-MIX ASPHALT OVERLAY REMOVAL."
- SAW CUT/SCORING OF EXISTING HMA OVERLAY IS INCLUDED IN THE COST OF PAVEMENT PATCHING.
- SAW CUT/SCORING OF EXISTING PAVEMENT IS INCLUDED IN THE COST OF PAVEMENT PATCHING.



SEQUENCE OF CONSTRUCTION (PATCHING FIRST)

1. REMOVE THE EXISTING HMA MATERIAL OVER THE AREA TO BE PATCHED.

SEE TYPICAL SECTIONS FOR

THICKNESS AND MATERIALS


- 2. REMOVE AND REPLACE WITH CLASS C OR D PATCH.
- 3. REPLACE HMA MATERIAL OVER THE AREA TO BE PATCHED.

SEQUENCE OF CONSTRUCTION (MILLING FIRST)

- 1. MILL HMA FIRST IF THERE IS AT LEAST 4½ INCHES OR MORE OF HMA MATERIAL ON TOP OF THE EXISTING PAVEMENT OR IF THE PAVEMENT IS FULL DEPTH HMA. A MINIMUM OF 2 INCHES OF HMA MATERIAL SHALL BE IN PLACE AFTER MILLING.
- 2. REMOVE AND REPLACE WITH FULL DEPTH CLASS D PATCHES TO TOP OF MILLED SURFACE.

ALL DIMENSIONS ARE IN INCHES (MILLIMETERS) UNLESS OTHERWISE SHOWN.

| USER NAME = Lawrence.DeManche | DESIGNED - R. SHAH | REVISED - R. BORO 01-01-07 | | PAVEMENT PATCHING FOR | | SECTION | COUNTY | TOTAL SHEET | |
|-------------------------------|--------------------|-----------------------------|------------------------------|--|----------|------------------|-----------|--------------------|--|
| | DRAWN - | REVISED - R. BORO 09-04-07 | STATE OF ILLINOIS | | 156 | 20-00016-00-RS | MCHENRY | 87 36 | |
| PLOT SCALE = 100.0000 ' / in. | CHECKED - | REVISED - K. ENG 10-27-08 | DEPARTMENT OF TRANSPORTATION | HMA SURFACED PAVEMENT | | BD400-04 (BD-22) | | CONTRACT NO. 61J68 | |
| PLOT DATE = 11/18/2022 | DATE - 10-25-94 | REVISED - K. SMITH 11-18-22 | | SCALE: NONE SHEET 1 OF 1 SHEETS STA. TO STA. | — | ILLINOIS FED. A | D PROJECT | | |




- X 3" (75) MINIMUM FROM TOP AND BOTTOM OF THE CONCRETE PAVEMENT OR BASE COURSE.
- ** IF THE FINAL SURFACE OF THE PAVEMENT IS CONCRETE, THE GUTTER IS TO BE FLUSH WITH THE PAVEMENT.

CURB OR CURB AND GUTTER REMOVAL AND REPLACEMENT


ALL DIMENSIONS ARE IN INCHES (MILLIMETERS) UNLESS OTHERWISE SHOWN.

| USER NAME = footemj | DESIGNED - A. HOUSEH | REVISED - A. ABBAS 03-21-97 | STATE OF ILLINOIS | CURB OR CURB AND GUTTER | F. R | RTE. SECTION | COUNTY SHEETS NO. |
|----------------------------|----------------------|-----------------------------|------------------------------|---|------|--------------------|--------------------|
| | DRAWN - | REVISED - M. GOMEZ 01-22-01 | | REMOVAL AND REPLACEMENT | | 156 20-00016-00-RS | MCHENRY 87 37 |
| PLOT SCALE = 50.0000 / in. | CHECKED - | REVISED - R. BORO 12-15-09 | DEPARTMENT OF TRANSPORTATION | COLE, NONE CHEET 1 OF 1 CHEETS STA TO S | | BD600-06 (BD-24) | CONTRACT NO. 61J68 |
| PLOT DATE = 7/11/2019 | DATE - 03-11-94 | REVISED - K. SMITH 07-11-19 | | SCALE: NONE SHEET 1 OF 1 SHEETS STA. TO S | STA. | ILLINOIS FED. A | ID PROJECT |



(FOR BUTT JOINT AND HMA TAPER SEE DETAIL BELOW)

OPTION 1




HMA CONSTRUCTED TEMPORARY RAMP

(FOR BUTT JOINT AND HMA TAPER SEE DETAIL BELOW)

OPTION 2

TYPICAL TEMPORARY RAMP




TYPICAL BUTT JOINT AND HMA TAPER FOR MILLING AND RESURFACING

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

PROPOSED HMA OR PCC
SURFACE REMOVAL - BUTT JOINT
30'-0" (9.0 m) (NOTE "A")
15'-0" (4.5 m) (NOTE "B")
(NOTE "D")
40'-0" (12.0M) (NOTE "A1")

** * EXISTING PAVEMENT

BUTT JOINT DETAIL



TYPICAL BUTT JOINT AND HMA TAPER FOR RESURFACING ONLY

** PC CONCRETE, HMA OR HMA RESURFACED PAVEMENT.

GENERAL NOTES

- A. MAINLINE ARTERIAL ROADWAYS AND MAJOR SIDE ROADS.
- A1. INTERSTATES
- B. MINOR SIDE ROADS.
- C. THE TEMP. RAMP SHALL BE CONSTRUCTED IMMEDIATELY UPON REMOVAL OF THE EXISTING HMA SURFACE.
- D. THE BUTT JOINT SHALL BE CONSTRUCTED IMMEDIATELY PRIOR TO PLACING THE PROPOSED HMA COURSES.
- E. TAPER THE TEMP. RAMP AT A RATE OF 3' 4" (1.02m) PER 1 INCH (25 mm) OF MILLING THICKNESS.
 - * SEE TYPICAL SECTIONS FOR MILLING THICKNESS.
- F. SEE ARTICLE 406.08 AND 406.14 OF THE STANDARD SPECIFICATIONS FOR "HMA AND/OR PCC SURFACE REMOVAL, BUTT JOINT".
- *** 20'-0" (6.1 m) PER 1 (25) RESURFACING (NOTE "A") 10'-0" (3.0 m) PER 1 (25) RESURFACING (NOTE "B")

BASIS OF PAYMENT

- THE BUTT JOINT WILL BE PAID FOR AT THE CONTRACT UNIT PRICE PER SQUARE YARD (SQUARE METER) FOR "HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT" OR FOR "PORTLAND CEMENT CONCRETE SURFACE REMOVAL- BUTT JOINT".
- THE TEMPORARY RAMP AND SAW CUT SHALL BE INCLUDED IN THE UNIT COST FOR HMA OR PCC SURFACE REMOVAL-BUTT JOINT.


SCALE: NONE

ALL DIMENSIONS ARE IN INCHES (MILLIMETERS) UNLESS OTHERWISE SHOWN.

COUNTY

MCHENRY 87 38

CONTRACT NO. 61J68



SECTION A-A


NOTES:

- 1. THE AGGREGATE SHOULDER, 10 (250) OR HMA SHOULDER, 6 (150) (IF REQUIRED) SHALL EXTEND UNDER THE TRAFFIC BARRIER TERMINAL.
- 2. "EXISTING" GUARDRAIL REFERS TO CONNECTING TERMINAL SECTION TO GUARD RAILING PRIOR TO THE MIDWEST GUARDRAIL SYSTEM.
- 3. THE CONTRACTOR SHALL VERIFY THE TYPE/HEIGHT OF GUARDRAIL IN-PLACE BEFORE ORDERING THE NEW TERMINAL SECTION. COST INCLUDED WITH THE COST OF THE TERMINAL. THE EXISTING GUARDRAIL HEIGHT SHALL TRANSISTION TO MATCH THE NEW TERMINAL END SECTION AND SHALL BE PAID FOR AS VERTICAL ADJUSTMENT OF EXISTING GUADRAIL.

DETAILS FOR STEEL PLATE BEAM

GUARD RAIL ADJACENT TO CURB AND GUTTER

[FOR ROADWAY SPEED 35 MPH (60 kmh) TO 45 MPH (70 kmh)]



DEPRESSED CURB AND GUTTER AND SHOULDER TREATMENT AT TBT TY. 1 SPL.

AGGREGATE SHOULDER, 10 (250) WILL BE PAID ACCORDING TO SECTION 481.

HMA SHOULDERS 6 (150) (IF REQUIRED) WILL BE PAID ACCORDING TO SECTION 482.

COMB. CONC. C&G, STEEL PLATE BEAM GUARD RAIL AND TRAFFIC BARRIER TERMINAL, OF THE TYPE SPECIFIED WILL BE PAID FOR SEPARATELY.

TBT = TRAFFIC BARRIER TERMINAL
ALL DIMENSIONS ARE IN INCHES (MILLIMETERS)
UNLESS OTHERWISE SHOWN.

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

DETAILS FOR DEPRESSED CURB & GUTTER AND SHOULDER TREATMENT AT TBT TY. 1 SPL.

SHEET 1 OF 1 SHEETS STA. TO STA

TYPICAL BENCHING DETAIL FOR EMBANKMENT

GENERAL NOTES


- CONSTRUCT SUCCEEDING BENCH CUTS AND EMBANKMENT PLACEMENT AND COMPACTION FROM BOTTOM TO TOP IN STAIRSTEP FASHION.
- 2. EXISTING FORESLOPE PREPARED IN ACCORDANCE WITH ARTICLE 205.03 OF THE STANDARD SPECIFICATIONS.
- 3. BENCH CUT EXISTING SLOPE TYPICAL FOR EACH STEP.
- 4. TRIM TO FINAL SLOPE.
- EQUAL 8-INCH (200) LIFTS OF EMBANKMENT COMPACTED IN ACCORDANCE WITH ARTICLE 205.05 OF THE STANDARD SPECIFICATIONS.

BASIS OF PAYMENT

 EXCAVATION OF BENCH CUTS WITHIN EXISTING EMBANKMENT WILL BE PAID FOR AT THE CONTRACT UNIT PRICE PER CUBIC METER OR CUBIC YARD FOR "EARTH EXCAVATION". THIS PRICE WILL INCLUDE ALL LABOR AND MATERIAL, NO ADDITIONAL COMPENSATION WILL BE ALLOWED.

ALL DIMENSIONS ARE IN INCHES (MILLIMETERS) UNLESS OTHERWISE SHOWN.

| USER NAME = Lawrence.DeManche | DESIGNED - | REVISED - K. SMITH 11-18-22 | /ISED - K. SMITH 11-18-22 | | | BENCHING DETAIL | | | | | SECTION | COUNTY | TOTAL SHEET NO. | |
|-------------------------------|------------------|-----------------------------|------------------------------|-------------|---------|-------------------------|--------|------|---------|----------------|-----------------|-----------|-----------------|-------------|
| | DRAWN - CADD | REVISED - | STATE OF ILLINOIS | | | | | | 156 | 20-00016-00-RS | MCHENRY | 87 40 | | |
| PLOT SCALE = 100,0000 ' / in. | CHECKED - S.E.B. | REVISED - | DEPARTMENT OF TRANSPORTATION | | | FOR EMBANKMENT WIDENING | | | | | | BD-51 | CONTRAC | T NO. 61J68 |
| PLOT DATE = 11/18/2022 | DATE - 06-16-04 | REVISED - | | SCALE: NONE | SHEET 1 | OF 1 | SHEETS | STA. | TO STA. | | ILLINOIS FED. A | D PROJECT | | |



NOTES:

- SIDE ROAD WITH A SPEED LIMIT OF 40 MPH (60 km/h) OR LESS AS SHOWN ON THE DRAWING AND AS DIRECTED BY THE ENGINEER:
- a) ONE "ROAD CONSTRUCTION AHEAD" SIGN 36 x 36 (900x900) WITH A FLASHER MOUNTED ON IT APPROXIMATELY 200' (60 m) IN ADVANCE OF THE MAIN ROUTE.
- b) THE CLOSED PORTION OF THE MAIN ROUTE SHALL BE PROTECTED BY BLOCKING WITH TYPE I, TYPE II OR TYPE III BARRICADES, 1/3 OF THE CROSS SECTION OF THE CLOSED PORTION.
- SIDE ROAD WITH A SPEED LIMIT GREATER THAN 40 MPH (60 km/h) AS SHOWN ON THE DRAWING AND AS DIRECTED BY THE ENGINEER:
- a) ONE "ROAD CONSTRUCTION AHEAD" SIGN 48 x 48 (1.2 m x 1.2 m) WITH A FLASHER MOUNTED ON IT APPROXIMATELY 500" (150 m) IN ADVANCE OF THE MAIN POLITE
- THE CLOSED PORTION OF THE MAIN ROUTE SHALL BE PROTECTED BY
 b) BLOCKING WITH TYPE III BARRICADES, 1/2 OF THE CROSS SECTION
 OF THE CLOSED PORTION.
- CONES MAY BE SUBSTITUTED FOR BARRICADES OR DRUMS AT HALF THE SPACING DURING DAY OPERATIONS. CONES SHALL BE A MINIMUM OF 28 (710)
- WHEN THE SIDE ROAD LIES BETWEEN THE BEGINNING OF THE MAINLINE
 4. SIGNING AND THE WORK ZONE, A SINGLE HEADED ARROW (M6-1) SHALL
 BE USED IN LIEU OF THE DOUBLE HEADED ARROW (M6-4).


- WHEN WORK IS BEING PERFORMED ON A SIDE ROAD OR DRIVEWAY, FOLLOW THE APPLICABLE STANDARD(S). THE DIRECTIONAL ARROW (M6-1 OR M6-4) SHALL BE COVERED OR REMOVED WHEN NO LONGER CONSISTENT WITH THE TRAFFIC CONTROL SET-UP.
- 6. ADVANCE WARNING SIGNS ARE TO BE OMITTED ON DRIVEWAYS UNLESS OTHERWISE SPECIFIED IN THE PLANS OR BY THE ENGINEER
- THE TRAFFIC CONTROL AND PROTECTION FOR SIDE ROADS, INTERSECTIONS, AND DRIVEWAYS SHALL BE INCLUDED IN THE COST OF SPECIFIED TRAFFIC CONTROL STANDARDS OR ITEMS.

All dimensions are in inches (millimeters) unless otherwise shown.

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

TRAFFIC CONTROL AND PROTECTION FOR SIDE ROADS, INTERSECTIONS, AND DRIVEWAYS


| SHEET 1 OF 1 SHEETS STA. TO ST



*** REDUCE TO 40' (12 m) O.C. ON CURVES WITH POSTED OR ADVISORY SPEED 45 M.P.H. (70 km/h) OR LESS.


3 @ 40' (12 m) O.C. \Rightarrow LANE REDUCTION TRANSITION


SEE FIGURE 3B-14 MUTCD



TW0-LANE/TW0-WAY

O.C.






MULTI-LANE/DIVIDED

MULTI-LANE/UNDIVIDED

3 @ 40' (12 m)



** WHERE THE MEDIAN WIDTH IS 6' (2 m) OR LESS USE TWO-WAY MARKERS.

TURN LANES

GENERAL NOTES

- 1. MARKERS USED WITH DASHED LINES SHALL BE CENTERED IN THE GAP BETWEEN SEGMENTS.
- 2. MARKERS USED ADJACENT TO SOLID LINES SHALL BE OFFSET 2 TO 3 (50 TO 75) TOWARD TRAFFIC AS SHOWN.
- MARKERS THROUGH TANGENTS LESS THAN 500° (150 m) IN LENGTH BETWEEN CURVES SHALL BE INSTALLED AT THE LESSER OF THE TWO CURVE SPACINGS.
- 4. MARKERS ARE TO BE USED ADJACENT TO BOTH SOLID WHITE LINES IN DUAL LEFT TURN LANES

SYMBOLS

- YELLOW STRIPE
- WHITE STRIPE
- ONE-WAY AMBER MARKER
- ONE-WAY CRYSTAL MARKER (W/O)
- TWO-WAY AMBER MARKER

LANE MARKER NOTES

- A. USE DOUBLE LANE LINE MARKERS SPACED AS SHOWN.
- B. REDUCE TO 40' (12 m) O.C. ON CURVES WHERE ADVISORY SPEEDS ARE 10 M.P.H (20 km/h) LOWER THAN POSTED SPEEDS.


DESIGN NOTES

- 1. DOUBLE LANE LINE MARKERS SHALL BE USED UNLESS SPECIFIED OTHERWISE.
- 2. EXCEPT AS SHOWN ON THE LANE REDUCTION TRANSITION AND FREEWAY EXIT RAMP DETAIL. MARKERS ARE NOT TO BE SPECIFIED ON RIGHT EDGE LINES.
- THE EXACT MARKER LIMITS, SPACING, AND COLOR SHALL BE INCLUDED IN THE PLANS WHEN STANDARD SPECIFICATIONS ARE NOT BEING USED.
- 4. MARKERS SHOULD NOT BE USED ALONGSIDE CURBS EXCEPT FOR EXTREMELY SHORT SECTIONS OF CURBS WHERE NOT MORE THAN TWO MARKERS WOULD BE INVOLVED.

All dimensions are in inches (millimeters) unless otherwise shown.

REVISED - T. RAMMACHER 03-12-99 USER NAME = footemj DESIGNED -SECTION COUNTY TYPICAL APPLICATIONS STATE OF ILLINOIS DRAWN REVISED - T. RAMMACHER 01-06-00 156 20-00016-00-RS MCHENRY 87 42 RAISED REFLECTIVE PAVEMENT MARKERS (SNOW-PLOW RESISTANT) PLOT SCALE = 50.0000 ' / in. CHECKED -REVISED - C. JUCIUS 09-09-09 **DEPARTMENT OF TRANSPORTATION** TC-11 CONTRACT NO. 61J68 SHEET 1 OF 1 SHEETS STA. PLOT DATE = 3/4/2019 DATE REVISED - C JUCIUS 07-01-13

3 @ 80' (24 m) O.C.



D(FT) SPEED LIMIT 665 750 COMBINATION LEFT AND U-TURN 5'-4" (1620) T 32 R (810) LANE REDUCTION TRANSITION

* LANE REDUCTION ARROWS REQUIRED AT SPEEDS OF 45 MPH OF GREATER OR WHEN SPECIFIED IN PLANS.

TYPE OF MARKING WIDTH OF LINE PATTERN COLOR SPACING / REMARKS NO PASSING ZONE LINES: FOR ONE DIRECTION FOR BOTH DIRECTIONS 5½ (140) C-C FROM SKIP-DASH CENTERLINE 11 (280) C-C OMIT SKIP-DASH CENTERLINE BETWEEN 4 (100) 2 @ 4 (100) LANE LINES SKIP-DASH SKIP-DASH 10' (3 m) LINE WITH 30' (9 m) SPACE (125) ON FREEWAYS DOTTED LINES SAME AS LINE BEING EXTENDED SKIP-DASH SAME AS LINE BEING EXTENDED 2' (600) LINE WITH 6' (1.8 m) SPACE (EXTENSIONS OF CENTER, LANE OR TURN LANE MARKINGS) EDGE LINES 4 (100) SOLID YELLOW-LEFT WHITE-RIGHT OUTLINE MEDIANS IN YELLOW 6 (150) LINE; FULL SIZE LETTERS & SYMBOLS (8' (2.4m)) TURN LANE MARKINGS SOLID SEE TYPICAL TURN LANE MARKING DETAIL WHITE WO WAY LEFT TURN MARKING YELLOW 10' (3 m) LINE WITH 30' (9 m) SPACE FOR 2 @ 4 (100) EACH DIRECTION SKIP-DASH; 51/2 (140) C-C BETWEEN SOLID LINE AND SKIP-DASH LINE SEE TYPICAL TWO-WAY LEFT TURN MARKING DETAIL 8' (2.4m) LEFT ARROW CROSSWALK LINES (PEDESTRIAN) A. DIAGONALS (BIKE & EQUESTRIAN) B. LONGITUDINAL BARS (SCHOOL) NOT LESS THAN 6' (1.8 m) APART 2' (600) APART 2' (600) APART SEE TYPICAL CROSSWALK MARKING DETAILS. PLACE 4' (1.2 m) IN ADVANCE OF AND PARALLEL TO CROSSWALK, IF PRESENT. OTHERWISE, PLACE AT DESIRED STOPPING POINT. PARALLEL TO CROSSROAD CENTERLINE, WHERE STOP LINES 24 (600) SOLID WHITE 11 (280) C-C FOR THE DOUBLE LINE SEE TYPICAL PAINTED MEDIAN MARKING. PAINTED MEDIANS 2 @ 4 (100) WITH 12 (300) DIAGONALS SOLID YELLOW: TWO WAY TRAFFIC WHITE: ONE WAY TRAFFIC NO DIAGONALS USED FOR 4" (1.2 m) WIDE MEDIANS 8 (200) WITH 12 (300) DIAGONALS @ 45° SOLID DIAGONALS: 15' (4.5 m) C-C (LESS THAN 30MPH (50 km/h)) 20' (6 m) C-C 30MPH (50 km/h) TO 45MPH (70 km/h)) 30' (9 m) C-C (OVER 45MPH (70 km/h)) 24 (600) TRANSVERSE LINES; "RR" IS 6' (1.8 m) LETTERS; 16 (400) LINE FOR "X" RAILROAD CROSSING SOLID WHITE SEE STATE STANDARD 780001 50' (15 m) C-C (LESS THAN 30MPH (50 km/h)) 75' (25 m) C-C (30 MPH (50 km/h) TO 45MPH (70 km/h)) 150' (45 m) C-C (OVER 45MPH (70 km/h)) SHOULDER DIAGONALS (REQUIRED FOR 12 (300) @ 45° SOLID WHITE - RIGHT YELLOW - LEFT HOULDERS > 8') U TURN ARROW SEE DETAIL SOLID WHITE 2 ARROW COMBINATION LEFT AND U TURN 30.4 SF

U-TURN

FOR FURTHER DETAILS ON PAVEMENT MARKING REFER TO STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION AND STATE STANDARD 780001.

8 (200) WHITE -

— 2 (50)

2 (50)

RAISED

unless otherwise shown.

DESIGNED - EVERS REVISED - C. JUCIUS 09-09-09 DISTRICT ONE DRAWN REVISED - C. JUCIUS 07-01-13 STATE OF ILLINOIS TYPICAL PAVEMENT MARKINGS REVISED -**DEPARTMENT OF TRANSPORTATION** CHECKED C. JUCIUS 12-21-15 OF 2 SHEETS STA. TO STA 03-19-90 REVISED -SCALE: NONE SHEET 1


DATE

USER NAME = footemj


PLOT SCALE = 50.0000 / in.

SECTION COUNTY COUNTY SHEETS NO.

MCHENRY 87 43 156 20-00016-00-RS CONTRACT NO. 61J68 TC-13



4 (100) LINE = 45.5 ft. (13.9 m) 15.2 sq. ft. (1.41 sq. m)



4 (100) LINE = 64.1 ft. (19.5 m)

USER NAME = footemj

PLOT DATE = 3/4/2019

21.4 sq. ft. (1.99 sq. m)


- 09-18-94

DESIGNED -

CHECKED -

DRAWN

DATE




QUANTITY

4 (100) LINE = 82.5 ft. (25.1 m) 27.5 sq. ft. (2.53 sq. m)

NOTE:

ALL QUANTITIES OF PLACEMENT ARE REPRESENTED IN LINEAR FEET OF 4" LINES TO MATCH THE 4" TEMPORARY TAPE PAY ITEM AND REPRESENTS THE TOTAL QUANTITY OF 4" TAPE REQUIRED.



4 (100) LINE = 225.9 ft. (68.9 m) 75.3 sq. ft. (6.99 sq. m)


> All dimensions are in inches (millimeters) unless otherwise shown.


REVISED - T. RAMMACHER 03-02-98 REVISED - E. GOMEZ 08-28-00 REVISED - E. GOMEZ 08-28-00 REVISED - A. SCHUETZE 09-15-16

STATE OF ILLINOIS **DEPARTMENT OF TRANSPORTATION**

SHORT TERM PAVEMENT MARKING LETTERS AND SYMBOLS SCALE: NONE SHEET 1 OF 1 SHEETS STA.

SECTION 156 20-00016-00-RS MCHENRY 87 44 TC-16 CONTRACT NO. 61J68





| CT NO.: 2//7 CONTACT: 2//700-sht R: /L.pdf.1 | |
|--|----------|
| HRG PROJECT I HRG PROJ, CON FILE NAME: 2/1/7 PLOT DRIVER: A | HRGreen. |

HRGreen.com ■Inols Professional Design Firm # 184-001322

| USER NAME = jstrzal | DESIGNED - | JJS | REVISED - |
|----------------------------|------------|-----|-----------|
| | DRAWN - | DMS | REVISED - |
| PLOT SCALE = 20.0075 / in. | CHECKED - | JJS | REVISED - |
| PLOT DATE = 7/10/2023 | DATE - | | REVISED - |
| | | | |

| STATE OF | ILLINOIS |
|---------------|----------------|
| DEPARTMENT OF | TRANSPORTATION |

| CONSTRUCTION DETAILS | F.A. RTE | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|---|---------------------------|----------------|----------|-----------------|--------------|
| RIVERSIDE DRIVE | 156 | 20-00016-00-RS | MCHENRY | 87 | 46 |
| IIIVENSIDE DIIIVE | | | CONTRACT | NO. | 51J68 |
| SCALE N.T.S. SHEET 1 OF 6 SHEETS STA. TO STA. | ILLINOIS FED. AID PROJECT | | | | |



COFFERDAM PROFILE

PLAN VIEW

AREA

PUMP

DISSIPATIN

1. ALL DISCHARGES SHOULD BE ON ENERGY DISSIPATING SURFACES.

2. LOCATIONS FOR THE SUMP PIT, FILTRATION AREA, AND ENERGY DISSIPATING SURFACES MAY VARY DEPENDING ON SITE CONDITIONS.

UNITED STATES ARMY CORPS OF ENGINEERS NOTES:

- 1. EARTHEN COFFERDAMS OR OTHER PRACTICES THAT WOULD RESULT IN A RELEASE OF SEDIMENT INTO WATERS OF THE U.S. ARE NOT AUTHORIZED FOR USE. COFFERDAMS SHALL BE CONSTRUCTED OF NON-ERODIBLE MATERIALS ONLY. ACCEPTABLE PRACTICES INCLUDE, BUT ARE NOT LIMITED TO: PRE-FABRICATED RIGID COFFERDAMS, SHEET PILING, INFLATABLE BLADDERS, SANDBAGS AND FABRIC-LINED BASINS. WORK IN THE WATERWAY SHOULD BE TIMED TO TAKE PLACE DURING LOW ORNO-FLOW CONDITIONS. LOW FLOW CONDITIONS ARE FLOW AT OR BELOW THE NORMAL WATER FLEVATION. CONDITIONS ARE FLOW AT OR BELOW THE NORMALWATER ELEVATION.
- 2. WATER SHALL BE ISOLATED FROM THE IN-STREAM WORK AREA USING ACOFFERDAM CONSTRUCTED OF NON-ERODIBLE MATERIALS (STEEL SHEETS, AQUABARRIERS, RIP RAP AND GEOTEXTILE FABRIC, ETC.). EARTHEN COFFERDAMS ARE NOTPERMISSIBLE.
- 3. WORK MAY NOT BE PERFORMED IN THE WATER, EXCEPT FOR THE PLACEMENT OFTHE MATERIALS NECESSARY FOR THE CONSTRUCTION OF THE COFFERDAM, THECOFFERDAM MUST BE CONSTRUCTED FROM THE UPLAND AREA AND NO EQUIPMENT MAYENTER THE WATER AT ANY TIME. IF THE INSTALLATION OF THE COFFERDAM CANNOTBE COMPLETED FROM SHORE AND ACCESS IS NEEDED TO REACH THE AREA TO BECOFFERED, OTHER MEASURES, SUCH AS THE CONSTRUCTION OF A CAUSEWAY, WILL BENECESSARY TO ENSURE THAT EQUIPMENT DOES NOT ENTER THE WATER. ONCE THECOFFERDAM IS IN PLACE AND THE ISOLATED AREA IS DEWATERED, EQUIPMENT MAYENTER THE COFFERED AREA TO PERFEDDENT THE PEDILIPED WORK. AREA TO PERFORM THE REQUIRED WORK.
- 4. IF BYPASS PUMPING IS NECESSARY, THE INTAKE HOSE SHALL BE PLACED ON ASTABLE SURFACE OR FLOATED TO PREVENT SEDIMENT FROM ENTERING THE HOSE. THE BYPASS DISCHARGE SHALL BE PLACED ON A NON-ERODIBLE, ENERGYDISSIPATING SURFACE PRIOR TO REJOINING THE STREAM FLOW AND SHALL NOTCAUSE EROSION. FILTERING OF BYPASS WATER IS NOT NECESSARY UNLESS THEBYPASS WATER HAS BECOME SEDIMENT-LADEN AS A RESULT OF THE CURRENTCONSTRUCTION ACTIVITIES.
- 5. DURING DEWATERING OF THE COFFERED AREA, ALL WATER MUST BE FILTERED TOREMOVE SEDIMENT. POSSIBLE OPTIONS FOR SEDIMENT REMOVAL INCLUDE BAFFLESYSTEMS, ANIONIC POLYMERS, DEWATERING BAGS, OR OTHER APPROPRIATE METHODS.WATER SHALL HAVE SEDIMENT REMOVED PRIOR TO BEING RE-INTRODUCED TO THEDOWNSTREAM WATERWAY. A STABILIZED CONVENED FOR THE DEWATERING FOR THE WATER TO THE WATER THE CONVEYANCE FROM THE DEWATERINGDEVICE TO THE WATERWAY MUST BE IDENTIFIED. DISCHARGE WATER IS CONSIDEREDCLEAN IF IT DOES NOT RESULT IN A VISUALLY IDENTIFIABLE DEGRADATION OFWATER CLARITY.
- 6. THE PORTION OF THE SIDE SLOPE THAT IS ABOVE THE OBSERVED WATERELEVATION SHALL BE STABILISED AS SPECIFIED IN THE PLANS PRIOR TOACCEPTING FLOWS. THE SUBSTRATE AND TOE OF SLOPE THAT HAS BEEN DISTURBEDDUE TO CONSTRUCTION ACTIVITIES SHALL BE RESTORED TO PRE-CONSTRUCTIONCONDITIONS AND FULLY STABILIZED PRIOR TO ACCEPTING

MCHENRY COUNTY STORMWATER PERMIT REQUIREMENTS

SOIL DISTURBANCE SHALL BE CONDUCTED IN SUCH A MANNER AS TO MINIMIZE EROSION. AREAS OF THE DEVELOPMENT SITE THAT ARE NOT TO BE GRADED SHALL BE PROTECTED FROM CONSTRUCTION TRAFFIC OR OTHER DISTURBANCE UNTIL FINAL SEEDING IS PREFORMED.

SOIL STABILIZATION MEASURES SHALL CONSIDER THE TIME OF YEAR, DEVELOPMENT SITE CONDITIONS AND THE USE OF TEMPORARY OR PERMANENT

STABILIZATION BY SEEDING SHALL INCLUDE TOPSOIL PLACEMENT AND FERTILIZATION, AS NECESSARY.

NATIVE SEED MIXTURES SHALL INCLUDE RAPID-GROWING ANNUAL GRASSES OR SMALL GRAINS TO PROVIDE INITIAL, TEMPORARY SOIL STABILIZATION.

OFFSITE PROPERTY SHALL BE PROTECTED FROM FROSION AND SEDIMENTATION VELOCITY DISSIPATION DEVICES SHALL BE PLACED AT CONCENTRATED DISCHARGE LOCATIONS ALONG THE LENGTH OF ANY OUTFALL CHANNEL, AS NECESSARY TO

SEDIMENT CONTROL MEASURES SHALL BE INSTALLED PRIOR TO THE DISTURBANCE

STABILIZATION OF DISTURBED AREAS SHALL BE INITIATED IMMEDIATELY WHENEVER ANY CLEARING, GRADING, EXCAVATING OR OTHER EARTH DISTURBING ACTIVITIES HAVE PERMANENTLY CEASED ON ANY PORTION OF THE DEVELOPMENT SITE, OR TEMPORARY CEASED ON ANY PORTION OF THE DEVELOPMENT SITE AND WILL NOT RESUME FOR A PERIOD EXCEEDING 14 CALENDAR DAYS. STABILIZATION OF DISTURBED AREAS SHALL BE INITIATED WITHIN 1 WORKING DAY OF PERMANENT OR DISTURBED AREAS SHALL BE INITIATED WITHIN 1 WORKING DAY OF PERMANENT OR TEMPORARY CESSATION OF EARTH DISTURBING ACTIVITIES AND SHALL BE COMPLETED AS SOON AS POSSIBLE, BUT NO LATER THAN 14 CALENDAR DAYS FROM THE INITIATION OF STABLIZATION WORK IN THE AREA. EXCEPTIONS TO THESE TIME FRAMES ARE SPECIFIED AS INSTANCES WHEN THE INITIATION OF STABILIZATION MEASURES IS PRECLUDED BY SNOW COVER, STABILIZATION MEASURES SHALL BE INITIATED AS SOON AS PRACTICABLE AND IN AREAS WHERE CONSTRUCTION ACTIVITY HAS TEMPORARILY CEASED AND WILL RESUME AFTER 14 DAYS, A TEMPORARY STABILIZATION METHOD MAY BE USED.

DISTURBANCE OF STEEPS SLOPES SHALL BE MINIMIZED. AREAS OR EMBANKMENTS HAVING SLOPES STEEPER THAN 3:1 SHALL BE STABILIZED WITH STAKING IN PLACE SOD, EROSION CONTROL BLANKET IN COMBINATION WITH SEEDING, OR EQUIVALENT CONTROL MEASURE.

PERIMETER CONTROL MEASURES SHALL BE PROVIDED DOWNSLOPE AND PERPENDICULAR TO THE FLOW OF RUNOFF FROM DISTURBED AREAS, WHERE THE TRIBUTARY AREA IS GREATER THAN 5,000 SQUARE FEET, AND WHERE RUNOFF WILL FLOW IN A SHEET FLOW MANNER, PERIMETER EROSION CONTROL SHALL ALSO BE PROVIDED AT THE BASE OF SOIL STOCKPILES.

THE DRAINAGE SYSTEM SHALL BE PROTECTED FROM EROSION AND SEDIMENTATION DOWNSLOPE FROM DISTURBED AREAS. INLET PROTECTION THAT REDUCES SEDIMENT LOADING, WHILE ALLOWING RUNOFF TO ENTER THE INLET SHALL BE REQUIRED FOR ALL STORM SEWERS. CHECK DAMS, OR AN EQUIVALENT CONTROL MEASURE, SHALL BE REQUIRED FOR ALL CHANNELS. FILTER FABRIC INLET PROTECTION AND STRAW BALE DITCH CHECKS ARE NOT ACCEPTABLE CONTROL MEASURES

IF DEWATERING SERVICES ARE USED, ADJOINING PROPERTIES AND DISCHARGE LOCATIONS SHALL BE PROTECTED FROM EROSION. DISCHARGES SHALL BE ROUTED THROUGH AN EFFECTIVE SEDIMENT CONTROL MEASURE (E.G., SEDIMENT TRAP, SEDIMENT BASIN, OR OTHER APPROPRIATE MEASURES). THE ENGINEER AND THE MCHENRY COUNTY SOIL AND WATER CONSERVATION DISTRICT SHALL BE NOTIFIED PRIOR TO THE COMMENCEMENT OF DEWATERING ACTIVITIES.

ALL TEMPORARY SOIL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE REMOVED WITHIN THIRTY (30) DAYS AFTER FINAL SITE STABILIZATION IS ACHIEVED OR AFTER THE TEMPORARY MEASURES ARE NO LONGER NEEDED. TRAPPED SEDIMENT AND OTHER DISTURBED SOIL AREAS SHALL BE PERMANENTLY

STOCKPILED SOIL AND MATERIALS SHALL BE REMOVED FROM FLOOD HAZARD AREAS AT THE END OF EACH WORK DAY. SOIL AND MATERIALS STOCKPILED IN IWMC OR BUFFER AREAS SHALL BE PLACED ON TIMBER MATS, OR AN EQUIVALENT CONTROL METALLINE.

EFFECTIVE CONTROL MEASURES SHALL BE UTILIZED TO MINIMIZE THE DISCHARGE OF POLLUTANTS FROM THE DEVELOPMENT SITE. AT A MINIMUM, CONTROL MEASURES SHALL BE IMPLEMENTED IN ORDER TO:

MINIMIZE THE DISCHARGE OF POLLUTANTS FROM EQUIPMENT AND VEHICLE WASHING, WHEEL WASH WATER, AND OTHER WASH WATER.

MINIMIZE THE EXPOSURE OF BUILDING MATERIALS, BUILDING PRODUCTS, CONSTRUCTION WASTES, TRASH, LANDSCAPE MATERIALS, FERTILIZERS, PESTICIDES, HERBICIDES, DETERGENTS, VEHICLE FLUIDS, SANITARY WASTE, AND OTHER MATERIALS PRESENT ON THE DEVELOPMENT SITE TO PRECIPITATION AND TO

ADEQUATE RECEPTACLES SHALL BE PROVIDED FOR THE DEPOSITION OF ALL CONSTRUCTION MATERIAL DEBRIS GENERATED DURING THE DEVELOPMENT PROCESS. THE CONTRACTOR SHALL NOT CAUSE OR PERMIT THE DUMPING, DEPOSITING, DROPPING, THROWING, DISCARDING OR LEAVING OF CONSTRUCTION MATERIAL DEBRIS UPON OR INTO ANY DEVELOPMENT SITE, CHANNEL OR IWMC THE DEVELPMENT SITE SHALL BE MAINTAINED FREE OF CONSTRUCTION MATERIAL

A STABILIZED MAT OF AGGREGATE UNDERLAIN WITH FILTER CLOTH (OR OTHER APPROPRIATE MEASURES) SHALL BE LOCATED AT ANY POINT WHERE TRAFFIC WILL BE ENTERING OR LEAVING A CONSTRUCTION-SITE OF A MAJOR DEVELOPMENT TO OR FROM A PUBLIC RIGHT-OF-WAY, STREET ALLEY, OR PARKING AREA. ANY SEDIMENT OR SOIL REACHING AN IMPROVED PUBLIC RIGHT OF WAY, STREET, ALLEY OR PARKING AREA SHALL BE SCRAPED OR STREET CLEANED AS ACCUMULATIONS WARRANT AND TRANSPORTED TO A CONTROLLED SEDIMENT DISPOSAL AREA.

ALL TEMPORARY AND PERMANENT EROSION AND SEDIMENT CONTROL MEASURES SHALL BE MAINTAINED IN AN EFFECTIVE WORKING CONDITION.

DRAIN TILE SYSTEMS DISTURBED DURING DEVELOPMENT MUST BE RECONNECTED. BY THOSE RESPONSIBLE FOR THEIR DISTURBANCE UNLESS THE APPROVED ENGINEERING PLANS INDICATE HOW THE DRAIN TILE SYSTEM IS TO BE CONNECTED TO THE PROPOSED STORMWATER MANAGEMENT SYSTEM.

ALL ABANDONED DRAIN TILES SHALL BE REMOVED IN THEIR ENTIRETY WITHIN THE EXISTING ROW AND/OR EASEMENT.

DRAIN TILES WITHIN THE DISTURBED AREA OF THE DEVELOPMENT SHALL BE REPLACED, BYPASSED AROUND THE DEVELOPMENT OR INTERCEPTED AND CONNECTED TO THE DRAINAGE SYSTEM FOR THE DEVELOPMENT. THE SIZE OF THE REPLACED OR BYPASSED DRAIN TILE SHALL BE EQUIVALENT TO THE EXISTING


SCALE: N.T.S.


HRGreen.com **HRGreen**


| USER NAME = jstrzal | DESIGNED - JJS | REVISED - |
|---------------------------|----------------|-----------|
| | DRAWN - DMS | REVISED - |
| PLOT SCALE = 8.0000 / in. | CHECKED - JJS | REVISED - |
| PLOT DATE = 7/10/2023 | DATE - | REVISED - |
| | | |

STATE OF ILLINOIS **DEPARTMENT OF TRANSPORTATION**

| | CONSTRUCTION DETAILS | | | | | | | F.A. RTE | SEC. | SECTION | | TOTAL SHEETS | | |
|-----------------|----------------------|----|---|--------|------|----|------|-------------|---------|--------------|----------------|-----------------|-------|--|
| RIVERSIDE DRIVE | | | | | | | | 156 | 20-0001 | 6-00-RS | MCHENRY | 87 | 47 | |
| | NIVENSIDE DNIVE | | | | | | | • 400 | 3, 4004 | | CONTRACT | NO. | 61J68 | |
| HEET | 2 | OF | 6 | SHEETS | STA. | TO | STA. | | | ILLINOIS FEE | D. AID PROJECT | | | |










Checked Approved SHEET 1 OF 1

DATE 08-2-2019

SCALE: N.T.S.










HRGreen.com
#Indis Professional Design Firm
#184-001322

| USER NAME = jstrzal | DESIGNED - JJS | REVISED - |
|---------------------------|----------------|-----------|
| | DRAWN - DMS | REVISED - |
| PLOT SCALE = 8.0000 / in. | CHECKED - JJS | REVISED - |
| PLOT DATE = 7/10/2023 | DATE - | REVISED - |
| | | |

| | CONSTRUCTION DETAILS | | | | | | | | | F.A. RTE | SECT | ПОИ | ON COUNTY | | TOTAL SHEETS | SHEET NO. |
|---|----------------------|-------|---|-----|------|---------|------|----|------|-------------|---------------------------|-----|-----------|----------|-----------------|--------------|
| | RIVERSIDE DRIVE | | | | | | | | | 156 | 56 20-00016-00-RS | | | MCHENRY | 87 | 49 |
| | | | | 111 | VLII | SIDL DI | IIVL | | | | | | | CONTRACT | NO. | 61J68 |
| ı | SCALE: N.T.S. | SHEET | 4 | OF | 6 | SHEETS | STA. | TO | STA. | | ILLINOIS FED. AID PROJECT | | | | | |









HRGreen.

HRGreen.com


| USER NAME = jstrzal | DESIGNED - JJS | REVISED - |
|---------------------------|----------------|-----------|
| | DRAWN - DMS | REVISED - |
| PLOT SCALE = 8.0000 / in. | CHECKED - JJS | REVISED - |
| PLOT DATE = 7/10/2023 | DATE - | REVISED - |
| | | |

STATE OF ILLINOIS **DEPARTMENT OF TRANSPORTATION**

SCALE: N.T.S.

SHEET 5

| CONSTRUCTION DETAILS RIVERSIDE DRIVE | | | | | | SECT | ION | | COUNTY | TOTAL SHEETS | SHEET NO. |
|--------------------------------------|----------|-------|----|------|--|----------|------------|----------|---------|-----------------|--------------|
| | | | | | | 20-00016 | -00-RS | | MCHENRY | 87 | 50 |
| IIIVLI | ISIDE DI | IIV L | | | | | | CONTRACT | NO. | 61J68 | |
| OF 6 | SHEETS | STA. | TO | STA. | | | ID PROJECT | | | | |



NOTES:

- CONTAINMENT MUST BE STRUCTURALLY SOUND
 AND LEAK FREE AND CONTAIN ALL LIQUID WASTES.
- 2. CONTAINMENT DEVICES MUST BE OF SUFFICIENT QUANTITY OR VOLUME TO COMPLETELY CONTAIN THE LIQUID WASTES GENERATED.
- 3. WASHOUT MUST BE CLEANED OR NEW FACILITIES CONSTRUCTED AND READY TO USE ONCE WASHOUT IS 75% FULL.
- 4. WASHOUT AREA(S) SHALL BE INSTALLED IN A LOCATION EASILY ACCESSIBLE BY CONCRETE TRUCKS.
- 5. ONE OR MORE AREAS MAY BE INSTALLED ON THE CONSTRUCTION SITE AND MAY BE RELOCATED AS CONSTRUCTION PROGRESSES.
- 6. AT LEAST WEEKLY REMOVE ACCUMULATION OF SAND AND AGGREGATE AND DISPOSE OF PROPERLY.

TYPICAL SECTION


| HRGreen. | HRGreen.com Illinois Professional Design Firn # 184-001322 |
|----------|--|

| USER NAME = jstrzal | DESIGNED - | JJS | REVISED - |
|-----------------------------|------------|-----|-----------|
| | DRAWN - | DMS | REVISED - |
| PLOT SCALE = 8.0000 ' / in. | CHECKED - | JJS | REVISED - |
| PLOT DATE = 7/10/2023 | DATE - | | REVISED - |
| | | | |

| STATE | : OF | ILLINOIS | |
|------------|------|-----------------------|---|
| DEPARTMENT | 0F | TRANSPORTATION | ı |

| | | | | | | F.A. RTE | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|--|--|--|--|--|--|---------------|----------------|----------|-----------------|--------------|
| RIVERSIDE DRIVE | | | | | | 156 | 20-00016-00-RS | MCHENRY | 87 | 51 |
| NIVENSIDE DNIVE | | | | | | | | CONTRACT | NO. | 61J68 |
| SCALE: N.T.S. SHEET 6 OF 6 SHEETS STA. TO STA. | | | | | | ILLINOIS FED. | AID PROJECT | | | |

HRG PROJECT NO., 20/700 HRG PROJ. CONTACT: FILE NAME: 21/700-5n1-de104-eros.dgn PLOT DRIVER: IL.-Ddf., bw.p1/cfg



HRGreen

DRAWN - WJH REVISED PLOT DATE = 7/18/2023 CHECKED - AEU REVISED

DEPARTMENT OF TRANSPORTATION

MCHENRY 87 52 CONTRACT NO. 61J68

SHEET NO. 1 OF 11 SHEETS

GENERAL NOTES

- Layout of the slope protection system may be varied to suit ground conditions in the field as directed by the Engineer.
- 2. Precast Concrete alternate is not allowed.
- 3. Per Article 502.13 of the Standard Specifications, excavation for structures shall be considered included in the contract unit price for Concrete Box Culverts.

TOTAL BILL OF MATERIAL

| <u>ITEM</u> | UNIT | TOTAL |
|---|---------|--------|
| Porous Granular Embankment | Cu. Yd. | 74 |
| Stone Riprap, Class A4 | Sq. Yd. | 44 |
| Filter Fabric | Sq. Yd. | 45 |
| Pipe Culvert Removal | Foot | 114 |
| Removal and Disposal of Unsuitable Material | Cu. Yd. | 189 |
| Reinforcement Bars | Pound | 39,000 |
| Bicycle Railing | Foot | 31 |
| Name Plates | Each | 1 |
| Concrete Box Culverts | Cu. Yd. | 210 |
| Geocomposite Wall Drain | Sq. Yd. | 216 |
| Membrane Waterproofing System for Buried Structures | Sq. Yd. | 216 |
| Temporary Bypass Pumping System | L. Sum | 1 |
| Controlled Stiffness Columns | L. Sum | 1 |


INDEX OF SHEETS

- 1 General Plan and Elevation
- 2 General Data
- 3 Culvert Details Bottom Slab
- 4 Culvert Details Plan
- 5 Wall Elevation
- 6 Wingwall Details
- 7 Intentionally Left Blank
- 8 Culvert Details
- 9 Bicycle Railing Details
- 10 Soil Boring Log

DUTCH CREEK
BUILT BY
VILLAGE OF JOHNSBURG
SEC. 20-00016-00-RS
F.A.U. RTE. 156 STA. 40+92.48
STR. NO. 056-6019 LOADING HL-93

NAME PLATE
See Std. 515001

#4 bars = 1'-9" #5 bars = 2'-2"



Note:

Bars indicated thus 7x2-#4 etc. indicates 7 lines of #4 bars with 2 lengths per line.

| HRG PROJECT NO.: 2/1700 HRG PROJ. CONTACT: FILE NAME: 056-60/9-xxx-003 PLOT DRIVER: (L.pdf.bw.p/fcff | |
|--|----------|
| HRG PROJECT NO. 21/700 HRG PROJ. CONTACT: FILE NAME: 056-60/9-xxx PLOT DRIVER: IL_pdf_bw. PEN TABLE: plot/dcbe/tbi | HRGreen. |

HRGreen.com ■Inols Professional Design Firm # 184-001322


| USER NAME = jstrzal | DESIGNED - | RAT | REVISED | - | XX/XX/XXXX |
|-----------------------|------------|-----|---------|---|------------|
| | CHECKED - | SLS | REVISED | - | XX/XX/XXXX |
| PLOT SCALE = | DRAWN - | WJH | REVISED | - | XX/XX/XXXX |
| PLOT DATE = 7/10/2023 | CHECKED - | AEU | REVISED | - | XX/XX/XXXX |

| STATE | OF | ILLINOIS |
|------------|----|----------------|
| DEPARTMENT | 0F | TRANSPORTATION |

| CULVERT DETAILS — BOTTOM SLAB | |
|-------------------------------|---|
| STRUCTURE NO. 056-6019 | |
| SHEET NO 3 OF 11 SHEETS | _ |

| F.A.U. RTE. | SECTION | | COUNTY | TOTAL SHEETS | SHEE NO. |
|----------------|----------------|--------|-----------|-----------------|-------------|
| 156 | 20-00016-00-RS | | MCHENRY | 87 | 54 |
| | | | CONTRACT | NO. | 61J68 |
| | ILLINOIS | FFD ΔI | D PROJECT | | |

#4 bars = 1'-9" #5 bars = 2'-2"



Note:

Bars indicated thus 7x2-#4 etc. indicates 7 lines of #4 bars with 2 lengths per line.

| HRGreen. | HR(■Inols # 184 |
|----------|------------------------|

HRGreen.com


Inols Professional Design Firs
184-001322

| USER NAME = jstrzal | DESIGNED - | RAT | REVISED | - | XX/XX/XXXX |
|-----------------------|------------|-----|---------|---|------------|
| | CHECKED - | SLS | REVISED | - | XX/XX/XXXX |
| PLOT SCALE = | DRAWN - | WJH | REVISED | - | XX/XX/XXXX |
| PLOT DATE = 7/10/2023 | CHECKED - | AEU | REVISED | - | XX/XX/XXXX |

| STATI | E OI | F ILLINOIS |
|------------|------|----------------|
| DEPARTMENT | OF | TRANSPORTATION |

| CULVERT DETAILS - TOP SLAB | F.A.U. RTE | |
|----------------------------|---------------|---|
| STRUCTURE NO. 056-6019 | 156 | |
| 3111001011L NO. 030-0013 | | |
| SHEET NO. 4 OF 11 SHEETS | | _ |

| A.U. | SECT | ION | | COUNTY | TOTAL SHEETS | SHEET NO. |
|------|---------|----------|---------|-----------|-----------------|--------------|
| 156 | 20-0001 | 6-00-RS | | MCHENRY | 87 | 55 |
| | | | | CONTRACT | NO. | 61J68 |
| | | ILLINOIS | FFD. Al | D PROJECT | | |



Notes:

Bars indicated thus 7x2-#4 etc. indicates 7 lines of #4 bars with 2 lengths per line. At the Contractor's option, a longer v1 bar may be ordered to replace the v bar. No reduction in quantities shall be made for this substitution.




HRGreen.com


Inols Professional Design Firm
184-001322

| USER NAME = jstrzal | DESIGNED - RAT | REVISED - XX/XX/XXXX |
|-----------------------|----------------|----------------------|
| | CHECKED - SLS | REVISED - XX/XX/XXXX |
| PLOT SCALE = | DRAWN - WJH | REVISED - XX/XX/XXXX |
| PLOT DATE = 7/10/2023 | CHECKED - AEU | REVISED - XX/XX/XXXX |

| STATE OF ILLINOIS | |
|------------------------------|--|
| DEPARTMENT OF TRANSPORTATION | |

| WALL DETAILS STRUCTURE NO. 056-6019 | F.A.U. RTE | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|--|---------------|----------------|-------------|-----------------|--------------|
| | 156 | 20-00016-00-RS | MCHENRY | 87 | 56 |
| | | | CONTRAC | T NO. | 61J68 |
| SHEET NO. 5 OF 11 SHEETS | | ILLINOIS EED | AID PROJECT | | |





SECTION A-A

SECTION B-B

Note:

East ingwalls shown. West wingwalls similar.

A distance of half the length of the wingwall but not less than six feet of the barrel shall be poured monolithically with the wingwalls.

Bars indicated thus 12x4-#5 etc. indicates 12 lines of #5 bars with 4 lengths per line. At the Contractor's option, a longer v1 bar may be ordered to replace the v bar. No reduction in quantities shall be made for this substitution.

| | Green.com Professional Des 001322 |
|--|---|
|--|---|

USER NAME - jstrzal DESIGNED - RAT REVISED -CHECKED - SLS REVISED -DRAWN - WJH REVISED PLOT DATE = 7/10/2023 CHECKED - AEU REVISED -

STATE OF ILLINOIS

WINGWALL DETAILS **STRUCTURE NO. 056-6019** SHEET NO. 6 OF 11 SHEETS

COUNTY TOTAL SHEET NO.

MCHENRY 87 57 SECTION 156 20-00016-00-RS CONTRACT NO. 61J68

XX/XX/XXXX

XX/XX/XXXX

XX/XX/XXXX

THIS SHEET INTENTIONALLY LEFT BLANK

PEN TABLE: plotlabel.tbl

HRGreen.com
Indos Professional Design Firm
#184-001322

 USER NAME - jstrzál
 DESIGNED

 CHECKED CHECKED


 PLOT SCALE = DRAWN

 PLOT DATE = 7/10/2023
 CHECKED


STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION

SHEET NO. 7 OF 11 SHEETS


*Nonwoven geotextile fabric shall conform to the requirements of Article 1080.01 of the Standard Specifications. The minimum weight of the fabric shall be 6 ounces per square yard




(All costs associated with furnishing and constructing the above drain detail will not be measured for payment but shall be included in the contract unit price for the associated work.)




LONGITUDINAL SECTION




PHOEBE NESTING SITE DETAILS (Downstream End Only)



SECTION THRU HEADWALL







SECTION THRU TOEWALL

BILL OF MATERIAL

| | | | | _ |
|---------|----------|----------|------------------|----------|
| Bar | No. | Size | Length | Shape |
| a1 | 164 | #7 | 34'- 0" | |
| a2 | 164 | #7 | 32'- 4" | |
| | | | | |
| d | 64 | #4 | 4'- 5" | |
| | | | | |
| h | 132 | #5 | 28'- 3" | |
| h1 | 132 | #4 | 28'- 3" | |
| h2 | 64 | #4 | 28'- 3" | |
| h3 | 30 | #8 | 8'- 0" | |
| h4 | 4 | #7 | 32'- 5" | |
| h5 | 6 | #5 | 32'- 5" | |
| h6 | 28 | #8 | 15'- 10" | |
| h7 | 30 | #8 | 8'- 0" | <u></u> |
| h8 | 28 | #8 | 14'- 10" | <u> </u> |
| h9 | 8 | #6 | 32'- 5" | |
| | | | | |
| 5 | 32 32 | #4 | 5'- 9" 8'- 2" | ľ |
| s 1 | 32 | #4 | 8'- 2" | ŋ |
| | | | | |
| V | 332 | #5 | 7'- 2" | |
| v 1 | 332 | #5 | 4'- 6" | |
| v3 | 12 12 | #4 | 11'- 8" | |
| v 4 | 12 | #4 | 15'- 2" | |
| | | | | |
| Concret | е Вох (| Culverts | Cu. Yd. | 210 |
| Reinfor | cement | Bars | Pound | 39,000 |
| · | · | | | |

SECTION THRU BARREL





BAR s

BAR s1


HRGreen.com HRGreen

| USER NAME - jstrzal | DESIGNED - | RAT | REVISED | - |
|-----------------------|------------|-----|---------|---|
| | CHECKED - | SLS | REVISED | - |
| PLOT SCALE = | DRAWN - | WJH | REVISED | - |
| PLOT DATE = 7/10/2023 | CHECKED - | AEU | REVISED | - |
| | | | | |

STATE OF ILLINOIS **DEPARTMENT OF TRANSPORTATION**

| CULVERT DETAILS STRUCTURE NO. 056–6019 |
|---|
| SHEET NO. 8 OF 11 SHEETS |

| F.A.U. RTE | SECTION | | | COUNTY | TOTAL SHEETS | SHEE NO. |
|---------------|----------------|-----|----|------------|-----------------|----------|
| 156 | 20-00016-00-RS | | | MCHENRY | 87 | 59 |
| | | | | CONTRACT | NO. | 61J68 |
| | ILLINOIS | EED | ΛΙ | ID PROJECT | | |



SECTION A-A

i O i

— Top of Headwall

Railing frame and attachment brackets shall be powder coated black after fabrication.

Attachment bolts and nuts shall be painted black after installation.


Cost included in unit price of Bicycle Railing.

RAILING CRITERIA

| Bicycle Railing Weight (plf) | 50 |
|------------------------------|--------|
| Max Post Spacing | 10'-0" |

BILL OF MATERIAL

| Item | Unit | Quantity |
|-----------------|------|----------|
| Bicycle Railing | Foot | 31 |



HRGreen.com HRGreen

| USER NAME - jstrzal | DESIGNED - RAT | REVISED - X | X/XX/XXXX |
|-----------------------|----------------|-------------|-----------|
| | CHECKED - SLS | REVISED - X | X/XX/XXXX |
| PLOT SCALE = | DRAWN - WJH | REVISED - X | X/XX/XXXX |
| PLOT DATE = 7/10/2023 | CHECKED - AEU | REVISED - X | X/XX/XXXX |

STATE OF ILLINOIS **DEPARTMENT OF TRANSPORTATION**

| BICYCLE RAILING DETAILS STRUCTURE NO. 056–6019 | - |
|---|---|
| SHEET NO. 9 OF 11 SHEETS | _ |

| 4.U. ΓΕ. | | | | COUNTY | TOTAL SHEETS | SHEET NO. |
|-------------|----------------|----------|----------|-----------|-----------------|--------------|
| 56 | 20-00016-00-RS | | | MCHENRY | 87 | 60 |
| | | | CONTRACT | NO. | 61J68 | |
| | | ILLINOIS | FED. A | D PROJECT | | |

| PROJECT: | T NO.: 22570 LOG OF BOR Riverside Drive - Culvert | | | | | N· | | Johnsbu | age 1 of 2 |
|---------------------------------------|--|----------------|-------|------|--------------------------|-------|-------------------------|--|-------------|
| BORING LOC | | | | | | money | | ge of John | |
| T T | SD Lane, North of Chivert | _ | | AMPL | | | | STS | sburg |
| SOIL TYPE | Material Description | Elevation | TYPE/ | NO. | N-VALUE Blows per ft. | Wc% | Dry Unit Weight, pof | Unconfined Compressive Strength, tsf | REMARKS |
| 0 | (0.100) | 746.1 | | | | | | | |
| | FILL DIOWIT CITY LONIN, A-0 IIIII | 745.7 744.6 | SS | 1A | 10 | 8 | 121 | 0.78 | |
| 18888 | FILL: Brown SAND, A-3, medium dense | 744.0 | | 1B | 16 | 5 | | | |
| 4- | Probable FiLL: Brown SAND, A-2 to 7 A-3, slightly dense to very loose | 743.1 | ss | 2 | 8 | 5 | | | |
| | | | ss | 3 | 1 | 17 | | | |
| 8- | Z | | | | | | | | |
| | with Gravel | | SS | 4 | 1 | 21 | | | |
| 12 – 12 | Brown Grey Sandy LOAM, with shells A-1-b, very loose | 735.6 | ss | 5 | 1 | 19 | | | |
| | | | SS | 6 | 4 | | | | No Recovery |
| 16 - 6 6 6 | Dark Grey Organic Sandy LOAM, 7 with shells, A-2-4, very loose | 730.6 | SS | 7 | 3 | 72 | | | |
| 20 - 7 7 | | | SS | 8 | 0 | 42 | | | |
| 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 | Grey Organic SILT with shells, A-8, 7 very loose | 25.6 | SS | 9 | 0 | 65 | | | |
| 24 | Grey SAND, A-3, medium dense 7 | 22.6 | ss | 10 | 20 | 19 | | | |
| 28 | _ confirmed - | | ss | 11 | 16 | 25 | | | |

| PROJE | CT: | Riverside Drive - Culvert | | SITE | LOC | ATIO | N: _ | | Johnsbur | rg, IL |
|-----------------|------------------------------------|---|-----------|-------------------|------|--------------------------|------|-------------------------|--|--------------------------|
| BORIN | G LOCA | TION: SB Lane, North of Culver | t | CLIE | NT: | | | Villa | ge of Johns | burg |
| | | | - | | AMPL | | | | STS | |
| DEPTH (feet) | SOIL | Material Description | Elevation | TYPE/ INTERVAL | NO. | N-VALUE Blows per ft. | Wc% | Dry Unit Weight, pcf | Unconfined Compressive Strength, 1sf | REMARKS |
| 32 - | | Grey SAND, A-2 to A-3, medium dense | | | | | | | | |
| 36 - | | | | SS | 12 | 10 | 25 | | | |
| 30 | | Grey SAND with Silt, A-2-4 to A-3 | 709.6 | | | | | | | |
| 40 - | | | | SS | 13 | 6 | 23 | | | |
| 9 | | | | | | | | | | |
| 44 - | | | | SS | 14 | 10 | 21 | | | |
| 1 | PARTY PARTY PARTY REFEREN | | | _ | | | | | | |
| | 96961411 17721772 43394113 | End of Boring at 50 Feet | 696.1 | SS | 15 | 6 | 21 | | | |
| | | | | | | | | | | |
| DURING | DRILLING | BSERVATIONS, ft. 3: \$\forall 8.5'\$ FTER DRILLING: \$\forall Dry\$ | ERO. | use: | | Т | BO | | TARTED: | 12/2/22 12/2/22 BB |

Page 2 of 2

MSET PROJECT NO.: 22570 LOG OF BORING NO. SB-1

| | | No.: 22570 LOG OF BORII Riverside Drive - Culvert | | | | | | | Johnsbur | ge 1 of 1 |
|--------|----------|---|-----------|-------------------|------|--------------------------|-----|-------------------------|--|--------------------------|
| | 05080 | | | | | | | 100 2000000 | | |
| OKIN | LUCA | TION: NB Lane, South of Culvert | - (| | | | | | ge of Johnsl | ourg |
| | | | <u> </u> | | AMPL | 77 | | | STS | |
| (feet) | SOIL | Material Description | Elevation | TYPE/ INTERVAL | NO. | N-VALUE Blows per ft. | Wc% | Dry Unit Weight, pof | Unconfined Compressive Strength, 1sf | REMARKS |
| 0 | | Pavement: 8" Bituminous Concrete 74 over 12" Granular Base Course | 4.5 | | 100 | | | | | |
| 78 | | FILL: Brown SAND with Gravel, A-1- 74 b, slightly dense to very loose | 2.8- | SS | 1 | 7 | 8 | | | |
| 4 - | ÷ | | | SS | 2 | 3 | 10 | | | |
| 150 | | | | SS | 3 | 2 | 16 | | | |
| 8- | | Brown Sandy LOAM, little Gravel, with shells, A-2-4, loose to very loose | 6.5 | ss | 4 | 4 | 19 | | | |
| 12 - | | to Grey | | ss | 5 | 1 | 15 | | | |
| | | Black & Grey to Grey Organic Sandy 73 LOAM, with shells, A-2-4 to A-8, very loose | | SS | 6 | wон | 152 | | | |
| 16- | | to Grey | | ss | 7 | wон | 117 | | | |
| 20- | | | | ss | 8 | wон | 86 | | | |
| | | Brown SAND, little Clay, A-2-6 to A- 72- 2, slightly to medium dense | - | SS | 9 | 8 | 41 | | | |
| 24- | | | | ss | 10 | 12 | 18 | | | |
| | | | | ss | 11 | 10 | 17 | | | |
| 28 - | | | - | - | 10 | ** | 15 | | | |
| | | End of Boring at 30 Feet 714 | - 1 | SS | 12 | 13 | 15 | | | |
| RING | DRILLING | ISERVATIONS, ft. 1: \$\forall 3.5'\$ TER DRILLING: \$\forall 5.4'\$ GAFTER GAFTER |),, | SET | г | | BOF | | TARTED: OMPLETED: SY: | 10/7/22 10/7/22 BB |


| Midfand Standard Engineering & | Tassing inc | 410 Nales Daire | Parish Phylip IIII - in CO177 | 10471 044 1005 | ((0.27) 0.44 0.07F |
|--------------------------------|-------------|-----------------|-------------------------------|----------------|--------------------|

| HRGreen» | HRGree |
|----------|--------|

| USER NAME - jstrzal | DESIGNED - | RAT | REVISED | - | XX/XX/XXXX |
|-----------------------|------------|-----|---------|---|------------|
| | CHECKED - | SLS | REVISED | - | XX/XX/XXXX |
| PLOT SCALE = | DRAWN - | WJH | REVISED | - | XX/XX/XXXX |
| PLOT DATE = 7/10/2023 | CHECKED - | AEU | REVISED | - | XX/XX/XXXX |

| STATE OF ILLI | INOIS |
|--------------------|-------------|
| DEPARTMENT OF TRAI | NSPORTATION |

| SOIL BORING LOGS | | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. | |
|---------------------------|-----|----------------|----------|-----------------|--------------|-------|
| STRUCTURE NO. 056-6019 | 156 | 20-00016-00-RS | | MCHENRY | 87 | 61 |
| | | | | CONTRACT | NO. | 61J68 |
| SHEET NO. 10 OF 11 SHEETS | | ILLINOIS | FED. AII | D PROJECT | | |
| | | | | | | |



LOT SCALE = 20.0000 ' / in. REVISED -PLOT DATE = 7/10/2023 REVISED -

DEPARTMENT OF TRANSPORTATION

SCALE: 1"=10' SHEET 11 OF 11 SHEETS STA.

TO STA.

CONTRACT NO. 61J68

