09-22-2023 LETTING ITEM 033

0

0

0

0

FOR INDEX OF SHEETS, SEE SHEET NO. 2

STATE OF ILLINOIS

DEPARTMENT OF TRANSPORTATION

IO DAVIESS	STEPHENSON	WINNEBAGO	BOONE	MC HENRY	LAKE
CAR	POLL	OGLE		7	$\overline{}$
WHITES	IDE IDE	LEE	DE KALE	KANE D	U PAGE COOK

(140 142)CLV

KNOX 38 1

CONTRACT NO. 68G66

PROPOSED HIGHWAY PLANS

FAP 665 (IL 116) **SECTION** (140,142)CLV **CONTRACT MAINTENANCE CULVERT REPAIRS KNOX COUNTY**

C-94-090-21

IL 116 STA. 117 + 12

DESIGN DESIGNATION

HIGHWAY STANDARDS

001001-02 701001-02

280001-07 701006-05 442201-03 701201-05 515001-04 701311-03 630001-12 701321-18

630101-10 701901-08 630106-02 704001-08

630301-09 780001-05 631011-10 782006-01


DOUBLE 4x4 CULVERT LOCATION MINOR ARTERIAL

ADT: 1,100 (2021) MU: 12.7% SU: 10.0%

10x7 CULVERT LOCATION

MINOR ARTERIAL ADT: 1,350 (2021) MU: 6.67% SU: 6.67%

> IL 116 STA. 1451 + 20 (SN 048-1005) 4' X 4' DOUBLÉ BOX CULVERT




FULL SIZE PLANS HAVE BEEN PREPARED USING STANDARD ENGINEERING SCALES. REDUCED SIZED PLANS WILL NOT CONFORM TO STANDARD SCALES. IN MAKING MEASUREMENTS ON REDUCED PLANS, THE ABOVE SCALES MAY BE USED.

JOINT UTILITY LOCATION INFORMATION FOR EXCAVATORS 1-800-892-0123 OR 811

PROJECT ENGINEER: NICOLE FAYANT (309) 671-3454 PROJECT MANAGER: DAVID GREEN (309) 671-3475

CATALOG NO. 036253-00D CONTRACT NO. 68G66



NET LENGTH = 0.16 MILES

POP: 152


LOCATION OF SECTION INDICATED THUS: - -

PROJECT DESCRIPTION:

CULVERT REPAIRS ON 2 BOX CULVERTS CROSSING IL 116 IN

0.49 MILE EAST OF WARREN COUNTY LINE: EXTEND CULVERT TO CLEAR ZONE AND REMOVE GUARDRAIL OF DOUBLE 4'X4' BOX

0.15 MILE EAST OF 325TH STREET: REPLACE WINGWALLS. HEADWALLS, AND GUARDRAIL OF 10'X7' BOX



PRINTED BY THE AUTHORITY OF THE STATE OF ILLINOIS

INDEX OF SHEETS

- **COVER SHEET**
- INDEX OF SHEETS, GENERAL NOTES AND STATUS OF UTILITIES
- SUMMARY OF QUANTITIES 3–7.
- 8-9. SCHEDULE OF QUANTITIES
- LINE DIAGRAM
- 11. TYPCIALS SECTIONS
- 12. REMOVAL PLAN
- 13. PROPOSED PLAN
- **EROSION CONTROL PLAN** 14.
- 15. **GUARDRAIL PLAN**
- 16–19. STAGING DETAILS
- 20-27. 4x4 BOX CULVERT DETAILS
- 28-34. 10x7 BOX CULVERT DETAILS
- 35-38. DISTRICT CADD STANDARDS

GENERAL NOTES

COMMITMENTS

Commitments are not to be altered without the written approval of all parties to which the commitment was made,

No commitments have been made on this contract,

ENVIRONMENTAL REVIEWS

Prior to the use of any proposed borrow areas, use areas (temporary access roads, detours, run-arounds, etc.) and/or waste areas, the Contractor shall file the required environmental resource request surveys according to Section 107.22 of the Standard Specifications. These surveys are required in order for the Department to conduct cultural and biological resource surveys for the proposed site.

The required environmental resource documentation shall include the following:

- BDE Form 2289 (Borrow Site Review)
- BDE Form 2290 (Waste/Use Area Review)
- A location map showing the size limits and location of the use area
- Color photographs depicting the use area
- Borrow Area Entry Agreement form D4 PI0101

Prior to any waste materials being removed from the construction site the required environmental resource surveys shall be obtained and filed by the Contractor. Excess waste products removed from the construction site shall be disposed of as required in Section 202.03 of the Standard Specifications.

Any protruding metal bars shall be removed prior to the disposal of broken concrete at approved disposal sites.

Please note that a minimum of four weeks shall be allowed for the District to obtain the required waste site environmental clearances and six weeks for the required borrow site environmental clearances.

POLYMERIZED BITUMINOUS MATERIALS (TACK COAT) RATES

Surface Type	Residual Rate
Milled (HMA or PCC)	0.08 lb /sq ft
Existing Pavement	0.08 lb /sq ft
Fog Coat (between lifts)	0.08 lb /sq ft

ORDERING LENGTH CONFIRMATION - DRAINAGE ITEMS

JSER NAME = \$USER\$

PLOT SCALE = 1:100

PLOT DATE = 7/7/2023

The Contractor shall consult with the Engineer in regard to the exact length of the box/pipe culverts, storm sewers, and/or pipe drains required prior to ordering these items.

DESIGNED -

DRAWN

DATE

CHECKED

REVISED

REVISED

REVISED

REVISED

HOT-MIX ASPHALT MIXTURE REQUIREMENTS

Location(s):	Mainline	Mainline
Mixture Use(s):	Surface 2"	Lower Lifts
AC/PG:	PG 58-28	PG 58-28
Design Air Voids:	4.0% @ N=50	4.0% @ N=50
Mixture Composition: (Mixture Gradation)	IL 9.5	IL 19.0
Friction Aggregate:	Mix D	N.A.
Quality Management Program:	QCQA	QCQA
MTD:	No	No

1) Individual lift thickness of each mix type will be no less than 3 times nominal maximum aggregate size and no more than 6 times nominal maximum aggregate size, unless otherwise approved by the

2) For design purposes, mixture weight for all mixes is determined to be 112.0 lb/s,y/in., unless otherwise

3) Sublot size for PFP and QCP mixes will be 600 tons, unless otherwise agreed to by the Engineer and the paving contractor.

p	partment ortation			Status of Utilitie
ility Company		Sec Cou Cor	tion unty ntract No.	FAP 665 (IL 116) (140, 142)CLV Knox 68G66 036253-00D
Offset	Location	Type of Utility	Type of Conflict	Disposition
Rt 58'	Sta 117+46	Fiber optic	Rip Rap	TBD - Utility investigating
	<u> </u>			
+				
4				
+	- 			
+				
	-			
+				
	- 			
	Offset	Offset Location	Sec Cot Cot Cot Cat Offset Location Type of Utility	Section County Contract No. Catalog No. Offset Location Type of Utility Type of Conflict

STATE OF ILLINOIS **DEPARTMENT OF TRANSPORTATION** INDEX OF SHEETS, GENERAL NOTES AND STATUS OF UTILITIES

TO STA.

SHEET 1 OF 1 SHEETS STA.

SECTION COUNTY (140,142)CLV 665 KNOX 38 2 CONTRACT NO. 68G66

USER NAME = \$USER\$	DESIGNED -	REVISED -
	DRAWN -	REVISED -
PLOT SCALE = 1:100	CHECKED -	REVISED -
PLOT DATE = 7/7/2023	DATE -	REVISED -

STATE OF	ILLINOIS
DEPARTMENT OF	TRANSPORTATION

SCALE:

							F.A.P. RTE	SEC ⁻	TION	
SUMMARY OF QUANTITIES						665	(140,1	42)CLV		
SHEET	1	OF	5	SHEETS	STA.	TO STA.			ILLINOIS	FED.

CONSTRUCTION CODE

				CONSTRUC	ION CODE	
				100% STATE	100% STATE	
	T			KNOX COUNTY	KNOX COUNTY	
CODE			TOTAL	BOX CULVERT	BOX CULVERT 0004	
NO.	ITEM	UNIT		S.N. 048-1005		
NO.	1120	ONTT	QUANTITI	3.N. 040-1003	3.N. 040-1000	
28100109	STONE RIPRAP, CLASS A5	SQ YD	256	163	93	
28200200	FILTER FABRIC	SQ YD	323	163	160	
35101100	AGGREGATE BASE COURSE, TYPE A 12"	SQ YD	187	95	92	
40800025	BITUMINOUS MATERIALS (PRIME COAT)	POUND	420	213	207	
40800029	BITUMINOUS MATERIALS (TACK COAT)	POUND	135	68	67	
44201821	CLASS D PATCHES, TYPE IV, 14 INCH	SQ YD	187	95	92	
48100200	AGGREGATE SHOULDERS, TYPE A	CU YD	25	0	25	
50102400	CONCRETE REMOVAL	CU YD	75.1	13.7	61.4	
50800105	REINFORCEMENT BARS	POUND	530	240	290	
51500100	NAME PLATES	EACH	2	1	1	
52200020	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	682	207	475	
54001001	BOX CULVERT END SECTIONS, CULVERT NO. 1	EACH	2	2	0	
54001002	BOX CULVERT END SECTIONS, CULVERT NO. 2	EACH	2	0	2	
54003000	CONCRETE BOX CULVERTS	CU YD	6 . 1	2.6	3.5	

ME: pw:\\ildot.pw.bentley.com:PWIDOT\Documents\IDOT Offices\District 4\Projects\D4_68G66\C\

 USER NAME
 = \$USER\$
 DESIGNED
 REVISED

 DRAWN
 REVISED

 PLOT SCALE
 = 1:100
 CHECKED
 REVISED

 PLOT DATE
 = 7/7/2023
 DATE
 REVISED

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

 SUMMARY OF QUANTITIES
 F.A.P. RTE. G65
 SECTION G65

 SCALE:
 SHEET 2
 OF 5
 SHEETS
 STA.
 TO STA.
 ILLINOIS

 USER NAME
 = \$USER\$
 DESIGNED REVISED

 DRAWN REVISED

 PLOT SCALE
 = 1:100
 CHECKED REVISED

 PLOT DATE
 = 7/7/2023
 DATE REVISED

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

| SHEET 3 OF 5 SHEETS STA. TO STA. |

CONSTRUCTION CODE

ault	
MODEL: Defa	

*= SPECIALTY ITEM

CONSTRUCTION CODE

				CONSTRUC	TION CODE
				100% STATE	100% STATE
-				KNOX COUNTY	KNOX COUNTY
				BOX CULVERT	BOX CULVERT
CODE			TOTAL	0004	0004
NO .	ITEM	UNIT	QUANTITY	S.N. 048-1005	S.N. 048-1006
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	0.5	0.5
Z0054400	ROCK FILL	CU YD	41	0	41
*= SPECIAL	_TYITEM				

USER NAME = \$USER\$	DESIGNED -	REVISED -
	DRAWN -	REVISED -
PLOT SCALE = 1:100	CHECKED -	REVISED -
PLOT DATE = 7/7/2023	DATE -	REVISED -

STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES SCALE: SHEET 5 OF 5 SHEETS STA. TO STA.

COUNTY TOTAL SHEETS NO.

KNOX 38 7 SECTION (140,142)CLV CONTRACT NO. 68G66

LOCATION	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE, NARROW), TEST LEVEL 3	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE, NARROW), TEST LEVEL 3	TEMPORARY CONCRETE BARRIER	PINNING TEMPORARY CONCRETE BARRIER*	RELOCATE TEMPORARY CONCRETE BARRIER	PAVEMENT MARKING BLACKOUT TAPE, 5"	SHORT TERM PAVEMENT MARKING REMOVAL	TEMPORARY RUMBLE STRIPS
	EACH	EACH	FOOT	EACH	FOOT	FOOT	SQ. FT.	EACH
DOUBLE 4x4 CULVERT (SN 048-1005)								
STAGE I	2.0		250.0			120.0	50.0	6.0
STAGE II		2.0			125.0			
10x7 CULVERT (SN 048-1006)								
STAGE I	2.0	_	287.5			100.0	41.7	6.0
STAGE II		2.0		15.0	125.0			
4x4 SUBTOTAL	2.0	2.0	250.0	0.0	125.0	120.0	50.0	6.0
10x7 SUBTOTAL	2.0	2.0	287.5	15.0	125.0	100.0	42.0	6.0
TOTAL	4.0	4.0	537.5	15.0	250.0	220.0	92.0	12.0
*BARRIER WALL SHALL BE PINNED BETWEEN ST	ΓA. 116+33.7 AND 116+96.2							

				PAINT PAVEMENT MARKING - LINE 4"			
	LOCA	TIOI	N	EDGELINE	CL SKIP		
				WHITE	YELLOW		
				FOOT	FOOT		
DOUE	BLE 4x4 CULV	ERT	(SN 048-1005)				
STA.	1448+00	ТО	1455+00	1400.0	180.0		
10x7 (CULVERT (SN	048-	-1006)				
STA.	113+00	ТО	120+50	1500.0	190.0		
	4x4 SUE	3707	TAL.	1580.0			
	10x7 SU	вто	1690.0				
	TO	TAL		3270.0			

LOCATION	MOBILIZATION	CHANGEABLE MESSAGE SIGN*	CONSTRUCTION LAYOUT	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	
	LSUM	CAL DAY	LSUM	EACH	LSUM	
DOUBLE 4x4 CULVERT (SN 048-1005)	0.5	14.0	0.5	1.0	0.5	
10x7 CULVERT (SN 048-1006)	0.5	14.0	0.5	1.0	0.5	
TOTAL	1.0	28.0	1.0	2.0	1.0	
*4 Boards @ 7 Days Each						

SCALE:

LOCATION	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) FLARED	TRAFFIC BARRIER TERMINAL, TYPE 2		STRONG POST GUARDRAIL ATTACHED TO CULVERT	STEEL PLATE BEAM GUARDRAIL (SHORT RADIUS)	GUARDRAIL REFLECTORS, TYPE A	TERMINAL MARKER - DIRECT APPLIED	GUARDRAIL AGGREGATE EROSION CONTROL
	FOOT	EACH	EACH	FOOT	FOOT	FOOT	EACH	EACH	TON
10x7 CULVERT (SN 048-1006)									
LT STA 116+92.2 TO 117+06.1			1.0			25.0			7.6
LT STA 117+06.1 TO 118+93.6	175.0				12.5		4.0		38.2
LT STA 118+93.6 TO 119+43.6		1.0						1.0	12.2
RT STA 112+79.4 TO 113+29.4		1.0						1.0	12.2
RT STA 113+29.4 TO 116+48.4	319.0								64.9
RT STA 116+48.4 TO 116+98.4				50.0			5.0		10.2
RT STA 116+98.4 TO 119+23.4	275.0								56.0
RT STA 119+23.4 TO 119+73.4		1.0						1.0	12.2
TOTAL	769.0	3.0	1.0	50.0	12.5	25.0	9.0	3.0	213.0

USER NAME = \$USER\$	DESIGNED -	REVISED -
	DRAWN -	REVISED -
PLOT SCALE = 1:100	CHECKED -	REVISED -
PLOT DATE = 7/7/2023	DATE -	REVISED -

STATE	OF ILLINOIS
DEPARTMENT O	F TRANSPORTATION

							F.A.P. RTE	SEC.	ΓΙΟΝ		COUNTY	TOTAL SHEETS	SHEET NO.
SCHEDULE OF QUANTITIES						665	(140,1	42)CLV		KNOX	38	8	
											CONTRAC	T NO. 6	8G66
SHEET	1	OF	2	SHEETS	STA.	TO STA.			ILLINOIS	FED. A	ID PROJECT		

		EARTHWORK		TOPSOIL
	20200100			21101600
	EARTHWORK	EMBANKMENT	BALANCE	TOPSOIL
LOCATION	EXCAVATION		WASTE (+) OR	FURNISH AND
200/111011			SHORTAGE (-)	PLACE,
				VARIABLE DEPTH
	(CU YD)	(CU YD)	(CU YD)	(SQ YD)
STA 1451+15.32 IL R	TE 116 RC BOX CU	LVERT		
1451+15.35 RT	111.0	59.0	52.0	200.5
1451+15.35 LT	109.0	54.0	55.0	82.0
SUB-TOTAL	220.0	113.0	107.0	282.4
ADJ. SUB-TOTAL	220.0	115.0	110.0	285.0
STA 116+94.46 IL RT	E 116 RC BOX CUL	VERT		
116+94.46 RT	148.2	63.4	84.8	121.9
116+94.46 LT	129.2	63.4	65.8	144.7
SUB-TOTAL	277.4	126.8	150.6	266.6
ADJ. SUB-TOTAL	280.0	130.0	155.0	270.0
R.E. DESCRETION				
GRAND TOTAL	500.0	245.0	265.0	555.0

RAW VALUES NO SHRINKAGE FACTOR APPLIED

EARTHWORK - STA 1451+15.35

- 1. TRENCH FOR CULVERT UNDER PVMT ESTIMATED AT 40 CU YD PER SIDE
- 2. BARRELL SECTION ESTIMATED 20' LENGTH (SOUTH SIDE) FILL 2.5 CU YD PER FOOT & CUT 0.5 CU YD PER FOOT
- BARRELL SECTION ESTIMATED 22.5' LENGTH (NORTH SIDE) FILL 2.4 CU YD PER FOOT & CUT 0.6 CU YD PER FOOT
- 3. RIPRAP SECTION ESTIMATED AT 45' LENGTH (SOUTH SIDE) FILL 0.2 CU YD PER FOOT & CUT 1.4 CU YD PER FOOT RIPRAP SECTION ESTIMATED AT 12' LENGTH (NORTH SIDE) FILL 0.0 CU YD PER FOOT & CUT 4.6 CU YD PER FOOT

EARTHWORK - STA 116+94.46

- 1. TRENCH FOR CULVERT UNDER PVMT ESTIMATED AT 136 CU YD SOUTH SIDE & 117 CU YD NORTH SIDE
- 2. BARRELL SECTION ESTIMATED 12' LENGTH (SOUTH SIDE) FILL 2.5 CU YD PER FOOT & CUT 0.4 CU YD PER FOOT
- 3. WINGWALLS & RIPRAP SECTION ESTIMATED AT 37' LENGTH (SOUTH SIDE) FILL 0.2 CU YD PER FOOT & CUT 1.4 CU YD PER FOOT

							EROSION SCHED	ULE					
LO	CATI	ION	SEEDING CL 2A	NITROGEN FERT NUTR	PHOSPHORUS FERT NUTR	POTASSIUM FERT NUTR	MULCH METHOD 3	TURF REINF MAT	AGG DITCH CHECKS	PERIMETER EROS BAR	STONE RIPRAP, CLASS A3	STONE RIPRAP, CLASS A5	FILTER FABRIC
			25000210	25000400	25000500	25000600	25100125	25100900	28000315	28000400	28100105	28100109	28200200
STATION		STATION	(ACRE)	(POUND)	(POUND)	(POUND)	(ACRE)	(SQ YD)	(TON)	(FOOT)	(SQ YD)	(SQ YD)	(SQ YD)
STA 1451+15.	32 IL	RTE 116 RC E	OX CULVERT	•								•	
1450+75	RT	1451+16										116.2	116.2
1451+15	LT	1451+56										46.6	46.6
1451+04.03	LT	1451+44.08	0.017	1.5	1.5	1.5	0.017						
1450+74.2	RT	1451+27.14	0.041	3.7	3.7	3.7	0.041						
1451+65	LT								20				
1451+05	LT								20				
1451+30	RT								20				
1450+65	RT								20				
SUB-TOTAL			0.058	5.3	5.3	5.3	0.058		80			162.7	162.7
ADJUSTED S	UB-T	OTAL	0.1	6.0	6.0	6.0	0.1		80			163.0	163.0
STA 116+94.4	6 IL 1	RTE 116 RC BC	OX CULVERT										
117+28.24		117+46.02									19.6		19.6
116+30.15		116+61.94									48.0		48.0
117+30.31	LT	117+60.04										46.1	46.1
116+30.15	RT	166+59.88										46.1	46.1
117+46.02	LT	117+60.04	0.006	0.5	0.5	0.5	0.006	29.2					
116+94.36	LT	117+47	0.024	2.1	2.1	2.1	0.024	78.1					
116+43.2	RT	116+93.11	0.025	2.3	2.3	2.3	0.025	84.9					
116+15	RT	116+52.72								45			
117+70	LT								20				
116+90	RT								20				
SUB-TOTAL			0.055	5.0	5.0	5.0	0.055	192.3	40	45.0	67.6	92.3	159.9
ADJUSTED S	IIR.T	OTAL	0.000	5.0	5.0	5.0	0.1	193.0	40	45.0	68.0	93.0	160.0
GRAND TOTA		OIAL	0.1	11.0	11.0	11.0	0.1	193.0	120	45.0	68.0	256.0	323.0
ADJUSTED G		D TOTAL	0.25	11.0	11.0	11.0	0.25	193.0	120	45.0	68.0	256.0	323.0
	_												


				PAVEMENT SCHE	DULE			
LO	CATI	ON	AGG BASE CSE A 12	BIT MATLS PR CT	BIT MATLS TACK CT	CL D PATCH T4 14	AGGREGATE SHLDS A	
			35101100	40800025	40800029	44201821	48100200	
STATION		STATION	(SQ YD)	(POUND)	(POUND)	(SQ YD)	(CU YD)	
STA 1451+15.	32 IL	RTE 116 RC E	OX CULVERT					
1451+04.03	LT	1451+42.03	46.4	104.4	33.4	46.4		
1450+89.14	RT	1451+27.14	48.0	107.9	34.5	48.0		
SUB-TOTAL			94.4	212.3	67.9	94.4	0.0	
ADJUSTED S	UB-T	DTAL	95.0	213.0	68.0	95.0	0.0	
STA 116+94.4	6 IL 1	RTE 116 RC B	OX CULVERT					
116+94.92	LT	117+06.56	7.8	17.5	5.6	7.8	11.3	
116+43.87	RT	116+93.11	43.6	98.1	31.4	43.6	12.8	
116+94.92	LT	117+46.02	40.6	91.3	29.2	40.6		
SUB-TOTAL			91.9	206.8	66.2	91.9	24.1	
ADJUSTED S	UB-T	OTAL	92.0	207.0	67.0	92.0	25.0	
GRAND TOTA	L		187.0	420.0	135.0	187.0	25.0	
ADJUSTED GRAND TOTAL			187.0	420.0	135.0	187.0	25.0	


		REMOVA	AL SCHEDULE	
LO	CATI	ON	GUARDRAIL REMOV	REVETMENT MAT REMOVAL
			63200310	X2850001
STATION		STATION	(FOOT)	(SQ YD)
STA 1451+15.	32 IL	RTE 116 RC E	OX CULVERT	
1450+63.96	LT	1452+17.49	153.5	
1450+13.06	RT	1451+66.27	153.4	
SUB-TOTAL			306.9	0.0
ADJUSTED SU	JB-T	OTAL	307.0	0.0
STA 116+94.4	6 IL	RTE 116 RC BC	OX CULVERT	
115+55.99	RT	117+00.88	144.9	
117+07.98	LT	118+10.64	102.7	
116+94.92	LT	117+46.02		
116+94.92	LT	117+06.56		
116+43.87	RT	116+93.11		
116+30.15	RT	116+66.39		58.7
SUB-TOTAL			247.6	58.7
ADJUSTED SI	JB-T	OTAL	248.0	59.0
GRAND TOTA	L		555.0	59.0
ADJUSTED G	RANI) TOTAL	555.0	59.0

askaskia gineering Group, LLC	200 E. Main St., Suite 100 Belleville, Illinois 62220 638-233-877 phone 638-233-977 for own.karkaskdaeng.com LICENSE NO.
Illinois Professional Design Firm Professional Engineering Group	184.004773 20-5080586

USER NAME = rjo	DESIGNED - RJO	REVISED -
	DRAWN - RJO	REVISED -
PLOT SCALE = 10,0000 ' / in.	CHECKED - RJB	REVISED -
PLOT DATE = 7/7/2023	DATE -	REVISED -

SCHEDULE OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	
FAP 665 (IL 116) CONTRACT MAINTENANCE CULVERT REPAIRS	665	(140,142)CLV	KNOX	38	9
TAI 003 (IL 110) CONTINAUT MAINTENANCE COLVENT HELAINS			CONTRAC	Γ NO. 68	3G66
LE: N.T.S. SHEET 1 OF 1 SHEETS STA. TO STA.		ILLINOIS FED.	AID PROJECT		






PROPOSED TYPICAL SECTION

ILLINOIS ROUTE 116

STA 1450+89.14 TO STA 1451+27.14 RT

STA 1451+04.03 TO STA 1451+42.03 LT



PROPOSED TYPICAL SECTION
ILLINOIS ROUTE 116
STA 116+43.87 TO STA 116+93.11 RT
STA 116+94.92 TO STA 117+46.02 LT


CALCULATION/APPLICATION RATES
AGGREGATE 2.0 TONS/CU YD
TACK COAT 0.08 LBS/SQ FT
PRIME COAT 0.25 LBS/SQ FT
ASPHALT 112 LBS/SQ YD/IN (0.056 TONS/SQ YD/IN)
FERTILIZER 90 LBS/ACRE


	askaskia gineering Group, LLC	200 : Befs 618 618
7	Illinois Professional Design Firm Professional Engineering Group	184.) 20-5


	208 E. Main St., Suite 100 Belleville, Illinois 62220	USER NAME = rjo	DESIGNED - RJO	REVISED -
a	618,233,5877 physic 618,233,9977 fex prove, karbacklaene, cum		DRAWN - RJO	REVISED -
ONS	LICENSE NO. 184,004773	PLOT SCALE = 10,0000 ' / in.	CHECKED - RJB	REVISED -
up	20-5080596	PLOT DATE = 7/5/2023	DATE -	REVISED -


STATE	: OI	F ILLINOIS
DEPARTMENT	OF	TRANSPORTATION


	TYPICAL SECTIONS											
FAP 665 (IL 116) CO	NTRACT	MAINTE	NANCI	CULVERT REPAIRS							
SCALE: N.T.S.	SCALE: N.T.S. SHEET 1 OF 1 SHEETS STA. TO STA.											














MODEL: Default

JSER NAME = \$USER\$

PLOT DATE = 7/7/2023

DESIGNED -

DRAWN

DATE

CHECKED

REVISED

REVISED

REVISED

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION


 4' X 4' CULVERT STAGING DETAILS
 F.A.P. RTE. G65
 SECTION G65


 SHEET 2 OF 4 SHEETS STA. TO STA.
 TO STA.
 ILLIN


(140,142)CLV KNOX 38 17

CONTRACT NO. 68G66

| ILLINOIS | FED. AID PROJECT







USER NAME = \$USER\$ DESIGNED - REVISED - REVISED - REVISED - STATE OF ILLINOIS
PLOT SCALE = 1:100 CHECKED - REVISED - REVISED - REVISED - REVISED - CHECKED - REVISED - CHECKED - REVISED - CHECKED - REVISED - CHECKED -

SECTION

(140,142)CLV

KNOX 38 19

CONTRACT NO. 68G66

Existing Structure: The structure is a double 4' x 4' reinforced concrete box culvert constructed circa 1933 and rehabilitated circa 1975. Culvert extension work will be done under staged closures. See Roadway Plans.

Salvage: None.

DESIGN STRESSES PRECAST UNITS

 $f'c = 5,000 \ psi$

DESIGN SPECIFICATIONS 2020 AASHTO LRFD Bridge


LOADING HL-93 Design Specifications, 9th Edition


INDEX OF SHEETS


- 1 General Plan & Elevation
- 2 General Data
- 3 Culvert Removal Details
- 4-5 Precast Concrete Box Culvert Apron End Section Details
 - 6 Connection Collar Details
- 7-8 Boring Logs

fy = 65,000 psi (Welded Wire Reinforcement) FIELD UNITS

f'c = 3,500 psi fy = 60,000 psi (Reinforcement)







PLAN

REVISED

REVISED

REVISED -

REVISED -

TRUCTURA MOSHE L. COHEN 081-008104

Dated: 2023-08-16 Illinois Structural Engineer No. 081-008104 License Expires: 11-30-2024

GENERAL PLAN AND ELEVATION IL RTE. 116 OVER UNNAMED DITCH F.A.P. RTE. 665 SEC. (140,142)CLV KNOX COUNTY

SHEET 1 OF 8 SHEETS

STATION 1451+15.35 STRUCTURE NO. 048-1005

DESIGNED - MLC Kaskaskia CHECKED - MMC DRAWN PLOT DATE = CHECKED - MMC

STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION

SECTION COUNTY 665 (140,142)CLV KNOX 38 20 CONTRACT NO. 68G66

8/16/2023 2:22:35 PM


The design fill height for this box shall be determined by the contractor based on field measurements and accepted by the engineer. The precast box culvert sections shall conform to the requirements of ASTM C 1577.

Drain holes shall be provided on exterior culvert walls for each precast box segment with a clear rise greater than 3 ft. The drain hole shall be located within 1/3 of the clear rise of the box culvert, shall not intercept the haunch, and shall conform to the requirements of Article 503.11 of the Standard Specification.

Nonwoven geotextile fabric shall conform to the requirements of Art. 1080.01 of the Standard Specifications. The minimum weight of the fabric shall be 6 ounces per square yard.


Precast concrete box culverts and box culvert end sections shall be backfilled with Porous Granular Embankment in the required excavation areas on the sides of the box culvert from the top of the box culvert to the bottom of the box culvert. This area of PGE is included in the Porous Granular Embankment pay item. The 6-inch thick layer of porous granular material required under the precast concrete box culvert, according to Section 540.06 of the standard specifications, shall also apply to the end sections. Cost of this porous granular material will not be paid for separately but shall be included in the unit price of the work for which it is required.

All exposed concrete edges shall have a standard 3/4" chamfer unless noted otherwise. All construction joints shall be bonded.




DRAIN DETAIL

(All costs associated with furnishing and constructing the above drain detail will not be measured for payment but shall be included in the contract unit price for the associated work.)




TOTAL BILL OF MATERIAL

ITEM	UNIT	TOTAL
Porous Granular Embankment	Cu. Yd.	110
Concrete Removal	Cu. Yd.	13.7
Reinforcement Bars	Pound	2,570
Name Plates	Each	1
Temporary Soil Retention System	Sq. Ft.	207
Box Culvert End Sections, Culvert No. 1	Each	2
Concrete Box Culverts	Cu. Yd.	7.1
Precast Concrete Box Culverts 9' x 4'	Foot	41
Geocomposite Wall Drain	Sq. Yd.	81
Membrane Waterproofing System for Buried Structures	Sq. Yd.	81



SECTION THRU BARREL

Showing limits of Membrane Waterproofing System for Buried Structures and Geocomposite Wall Drain.



TEMPORARY SOIL RETENTION SYSTEM


(Showing Pay Limits)

The Contractor shall submit a temporary soil retention system design including plan details and calculations for review and acceptance by the Engineer. The Contractor's design shall incorporate all safety and strength requirements, including but not limited to those of IDOT and the Occupational Safety and Health Administration. Variations in the limits of the Temporary Soil Retention System from those shown shall not be paid; plan quantity will be considered total compensation for the amount actually furnished.

DESIGNED - MLC REVISED -Kaskaskia Batherita, Milina St., CHECKED - MMC REVISED -DRAWN MLC REVISED PLOT DATE = CHECKED - MMC REVISED -

STATE OF ILLINOIS **DEPARTMENT OF TRANSPORTATION**

SECTION COUNTY **GENERAL DATA** (140,142)CLV KNOX 38 21 665 **STRUCTURE NO. 048-1005** CONTRACT NO. 68G66 SHEET 2 OF 8 SHEETS



Kaskaskia Bakeria, Illinois 8

DESIGNED - MLC

CHECKED - MMC

DRAWN - MLC

CHECKED - MMC

REVISED -

REVISED -

REVISED -

REVISED -

STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION

CULVERT REMOVAL DETAILS STRUCTURE NO. 048-1005


F.A.P. RTE. 665 COUNTY TOTAL SHEETS NO.

KNOX 38 22 SECTION (140,142)CLV CONTRACT NO. 68G66

SHEET 3 OF 8 SHEETS

8/16/2023 2:22:42 PM

END VIEW



<u>PLAN</u>

SCB-AES 2-17-2017

208 II. Main St., Smite 100 Befleville, Bilnets 51220	USER NAME =	DESIGNED - MLC	REVISED -
Kaskaskia (68,233,897) plune (68		CHECKED - MMC	REVISED -
PROFESSIONAL REGISTRATIONS LICENSE NO. Illinois Professional Design Firm 184,004773	PLOT SCALE =	DRAWN - MLC	REVISED -
Professional Engineering Group 20-800086	PLOT DATE =	CHECKED - MMC	REVISED -

6'-0" min. $(R \le 3'-0")$ See General Notes 10'-0" min. (R > 3'-0") regarding culvert ties. F F SECTION A-A

GENERAL NOTES

Box Culvert End Sections shall be constructed according to the requirements of Section 540 of the Standard Specifications except as modified herein. End sections will be paid for at the contract unit price per each for Box Culvert End Sections.

The Contractor may furnish the end section as a single precast concrete piece or construct the end section in the field using cast-in-place (CIP) construction. For CIP construction, the bottom slab thickness shall be ncreased by 2" and the clear cover to the bottom mat of reinforcement shall be increased to 3".

Box section dimensions, materials, and reinforcement details for Box Culvert End Sections shall be according to the requirements for ASTM C 1577 as required for the design of the portion of the culvert within the limits of Precast Concrete Box Culverts except as modified herein.

The number of culvert ties shall be sufficient to engage the minimum length of culvert barrel shown within the pay limits for Precast Concrete Box Culverts and will be dependent upon the length of box culvert segments furnished by the Contractor. Culvert ties are not required for box culverts having a rise (R) less than or equal to 3 ft and a span (S) greater than or equal to 10 ft.

All costs associated with furnishing and installing or constructing the toewall and culvert ties will not be measured for payment but shall be included in the unit price for Box Culvert End Sections of the culvert number specified.

Shop drawings that detail slab thickness and reinforcement layout for the Box Culvert End Sections shall be provided to the Engineer for review and approval. Reinforcement bars not detailed herein shall be detailed with a clear distance at the end of the reinforcement not less than ½" nor more than 2". For the precast option, it shall be the Contractor's responsibility for determining a method of handling and a construction procedure shall be included on the shop drawings. The Contractor shall determine and detail in the shop drawings any necessary strengthening or stiffening provisions necessary to handle the precast segment. Any required modifications shall be at no extra charge.

The Contractor may use reinforcement bars in lieu of welded wire reinforcement (WWR). Reinforcement bars shall be limited to the sizes of #3 through #5 bars, a maximum spacing of the lesser of 8" or the member thickness, and shall result in an area of reinforcement equal to or greater than that provided by the WWR. Minimum lap lengths detailed herein are applicable to WWR and reinforcement bars.

Reinforcement (circumferential and longitudinal) in the culvert barrel portion of the end section being lapped with reinforcement from the wingwalls or bottom slab of the end section shall not be less than that required by ASTM C 1577 for the design fill height or the reinforcement detailed for the end section, whichever is greater.

One drain hole shall be provided in each wingwall for end sections of box culverts having an opening with a clear rise greater than 3 ft. The drain hole shall be located within the lower 1/3 of the clear rise of the box culvert and shall conform to the requirements of Article 503.11 of the Standard Specifications.

STATE OF ILLINOIS

DEPARTMENT OF TRANSPORTATION

APRON END SECTION DIMENSIONS

Span (S)	Rise (R)	Τι	Tb	Ts	А	В	С	D	Е	Concrete Cu. Yd.	Culvert Ti Required
3'-0"	2'-0"	7"	6"	4"	3'-4"	2'-2"	2'-105/8"	4'-1"	10'-45%"	2.8	Yes
3'-0"	2'-0"	4"	4"	4"	3'-1"	2'-1"	2'-71/8"	3'-9"	9'-11"	2.3	Yes
3'-0"	3'-0"	7"	6"	4"	4'-4"	2'-8"	3'-105/8"	5'-6"	12-45/8"	3.7	Yes
3'-0"	3'-0"	4"	4"	4"	4'-1"	2'-7"	3'-71/8"	5'-2"	11'-11"	3.1	Yes
4'-0"	2'-0"	7.5"	6"	5"	3'-41/2"	2'-21/2"	2'-113/8"	4'-2"	11'-8"	3.3	Yes
4'-0"	2'-0"	5"	5"	5"	3'-2"	2'-1"	2'-81/2"	3'-10"	11'-23/8"	2.8	Yes
4'-0"	3'-0"	7.5"	6"	5"	4'-41/2"	2'-81/2"	3'-113/8"	5'-7"	13'-81/8"	4.2	Yes
4'-0"	3'-0"	5"	5"	5"	4'-2"	2'-7"	3'-81/2"	5'-3"	13'-23/8"	3.7	Yes
4'-0"	4'-0"	7.5"	6"	5"	5'-4 ¹ / ₂ "	3'-21/2"	4'-113/8"	7'-0"	15'-81/8"	5.3	Yes
4'-0"	4'-0"	5"	5"	5"	5'-2"	3'-1"	4'-85/8"	6'-8"	15'-21/2"	4.7	Yes
5'-0"	2'-0"	8"	7"	6"	3'-5"	2'-3"	2'-113/8"	4'-2"	12'-10"	3.9	Yes
5'-0"	2'-0"	6"	6"	6"	3'-3"	2'-2"	2'-10"	4'-0"	12'-71/4"	3.5	Yes
5'-0"	3'-0"	8"	7"	6"	4'-5"	2'-9"	3'-113/8	5'-7"	14'-101/8"	4.9	Yes
5'-0"	3'-0"	6"	6"	6"	4'-3"	2'-8"	3'-10"	5'-5"	14'-71/4"	4.5	Yes
5'-0"	4'-0"	8"	7"	6"	5'-5"	3'-3"		7'-0"			Yes
							4'-113/8"		16'-101/8"	6.1	
5'-0"	4'-0"	6"	6" 7"	6"	5'-3"	3'-2"	4'-91/4"	6'-9"	16'-57/8"	5.5	Yes
5'-0"	5'-0"	8"	<u> </u>	6"	6'-5"	3'-9"	5'-113/8"	8'-5"	18'-101/8"	7.4	Yes
5'-0"	5'-0"	6"	6"	6"	6'-3"	3'-8"	5'-91/4"	8'-2"	18'-57/8"	6.8	Yes
6'-0"	2'-0"	8"	7"	7"	3'-5"	2'-3"	2'-113/8"	4'-2"	14'-0"	4.3	Yes
6'-0"	2'-0"	7"	7"	7"	3'-4"	2'-2"	2'-105/8"	4'-1"	13'-105%"	4.2	Yes
6'-0"	3'-0"	8"	7"	7"	4'-5"	2'-9"	3'-113/8"	5'-7"	16'-01/8"	5.4	Yes
6'-0"	3'-0"	7"	7"	7"	4'-4"	2'-8"	3'-105/8"	5'-6"	15'-10%"	5.2	Yes
5'-0"	4'-0"	8"	7"	7"	5'-5"	3'-3"	4'-113/8"	7'-0"	18'-01/8"	6.5	Yes
5'-0"	4'-0"	7"	7"	7"	5'-4"	3'-2"	4'-10¾"	6'-11"	17'-10¾"	6.5	Yes
5'-0"	5'-0"	8"	7"	7"	6'-5"	3'-9"	5'-113/8"	8'-5"	20'-0 ¹ / ₈ "	8.0	Yes
5'-0"	5'-0"	7"	7"	7"	6'-4"	3'-8"	5'-10¾"	8'-4"	19'-10¾"	7.8	Yes
5′−0"	6'-0"	8"	7"	7"	7'-5"	4'-3"	6'-111/2"	9'-10"	22'-01/4"	9.5	Yes
5'-0"	6'-0"	7"	7"	7"	7'-4"	4'-2"	6'-10¾"	9'-9"	21'-10¾"	9.3	Yes
7'-0"	2'-0"	8"	8"	8"	3'-5"	2'-3"	2'-113/8"	4'-2"	15'-2"	4.9	Yes
7'-0"	3'-0"	8"	8"	8"	4'-5"	2'-9"	3'-113/8"	5'-7"	17'-21/8"	6.1	Yes
7'-0"	4'-0"	8"	8"	8"	5'-5"	3'-3"	4'-113/8"	7'-0"	19'-21/8"	7.4	Yes
7'-0"	5'-0"	8"	8"	8"	6'-5"	3'-9"	5'-113/8"	8'-5"	21'-21/8"	8.9	Yes
7'-0"	6'-0"	8"	8"	8"	7'-5"	4'-3"	6'-111½"	9'-10"	23'-21/4"	10.6	Yes
8'-0"	2'-0"	8"	8"	8"	3'-5"	2'-3"	2'-113/8"	4'-2"	16'-2"	5.3	Yes
8'-0"	3'-0"	8"	8"	8"	4'-5"	2'-9"	3'-113/8"	5'-7"	18'-21/8"	6.5	Yes
8'-0"	4'-0"	8"	8"	8"	5'-5"	3'-3"	4'-113/8"	7'-0"	20'-21/8"	7.8	Yes
8'-0"	5'-0"	8"	8"	8"	6'-5"	3'-9"	5'-113/8"	8'-5"	22'-21/8"	9.3	Yes
8'-0"	6'-0"	8"	8"	8"	7'-5"	4'-3"	6'-111/2"	9'-10"	24'-21/4"	11.0	Yes
9'-0"	2'-0"	9"	9"	9"	3'-6"	2'-3"	3'-03/4"	4'-4"	17'-67/8"	6.2	Yes
		9"	_	_					_		
9'-0"	3'-0"		9"	9"	4'-6"	2'-9"	4'-03/4"	5'-9"	19'-67/8"	7.5	Yes
9'-0"	4'-0"	9'	9"	9"	5'-6"	3'-3"	5'-03/4"	7'-2"	21'-67/8"	9.0	Yes
9'-0"	5'-0"	9"	9"	9"	6'-6"	3'-9"	6'-07/8"	8'-7"	23'-7"	10.6	Yes
9'-0"	6'-0"	9"	9"	9"	7'-6"	4'-3"	7'-01/8"	9'-11"	25'-5%"	12.4	Yes
0'-0"	2'-0"	10"	10"	10"	3'-7"	2'-4"	3'-11/2"	4'-5"	18'-101/4"	7.1	No
0'-0"	3'-0"	10"	10"	10"	4'-7"	2'-10"	4'-11/2"	5'-10"	20'-101/4"	8.6	No
0'-0"	4'-0"	10"	10"	10"	5'-7"	3'-4"	5'-11/2"	7'-3"	22'-103/8"	10.2	Yes
0'-0"	5'-0"	10"	10"	10"	6'-7"	3'-10"	6'-1½"	8'-8"	24'-103/8"	12.0	Yes
0'-0"	6'-0"	10"	10"	10"	7'-7"	4'-4"	7'-1½"	10'-1"	26'-103/8"	13.9	Yes
1'-0"	2'-0"	11"	11"	11"	3'-8"	2'-4"	3'-21/8"	4'-7"	20'-3 ¹ / ₈ "	8.2	No
1'-0"	3'-0"	11"	11"	11"	4'-8"	2'-10"	4'-21/8"	6'-0"	22'-3 ¹ / ₈ "	9.8	No
1'-0"	4'-0"	11"	11"	11"	5'-8"	3'-4"	5'-2 ¹ / ₄ "	7'-4"	24'-1¾''	11.5	Yes
1'-0"	5'-0"	11"	11"	11"	6'-8"	3'-10"	6'-21/4"	8'-9"	26'-1¾"	13.3	Yes
1'-0"	6'-0"	11"	11"	11"	7'-8"	4'-4"	7'-21/4"	10'-2"	28'-1 ⁷ / ₈ "	15.5	Yes
2'-0"	2'-0"	12"	12"	12"	3'-9"	2'-5"	3'-35/8"	4'-8"	21'-6 ¹ / ₂ "	9.3	No
2'-0"	3'-0"	12"	12"	12"	4'-9"	2'-11"	4'-35/8"	6'-1"	23'-61/2"	11.1	No
2'-0"	4'-0"	12"	12"	12"	5'-9"	3'-5"	5'-35/8"	7'-6"	25'-65%"	13.0	Yes
2'-0"	5'-0"	12"	12"	12"	6'-9"	3'-11"	6'-35/8"	8'-11"	27'-65%"	14.1	Yes
2'-0"	6'-0"	12"	12"	12"	7'-9"	4'-5"	7'-35/8"	10'-4"	29'-65%"	17.4	Yes
	:						. 5,6			27.17	, , , , ,

Two sets of apron end section dimensions are shown above for some box culvert sizes due to the top and bottom slabs having different thicknesses per ASTM C 1577 for design fill heights less than 2 ft. (Sheet 1 of 2)

PRECAST CONCRETE BOX CULVERT APRON END SECTION DETAILS
STRUCTURE NO. 048-1005


SHEET 4 OF 8 SHEETS

8/16/2023 2:22:47 PM

iciles(ibot rio)cces(zi-to+4,09 iz 110 colocie

g-pw.bentley.com:keg-pw-01\Documents\IDOT F

DEL: Def E NAME:



SECTION B-B (Top slab at downstream end)

SECTION E-E

SECTION B-B

_____ , , , , , , , 1'-6" min. Optional lap splice. See General Notes for reinforcement requirements.

> SECTION B-B (Bottom Slab)

SECTION C-C

1'-6"

1" cl.


Bonded construction joint

3" Ø corrugated PE pipe per Article 1040.04 of the Standard Specifications. Fill with non-shrink grout 6-#5 h1 bars placed as shown #4 v1 bars drilled and epoxy grouted into toewall in 9" min. deep holes at 1'-6" cts., max. #4 s2 bars at 1'-0" cts., max. typ. 1'-0"

SECTION D-D

(Top slab at upstream end)

*** This dimension shall be increased by 2" for CIP construction.



SECTION F-F (Showing culvert tie details)

TOEWALL CONSTRUCTION SEQUENCE 1. Perform excavation and construct toewall. 2. Backfill accordingly and place bedding for precast box culvert end sections.

- 3. Set precast box culvert end section.
- 4. Drill and epoxy grout reinforcement in toewall in accordance with Section 584 of the Standard Specifications.
- 5. Pressure grout voids using non-shrink grout conforming to Section 1024 of the Standard Specifications.
- * The Contractor may furnish a precast or cast-in-place toewall. The Contractor shall be responsible for the strength and stability of the precast toewall during handling. Additional lifting points may be required depending upon the length of the toewall or the Contractor may need to modify the design of the toewall for the proposed handling method.
- ** If soil conditions permit, the sides of the toewall may be poured directly against the soil. The clear cover on the sides of the toewall shall be increased to 3" by increasing the thickness of the toewall.


COUNTY

KNOX 38 24

CONTRACT NO. 68G66


ℚ 1¼" Ø hole for 1" Ø anchor rod with 21/4" x 21/4" x 5/16" ¶ 1½" Ø hole in bottom leg of angle

RESTRAINT ANGLE DETAIL



TIE PLATE DETAIL

1" Ø anchor rods for the culvert ties shall conform to the requirements of ASTM F1554, Grade 105. Structural steel for the tie plate and restraint angle shall conform to the requirements of Article 1006.04 of the Standard Specifications. All components of the culvert tie detail shall be galvanized according to the requirements of AASHTO M 111 or M 232 as applicable. $2\frac{1}{4}$ " $x2\frac{1}{4}$ " $x^{\frac{5}{16}}$ " plate washers shall be provided under each nut required for the anchor rods. Anchor rods connecting precast sections shall be brought to a snug tight condition followed by an additional ½ turn on one of the nuts for anchor rods installed in the walls. Match marks shall be provided on the bolt and nut to verify relative rotation between the bolt and the nut. Holes in the walls for the culvert tie assembly may be drilled using core bits in lieu of using formed holes.



BAR s

31/8"

BAR s1

#4 s or s1 bars at spacing = Tt

(Spacing need not be less than 8")

DRAWN

CHECKED - MMC

BAR s2

9"

BAR s3

REVISED -

REVISED -

REVISED -

REVISED


SCB-AES 2-17-2017 JSER NAME = DESIGNED - MLC Kaskaskia CHECKED - MMC

PLOT DATE =

STATE OF ILLINOIS **DEPARTMENT OF TRANSPORTATION**

(Sheet 2 of 2)			
PRECAST CONCRETE BOX CULVERT APRON END SECTION DETAILS	F.A.P. RTE.	SECTION	
STRUCTURE NO. 048-1005	665	(140,142)CLV	
SINOUTONE NO. 040-1003			

8/16/2023 2:22:48 PM



8/16/2023 2:22:51 PM

Illinois Department of Transportation Division of Highways inor

SOIL BORING LOG

Page $\underline{1}$ of $\underline{2}$

Date ___1/23/23

FAP 665 (IL 116) LOGGED BY Maria Rojo DESCRIPTION Structure boring for culvert LOCATION IL 116 west of IL 41, SEC. 30, TWP. 9 N, RNG. 1 E, 4th PM. SECTION 140 and 142 Latitude 40.729320, Longitude -90.434831 HSA **DRILLING METHOD** HAMMER TYPE Knox Automatic COUNTY В U D U D В STRUCT. NO. Surface Water Elev. 1451+20 L С 0 Е L С 0 Stream Bed Elev. Station О 0 S S W W CB-1W BORING NO. s Qu Т S Qu 1451+08 587.4 ft**▼** Station First Encounter 24.0 ft LT Offset Upon Completion the borehole ft ft (ft) (/6") (tsf) (%) (ft) (/6") (tsf) (%) Ground Surface Elev. 601.39 After Hrs. 12-inch thick, dark brown SILTY Loose, gray medium grained CLAY LOAM; damp SAND, trace gravel; saturated --TOPSOIL--/ --RDR 2-- (continued) 4 NR --mud rotary below 21 ft-- 579.39 Stiff to very stiff, brown and gray 2 2.0 26 SILTY CLAY to SILTY CLAY 2 4 Ρ Stiff to very stiff, gray SILTY LOAM, trace gravel; damp 3 CLAY, trace gravel; damp 5 2.2 19 2 27 1.0 В 3 -25 2 Ρ 3 2.5 Stiff to very stiff, gray and brown 3 21 CLAY to SILTY CLAY; damp 3 23 Ρ 2.1 4 В 5 5 -30 3 1.6 18 2 23 4 В 1.7 3 В 4 Very loose to medium dense, orange brown to gray fine SAND NP 17 to SANDY LOAM; damp to wet 6 6 -35 1.4 20 18 NP 3 3 NP 20 2 --gray-582.89 3 1.7 25 Loose, gray medium grained SAND, trace gravel; saturated 0 NΡ 20 4 В --RDR 2--0

The Unconfined Compressive Strength (UCS) Failure Mode is indicated by (B-Bulge, S-Shear, P-Penetrometer) The SPT (N value) is the sum of the last two blow values in each sampling zone (AASHTO T206)

BBS, form 137 (Rev. 8-99)



SOIL BORING LOG

Page <u>2</u> of <u>2</u>

Date ___1/23/23

IDOT			Date
ROUTE FAP 665 (IL 116)	_ DESCRIPTION _	Structure boring for culvert	LOGGED BY Maria Rojo
SECTION 140 and 142	LOCATION	IL 116 west of IL 41, SEC. 30, TWP. 9 N,	RNG. 1 E, 4 th PM,
COUNTY Knox DR	RILLING METHOD	Latitude 40.729320, Longitude -90.434 HSA HAMMER	
STRUCT. NO. Station 1451+20 BORING NO. CB-1W Station 1451+08 Offset 24.0 ft LT Ground Surface Elev. 601.39		Stream Bed Elev. Stream Bed Elev. Groundwater Elev.: First Encounter 587.4 Upon Completidnin the borehole	ft <u>↓</u> ft <u>▼</u> <u>∍</u> ft
Stiff to very stiff, gray SILTY CLAY, trace gravel; dampRDR 2 (continued)		4 21	

The Unconfined Compressive Strength (UCS) Failure Mode is indicated by (B-Bulge, S-Shear, P-Penetrometer) The SPT (N value) is the sum of the last two blow values in each sampling zone (AASHTO T206)

BBS, form 137 (Rev. 8-99)

Kaskaskia
Engineering Group LLC
Programme from Photocock secretary from

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

Illinois Department of Transportation Division of Highways

SOIL BORING LOG

Page $\underline{1}$ of $\underline{2}$

Date ___1/23/23

ROUTE	FAP 665 (IL 116)	DES	SCR	PTION	ı		Structure boring for culvert	_ LO	GGI	ED BY	Maria	a Rojo
SECTION	140 and 142		_ ι	OCAT	ION _	IL 116	west of IL 41, SEC. 31, TWP. 9 N, RNO	G . 1 E	, 4 th	PM,		
COUNTY	Knox DRI I	LLING	ME	THOD			de 40.729156, Longitude -90.434805 HSA HAMMER TY			Auto	matic	
STRUCT. NO Station BORING NO. Station Offset			D E P T H	B L O W S	U C S	M O I S T	Surface Water Elev. Stream Bed Elev. Groundwater Elev.: First Encounter 582.7 Upon Completion the borehole	ft ft	D E P T H	B L O W S	U C S Qu	M O I S T
	face Elev. 597.68	_ ft	(ft)	(/6")	(tsf)	(%)	After Hrs.	ft	(ft)	(/6")	(tsf)	(%)
LOAM Medium stiff,	TOPSOIL/ brown SILTY CLAY AY LOAM, trace	96.68		0 0 4	0.5 P	25	Stiff to very stiff, gray CLAY to SILTY CLAY, trace to some gravel; damp	76.93 - -		4 4 3 4	3.4 B	24
	5	591.68	-5	1 2 2	0.5 P	37		-	-25	3 4 4	1.3 P	25
Very stiff, blac	ck CLAY; damp Buried TOPSOIL			2 3 4	2.1 B	29	silt seams	- 69.68		3 3 4	1.2 B	22
	wn and gray CLAY to trace organic RDR 2	589.18	-10	2 2 2	2.1 B	26	Very soft, brown Organic SILTY CLAY LOAM, trace twigs, organic matter, gravel; dampRDR 2organic matter debris	-	-30	2 3 3	0.3 P	94
	n to gray, fine SAND DAM; damp to RDR 2			3 3 6	NP	18	Medium stiff, gray CLAY; damp RDR 2	65.93 - -				
		Ţ	7 -15	4 4 4	NP	20		-	-35	2 3 3	0.8 B	24
			_	3 3 4	NP	20	Loose, gray SILT, trace organic matter; dampRDR 2black organic matter debris	60.93		3	NP	32
	gray			3	NP	21		-		3 4 4	INF	32

The Unconfined Compressive Strength (UCS) Failure Mode is indicated by (B-Bulge, S-Shear, P-Penetrometer)
The SPT (N value) is the sum of the last two blow values in each sampling zone (AASHTO T206)

BBS, form 137 (Rev. 8-99)



SOIL BORING LOG

Page $\underline{2}$ of $\underline{2}$

Date ___1/23/23

SECTION	140 and	142		LOCAT	TION	IL 116	west of IL 41, SEC. 31, TV	<u> </u>	G. 1 E, 4	4 th PM,
						Latitu	de 40.729156, Longitude	90.43480	5	
COUNTY	Knox	_ DRILLIN	G ME	THOD			HSA	HAMMER T	YPE	Automatic
STRUCT. NO.			D	В	U	М	Surface Water Elev.		ft	
Station	1451+2	.0	E	L	С	0	Stream Bed Elev.		ft	
			P	0	S	ı				
BORING NO.	CB-2W	<u>'</u>	¦	W S	Qu	S	Groundwater Elev.:		—	
Station	1451+17 22.0 ft R	<u>/</u>	1	"	Qu	'	First Encounter Upon Completion the			
Ground Surf	face Elev. 59	7.68 ft	(ft)	(/6")	(tsf)	(%)	After Hrs.		ft	
Orouna Gun	140c Lic V	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	1, ,	ļ , ,	· ,	· ,	Aitei iiis			
			_]						
		555.93	_							
Stiff grav SII	TY CLAY, trace			1						
gravel; damp	02/11, 11400		_	1						
	RD	R 2		-						
			_	4	1.2	18				
				5	B	10				
			-45	5						
				1						
			_	1						
. /	· OANDY OLAY	551.43		1						
very soft, grag LOAM; satura	y SANDY CLAY			1						
LOAW, Satura		R 2								
			_	_						
				2 5	0.3 P	21				
		547.68	-50	1 -						
End of Boring		047.00	-50	1						
			_	1						
			_							
			_	4						
				-						
			-55	1						
			-55	1						
			_	1						
				1						
			_	1						
				1						
			_	1						
]						
			-60	1	1					

The Unconfined Compressive Strength (UCS) Failure Mode is indicated by (B-Bulge, S-Shear, P-Penetrometer)
The SPT (N value) is the sum of the last two blow values in each sampling zone (AASHTO T206)

BBS, form 137 (Rev. 8-99)

| Company | Comp

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION


Existing Structure: The structure is a 10' x 7' reinforced concrete box culvert constructed circa 1933.


Culvert extension work will be done under staged closures. See Roadway Plans.

Salvage: None.

INDEX OF SHEETS

- 1 General Plan & Elevation
- 2 General Data
- 3 Culvert Removal Details
- 4-5 Single Cell Precast Box Culvert Tapered End Sections
- 6 Connection Collar Details
- 7 Boring Logs





MOSHE L. COHEN 081-008104

Signed: Worke & Color

Dated: 2023-08-16

Illinois Structural Engineer
No. 081-008104
License Expires: 11-30-2024

DESIGN SPECIFICATIONS

2020 AASHTO LRFD Bridge Design Specifications, 9th Edition

LOADING HL-93

<u>DESIGN STRESSES</u> <u>PRECAST UNITS</u>

f'c = 5,000 psi

fy = 65,000 psi (Welded Wire Reinforcement)

FIELD UNITS

f'c = 3,500 psi

fy = 60,000 psi (Reinforcement)

GENERAL PLAN AND ELEVATION
IL RTE. 116 OVER UNNAMED DITCH
F.A.P. RTE. 665 SEC. (140,142)CLV

KNOX COUNTY

STATION 116+94.46

STRUCTURE NO. 048-1006

Kaskaskia Engineering Group, LLC SAMO 15 Induction, Ind

 USER NAME
 =
 DESIGNED
 MLC
 REVISED

 CHECKED
 MMC
 REVISED

 PLOT SCALE
 =
 DRAWN
 MLC
 REVISED

 PLOT DATE
 =
 CHECKED
 MMC
 REVISED

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION


The design fill height for this box shall be determined by the contractor based on field measurements and accepted by the engineer. The precast box culvert sections shall conform to the requirements of ASTM C 1577.

Drain holes shall be provided on exterior culvert walls for each precast box segment with a clear rise greater than 3 ft. The drain hole shall be located within 1/3 of the clear rise of the box culvert, shall not intercept the haunch, and shall conform to the requirements of Article 503.11 of the Standard Specification.

Nonwoven geotextile fabric shall conform to the requirements of Art. 1080.01 of the Standard Specifications. The minimum weight of the fabric shall be 6 ounces per square yard.


Precast concrete box culverts and box culvert end sections shall be backfilled with Porous Granular Embankment in the required excavation areas on the sides of the box culvert from the top of the box culvert to the bottom of the box culvert. This area of PGE is included in the Porous Granular Embankment pay item. The 6-inch thick layer of porous granular material required under the precast concrete box culvert, according to Section 540.06 of the standard specifications, shall also apply to the end sections. Cost of this porous granular material will not be paid for separately but shall be included in the unit price of the work for which it is required.

All exposed concrete edges shall have a standard $\frac{3}{4}$ " chamfer unless noted otherwise. All construction joints shall be bonded.




TOTAL BILL OF MATERIAL

ITEM	UNIT	TOTAL
Porous Granular Embankment	Cu. Yd.	235
Geotechnical Fabric for Ground Stabilization	Sq. Yd.	48
Concrete Removal	Cu. Yd.	61.4
Removal and Disposal of Unsuitable Material for Structures	Cu. Yd.	40
Reinforcement Bars	Pound	3,140
Name Plates	Each	1
Temporary Soil Retention System	Sq. Ft.	475
Box Culvert End Sections, Culvert No. 2	Each	2
Concrete Box Culverts	Cu. Yd.	8.8
Precast Concrete Box Culverts 10' x 7'	Foot	35
Geocomposite Wall Drain	Sq. Yd.	79
Membrane Waterproofing System for Buried Structures	Sq. Yd.	79
Rock Fill	Ton	41
		, and the second



SECTION THRU BARREL

Showing limits of Membrane Waterproofing System for Buried Structures and Geocomposite Wall Drain.





TEMPORARY SOIL RETENTION SYSTEM

(Showing Pay Limits)

The Contractor shall submit a temporary soil retention system design including plan details and calculations for review and acceptance by the Engineer. The Contractor's design shall incorporate all safety and strength requirements, including but not limited to those of IDOT and the Occupational Safety and Health Administration. Variations in the limits of the Temporary Soil Retention System from those shown shall not be paid; plan quantity will be considered total compensation for the amount actually furnished.


STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION






Headwall -2'-0" typ. Span ∖Porous granular

END VIEW



RESTRAINT ANGLE DETAIL



SECTION A-A

(All costs associated with furnishing and constructing the above drain detail will not be measured for payment but shall be included in the contract unit price for the associated work.) (Sheet 1 of 2)

GENERAL NOTES

Box Culvert End Sections shall be constructed according to the requirements of Section 540 of the Standard Specifications except as modified herein. This work will be measured for payment as each, with each end of each culvert being one each. End sections will be paid for at the contract unit price per each for Box Culvert End Sections of the culvert number specified.

Typical box section dimensions, materials, and reinforcement details for Box Culvert End Sections shall be according to the requirements of ASTM C 1577 as required for

the design of the portion of the culvert within the limits of Precast Concrete Box Culverts except as modified herein.

Number of segments shown in Elevation is for example only. Length and number of precast box sections required to construct Box Culvert End Sections shall be determined by the Contractor.

See roadway plans for embankment slope (V:H).


1" Ø anchor rods for the culvert ties shall conform to the requirements of ASTM F1554, Grade 105. Structural steel for tie plate and restraint angle shall conform to the requirements of Article 1006.04 of the Standard Specifications. All components of the culvert tie detail shall be galvanized according to the requirements of AASHTO M 111 or M 232 as applicable. 21/4" x 21/4" x 5/16" plate washers shall be provided under each nut required for the anchor rods. Anchor rods connecting precast sections shall be brought to a snug tight condition followed by an additional 1/2 turn on one of the nuts for anchor rods installed in the walls. Match marks shall be provided on the bolt and nut to verify relative rotation between the bolt and the nut. Holes in the walls for the culvert tie assembly may be drilled using core bits in lieu of using formed holes.

All costs associated with furnishing and installing or constructing the toewall and culvert ties will not be measured for payment but shall be included in the contract unit price for Box Culvert End Sections of the culvert number specified.

Drain holes shall conform to the requirements of Article 503.11 of the Standard Specifications unless noted otherwise.

Nonwoven geotextile fabric shall conform to the requirements of Article 1080.01. The minimum weight of the fabric shall be 6 oz. / sq. yd..

For end sections with traversable pipe grate systems, see grate detail sheet for required modifications.



(Showing end section tie details) 3'-0" Q 11/4" x 21/2" Slotted hole, typ. typ. ± 0 Ф

TIE PLATE DETAIL

SCB-TES

¢ 3" Ø Drain hole→

2-17-2017 DESIGNED - MLC REVISED -Kaskaskia CHECKED - MMC REVISED -DRAWN REVISED PLOT DATE = CHECKED - MMC REVISED -

PLAN

STATE OF ILLINOIS **DEPARTMENT OF TRANSPORTATION**

Ε


Ε

SINGLE CELL PRECAST BOX CULVERT TAPERED END SECTIONS STRUCTURE NO. 048-1006

SHEET 4 OF 7 SHEETS

SECTION COUNTY (140,142)CLV KNOX 38 31 665 CONTRACT NO. 68G66

8/16/2023 4:50:53 PM



SECTION C-C

Optional bonded construction joint typ. As1m/21 typ.

ALTERNATE SECTION D-D

As1m REINFORCEMENT $(in.^2/ft)$ Rise (ft 2 3 5 6 7 10 Ts (in.) 0.19 0.17 0.26 0.21 0.18 0.22 0.26 0.23 0.22 0.33 0.59 0.27 0.28 0.40 0.35 0.43 0.39 0.36 0.34 0.40 0.44 0.39 0.35 0.43 0.40 0.37 0.36 0.48 10 0.55 0.49 0.58 0.54 0.50 0.48 0.45 0.46 0.46 0.61 0.75

(As1m reinforcement based upon welded wire reinforcement conforming to AASHTO M 55 or M 221)

l, DIMENSION

 $#3 \ bar = 2'-0"$ $#4 \ bar = 2'-8''$ $#5 \ bar = 3'-4''$


 $#6 \ bar = 3'-11''$

Alternate Section D-D is provided to allow the Contractor the option of casting the bottom slab of the end section first followed by construction of the sidewalls using conventional forming methods. Shop drawings that detail slab thickness and reinforcement layout shall be submitted to the Engineer for review and approval when using Alternate Section D-D.

11 12

The size and spacing of the v2 bars shall provide a minimum reinforcement area along each face of the walls (in.2/ft.) equal to 1.10*(As1m). v2 bars may consist of #3 thru #6 size reinforcement bars and the longitudinal spacing shall not exceed the lesser of the wall thickness or 8 inches.

Bonded construction joints shall be prepared according to Article 503.09 of the Standard Specifications.




#4 s bars at spacing = Tt (Spacing need not be less than 8") 4-h bars (See Section F-F) HEADWALL ELEVATION (Allow sidewall reinforcement to extend into end of headwall.)

TOEWALL CONSTRUCTION SEQUENCE

1. Perform excavation and construct toewall.

SECTION D-D

- 2. Backfill according to the applicable paragraphs of Article 502.10 of the Standard Specifications and place bedding for precast box culvert end sections.
- 3. Set precast box culvert end section.
- 4. Drill and epoxy grout reinforcement in toewall in accordance with Section 584 of the Standard Specifications.
- 5. Pressure grout voids using non-shrink grout conforming to Section 1024 of the Standard Specifications.
- The Contractor may furnish a precast or cast-in-place toewall. The Contractor shall be responsible for the strength and stability of the precast toewall during handling. Additional lifting points may be required depending upon the length of the toewall or the Contractor may need to modify the design of the toewall for the proposed handling the method.
- ** If soil conditions permit, the sides of the toewall may be poured directly against the soil. The clear cover on the sides of the toewall shall be increased to 3" by increasing the thickness of the toewall.



SECTION E-E

$2-#7 \ h \ bars (S < 8'-0")$ 2-#8 h bars (S ≥ 8'-0") Top and bottom of headwall ¾" "∆" Drip notch full length of span

SECTION F-F

SINGLE


10h -- + 2 - + 21

	SCB-TES		2-17-2017		
	TZ 1 1 • 200 (12.)	M. in St., Suite 100 USER NAME =	DESIGNED - MLC	REVISED -	
1	Kaskaskia 🕮	ie, ramon sazar SITT des strandament com	CHECKED - MMC	REVISED -	
	PROPESSIONAL REGISTRATIONS LICEN Illinois Professional Design Firm 184064	PLOT SCALE =	DRAWN - MLC	REVISED -	
	Professional Engineering Group 20-800	PLOT DATE =	CHECKED - MMC	REVISED -	

STATE OF ILLINOIS **DEPARTMENT OF TRANSPORTATION**

(Sheet 2 of 2)					
CELL PRECAST BOX CULVERT TAPERED END SECTIONS	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
STRUCTURE NO. 048-1006	665	(140,142)CLV	KNOX	38	32
311001011L 110. 0+0-1000			CONTRAC	T NO. 68	G66
SHEET 5 OF 7 SHEETS		ILLINOIS FED. A	ID PROJECT		

8/16/2023 4:50:54 PM



SOIL BORING LOG

Page <u>1</u> of <u>1</u>

Date ___1/23/23

ROUTE	ROUTEFAP 665 (IL 116) DESCRIPTION					Structure boring for culvert	_ LC	GGI	ED BY	Maria	a Rojo	
SECTION _	140 and 142		_ ı	OCAT	ION _	IL 116	east of IL 41, SEC. 27, TWP. 9 N, RN	G . 1 E	, 4 th	PM,		
COLINTY	Vnev Dr			TUOD			ide 40.728821, Longitude -90.37910			A t a	matia	
COUNTY Knox DRILLING METHOD HSA							HSA HAMMER T	YPE -		Auto	matic	
STRUCT. NO	D117+12	_	D E P	B L O	U C S	M O I	Surface Water Elev Stream Bed Elev.	ft ft	D E P	вго	U C S	M O I
BORING NO	. <u>CB-1E</u>		Т	W		S	Groundwater Elev.:		Т	W		s
Station	116+98		Н	S	Qu	Т	First Encounter640.6	ft▼	Н	S	Qu	Т
Offset	20.0 ft LT		/£4\	//CIII	(4-6)	(0/)	Upon Completidrin the borehole		(£4)	(/CII)	(4-6)	(0/)
Ground Su	rface Elev. 657.58	ft	(π)	(/6")	(tsf)	(%)	After Hrs	ft	(ft)	(/6")	(tsf)	(%)
2-inch thick		657.38	_					37.08				
			_	3	1.5 P	24	Medium dense, black weathered COAL; dampRDR 2			11 10 10	NP	32
	RDR 2		_	4	Ů		6	34.58	_			
	FILL		-5	2 3	3.0 P	21	Medium dense to very dense, blue gray SILT, trace gravel; dampRDR 2Weathered SHALE BEDROCK		-25	4 6 7	3.3 S	15
0-#		651.58		2						50/5	NP	15
	um stiff, dark brown to CLAY, trace organic p Buried TOPSOIL RDR 2		_	2 2 2	0.4 B	35		-		30/3	INF	15
			_						_	FOIF	ND	4.2
				1	0.5	35		528.58		50/5	NP	13
			-10	2	0.5 P	33	End of Boring					
			-10	1					-30			
		646.58	_						_			
Stiff gray an	nd brown CLAY to	040.00		-								
	/, trace gracel; damp		_	1	1.6	30			_			
	RDR 2			3	В							
				3								
		644.08										
	stiff, light gray and to											
	SILTY CLAY, trace ents; damp to wet		_	3	1.2	23			_			
	hly Weathered SHALE		-15	3 5	S				-35			
	BEDROCK		_									
	RDR 2			2	1.4	25						
	silt seams			3	1. 4 B	25			_			
	siit seams	7		2	-							
			_	-					_			
				1								
	silt seams		_	5	2.1	17			_			
	3 252.110			6	В							
			20	9					40			

The Unconfined Compressive Strength (UCS) Failure Mode is indicated by (B-Bulge, S-Shear, P-Penetrometer)
The SPT (N value) is the sum of the last two blow values in each sampling zone (AASHTO T206)

BBS, form 137 (Rev. 8-99)



SOIL BORING LOG

Page <u>1</u> of <u>1</u>

Date ___1/23/23_


ROUTEF	FAP 665 (IL 116)	(IL 116) DESCRIPTION				Structure boring for culvert		_ LOGGED BY Maria Rojo					
SECTION 140 and 142							3. 1 E, 4 th	PM,					
COUNTY Knox DRILLING METHOD HSA HAMMER TYP								EAutomatic					
BORING NO Station Offset	117+12 CB-2E 116+92 17.0 ft RT Ince Elev. 662.81	- - !	D B L D W S S (/6")	U C S Qu (tsf)	M O I S T	Surface Water Elev.	ft P Ft.▼ H	B L O W S	U C S Qu (tsf)	M O I S T			
6-inch thick, br	own Gravelly	662.31				64	I1.81	8					
Medium stiff to and gray SILT	Shoulder very stiff, brown Y CLAY to SILTY race gravel; damp RDR 2 FILL-	_	2 2 2 1	1.3 P	32	Medium dense to very dense, blue gray SILT, trace gravel; damp to wetWeathered SHALE BEDROCKRDR 2		7 9 11	NP	13			
		_	2 -5 2 2	2.5 P	22		-25	8 14 13	NP	11			
		 654.31	2 2 2 2	0.4 B	31		_	8 7 16	NP	15			
trace gravel; da	lack SILTY CLAY, amp to moist Buried TOPSOIL RDR 2		1 10 2 2	1.0 B	32		-30	30 39 41	NP	13			
Very soft, gray	RDR 1 -weighted hammer	_	0 0	0.3 P	37		_						
Very stiff, gray gravel; damp	SILTY CLAY, traceRDR 2	549.31 — — 546.81	2 15 4	2.5 S	32		-35	22 37 50/4	NP	12			
trace gravel, da	, blue gray SILT, amp Weathered SHALE BEDROCK RDR 2		2 4 5	NP	18	auger refusal End of Boring	26.31 	50/4	NP	18			
Medium dense COAL, damp to	, black weathered	<u></u>	10 20 6	NP	29		-40	-					

The Unconfined Compressive Strength (UCS) Failure Mode is indicated by (B-Bulge, S-Shear, P-Penetrometer) The SPT (N value) is the sum of the last two blow values in each sampling zone (AASHTO T206)

BBS, form 137 (Rev. 8-99)

| See Name | Designed - MLC | Revised - Machine - Machin

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION



5-30-18 CHANGE B CURB TO CC&G

07-16-19 SPELLING CORRECTIONS

R.D.

R.D.

R.D.

03-07-11 ADDED DETAIL SHOWING PLAN VIEW

08-10-12 REVISED CURB "B" AND AGGREGATE

07-15-15 ADDRESSED SHOULDER INLET CURB

01-26-17 REVISED

GENERAL NOTES: GUARDRAIL AGGREGATE EROSION CONTROL

- 1. This work shall consist of grading as needed, furnishing and installing geotextile fabric and staples, and furnishing, placing and shaping crushed aggregate around and behind Steel Plate Beam Guardrail posts in accordance with Plan Details.
- 2. Before placing the aggregate and the Geotextile Fabric, weeds and grass shall be removed from the area to be covered.
- 3. After the area has been prepared, and in a dry condition, the Geotextile fabric shall be placed with a 12(300) minimum overlap. A knife cut for guardrail post installation is necessary.
- 4. The aggregate shall be deposited, compacted and shaped by either mechanical or hand methods, in a manner reasonably true to line and grade.
- 5. The Contractor shall have the option of placing the guardrail before or after the Geotextile Fabric and Aggregate are in place. If the guardrail is placed after the Geotextile Fabric and Aggregate, then any voids must be filled and the aggregate returned to line and grade.

All dimensions are in inches (millimeters)

SECTION

(140,142)CLV

COUNTY

KNOX

CONTRACT NO. 68G66

38 35


unless otherwise noted.

SHT. 1 OF 2
CADD STD. 630101-D4
FED. ROAD DIST. NO. | ILLINOIS FED. AID PROJECT

- 6. Materials shall meet the following requirements:
- A. The crushed aggregate shall be CA1 gradation in accordance with Article 1004.01(c) of the Standard Specifications.
- B. The Geotextile Fabric shall be nonwoven fabric in accordance with Article 1080.02 of the Standard Specifications.

GUARDRAIL EROSION CONTROL TREATMENTS


NOT TO SCALE





STATE OF ILLINOIS

DEPARTMENT OF TRANSPORTATION

R.D.








PLAN VIEW

APPROACH SLAB OR SHOULDER PLACEMENT




SECTION A-A

TYPICAL SECTION WITH BRIDGE APPROACH CURB

All dimensions are in inches (millimeters) unless otherwise noted.

rate Section County Hotal one	NO.
GUARDRAIL ERUSION CONTROL TREATMENTS 665 (140,142)CLV KNOX 38 30	36
SHT. 2 OF 2 CONTRACT NO. 68G6	i6
CADD STD. 630101-D4 FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT	
iU	JARDRAIL EROSION CONTROL TREATMENTS RTE. SECTION COUNTY SHEETS NO. 38 3 SHT. 2 OF 2 CONTRACT NO. 68G6 CONTRACT NO. CONTRACT NO. 68G6 CONTRACT NO. C



FLUSH PAVED MEDIAN: TWO-WAY LEFT TURN LANE WITH ONE-WAY LEFT TURN LANE AT SIGNALIZED INTERSECTION

TYPICAL PAVEMENT MARKING LEGEND

(Note: This is a District Standard Legend. Some elements may not apply to specific project.)

- 1) 4(100) Solid (Yellow)
- (2) 4(100) Solid (White)
- 2-6(150) Crosswalk @ 6'-6" (2m)min C.-C. (White)
 2-8(200) Crosswalk @ 6'-6" (2m)min C.-C. (White) (When traffic signals are present.)
- 4 6(150) Skip-Dash (White) 10' (3.05m) (9.14m) (3.05m) (See Special Note 1)
- 5) 8(200) Solid (White)
- (6) 12(300) Diagonal (White) (Item (6) is shown on Std. 780001)
- (7) 24(600) Stop Bar (White)
- 8 Letters & Arrows (See Std. 780001 and Special Notes 2 & 3)
- 9 4(100) Skip-Dash (Yellow) 10' 30' 10' (See Special Note 1)
- (1) 12(300) Diagonal (Yellow) (See Table A) 45° (1) 4(100) Double Solid (Yellow) 11(280) C.-C. See Table A

SPECIAL NOTES

- Skip-Dash markings will be centered between both ends of city blocks and shall be placed in alignment transversely across the pavement.
- 2. The following shall apply to arrows located in one-way left turn lanes:
 - A. A minimum of two (2) arrows is required.
 - B. The maximum spacing between arrows is 80′ (24 m).
 - C. Arrows shall be evenly spaced if three (3) or more are required.
- 3. The following shall apply to arrow pairs located in two-way left turn lanes:
 - A. A minimum of two (2) arrow pairs is required.B. The maximum spacing between arrow pairs
 - C. Arrow pairs shall be evenly spaced if three (3) or more are required.

NOT TO SCALE

D. The spacing between Bi Directional Left Turn Arrows is 33' (10 m).

GENERAL NOTES


- 1. Refer to State Standard 780001 for additional Pavement Markings including letters & arrows.
- See Plans for Pavement Markings adjacent to curbed islands and medians, and through lane reductions.
- 3. Refer to Article 780.13 for letter, number and symbol areas (sq. ft.)
- 4. Areas are grooved 1" beyond each edge for the following symbols: Through Arrow= 14.8 sq. ft.
 Large Left or Right Arrow= 21.9 sq. ft.
 2 Arrow Combination Left (or Right) and Through= 34.9 sq. ft.
 Wrong Way Arrow= 29.5 sq. ft.
 Railroad Crossing Symbol= 69.8 sq. ft.
 (For further information, refer to BDE Special Provision: Grooving for Recessed Pavement Markings)

01-01-97 RENUM. F-8.03, NEW REVISION BOX T.P. 10-16-06 REVISED TO 2007 SPEC. 2/29/16 ADD ED GROOVING AREAS R.D. 10-97 CORRECT BI DIRECTIONAL DIMENSION J.A. 07-16-19 SPELLING CORRECTIONS R.D. 08-02 ADD CROSSWALK DMNS. WITH T.S. M.A. T.P. 10-16-06 REVISED TO 2007 SPEC. 2/29/16 ADDED GROOVING AREAS R.D.

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION


is 200' (61 m).


TYPICAL PAVEMENT MARKINGS



FLUSH PAVED MEDIAN: RESTRICTED LEFT TURN LANE

TABLE A RECOMMENDED SPACING BETWEEN DIAGONAL LINES





MEDIAN INTRODUCTION - WIDTH TRANSITIONS

All dimensions are in inches (millimeters) unless otherwise noted.

		NOT TO SCALE CADD STD. 780001	-D4 FED. R	OAD DIST. NO. ILLINOI	S FED. AID PROJECT	. NO. 00000
	DEPARTMENT OF TRANSPORTATION	SHI 2.0		(= .0,= .=,==	CONTRAC	T NO 69066
	STATE OF ILLINOIS	TYPICAL PAVEMENT MARKINGS	665	(140,142)CLV	KNOX	38 38
			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEET SHEETS NO.