

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE			
				80% FEDERAL 20% STATE	80% FEDERAL 20% STATE	80% FEDERAL 20% STATE	80% FEDERAL 20% STATE
				ROADWAY 0004	BRIDGE 0014	LANDSCAPE 0031	TRAINEES 0042
				URBAN	URBAN	URBAN	URBAN
78300100	PAVEMENT MARKING REMOVAL	SQ FT	672	672			
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	52	52			
81012600	CONDUIT IN TRENCH, 2" DIA., PVC	FOOT	639	639			
81200120	CONDUIT EMBEDDED IN STRUCTURE, 2" DIA., GALVANIZED STEEL	FOOT	150	150			
81300320	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 8"X8"X6"	EACH	4	4			
81702500	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 4/C NO. 6	FOOT	939	939			
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	639	639			
• Z0010605	CLEANING DRAINAGE SYSTEM	L SUM	1	1			
• Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1			
• Z0015550	DEBRIS REMOVAL	CU YD	16	16			
• Z0026407	TEMPORARY SHEET PILING	SQ FT	258		258		
• Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	1	1			
• Z0030350	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	EACH	1	1			
• Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	228	228			
• Z0033028	MAINTENANCE OF LIGHTING SYSTEM	CAL MO	6	6			
• Z0046304	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	217		217		
• Z0062456	TEMPORARY PAVEMENT	SQ YD	357	357			
• Z0065700	SLOPE WALL REPAIR	SQ YD	62		62		
• Z0076600	TRAINEES	HOOR	1000				1000
B2006268	TREE, SYRINGA RETICULATA (JAPANESE TREE LILAC), 7' HEIGHT, CLUMP FORM, BALLED AND BURLAPPED	EACH	6			6	
C2C09918	SHRUB, SPIREA X BUMALDA GOLDFLAME (GOLD FLAME BUMALD SPIREA), 18" HEIGHT, CONTAINER	EACH	30			30	
K0012980	PERENNIAL PLANTS, ORNAMENTAL TYPE, QUART POT	UNIT	0.20			0.20	
K0012990	PERENNIAL PLANTS, ORNAMENTAL TYPE, GALLON POT	UNIT	2.15			2.15	
• X0323491	SLOPE WALL CRACK SEALING	FOOT	217		217		
• X0324534	REMOVE AND REINSTALL LIGHT POLES	L SUM	1	1			
• X0326243	SEDIMENT CONTROL, SILT CURTAIN	L SUM	1	1			
• X2070304	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	78		78		
• X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	1	1			
• X6310176	TRAFFIC BARRIER TERMINAL, TYPE 2 (SPECIAL)	EACH	1	1			
• X6310218	TRAFFIC BARRIER TERMINAL, TYPE 6 (SPECIAL)	EACH	1	1			
• X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1			
• X7030030	WET REFLECTIVE TEMPORARY TAPE TYPE III, 4 INCH	FOOT	4410	4410			
• X7030045	WET REFLECTIVE TEMPORARY TAPE TYPE III, 8 INCH	FOOT	384	384			
• X7030050	WET REFLECTIVE TEMPORARY TAPE TYPE III, 12 INCH	FOOT	344	344			
K0005200	ANNUAL PLANTS, BEGONIAS, 1 QUART	UNIT	60			60	
C2C06963	SHRUB, ROSA BONICA (BONICA MEIDILAND ROSE), 3-GALLON	EACH	30			30	

Δ Non-participating - 100% State
• DENOTES SPECIAL PROVISION

FILE NAME = ...Roadway\DI-62101-sht-S003.dgn	DESIGNED - MC	REVISED -	 800 W FLATON ST CHICAGO, ILLINOIS 60601-1259 TEL 312 454 9100 FAX 312 558 1217 WEB www.sepstein.com	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES		SCALE: N/A	SHEET NO. 3 OF 3 SHEETS	STA. TO STA.	F.A.U. RTE. 1257	SECTION 104RB-R	COUNTY LAKE	TOTAL SHEETS 54	SHEET NO. 5
PLOT TIME = 3:49:54 PM	DRAWN - MC	REVISED -								CONTRACT NO. 62102				
PLOT DATE = 6/23/2011	CHECKED - TRP	REVISED -								ILLINOIS FED. AID PROJECT				
	DATE - 06/24/2011	REVISED -												

Rev. 9-13-11

Rev.