


HEAVY DUTY
MAT'L ASTM A48 CL35

MACHINED BEARING SURFACE COVER WT: 125 LBS (56.7 kg)

STORM COVER DETAIL




KOR-N-TEE CONNECTOR OR APPROVED EQUAL

NOTES:

- . THE HOFFMAN ESTATES DEPARTMENT OF PUBLIC WORKS 847 490-6800 AND THE ENGINEERING DIVISION 847 252-5800 SHALL BE NOTIFIED BEFORE THE COMMENCEMENT OF WORK AND WHEN THE PIPE IS EXPOSED.
- 2. THE CONNECTION SHALL BE BACKFILLED COMPLETELY TO WITHIN SIX INCHES OF THE GROUND SURFACE WITH CA-6, CRUSHED STONE OR GRAVEL.
- 3. ONLY A PROFESSIONAL CONTRACTOR SHALL INSTALL THE CONNECTOR ACCORDING TO MANUFACTURERS REQUIREMENTS. THE PUBLIC WORKS DEPARTMENT IS NOT AVAILABLE TO ASSIST IN THE DIRECT CONNECTION TO THE STORM SEWER.
- KOR-N-TEE SEWER CONNECTORS, PART NO. 006-5 THRU 9, OR APPROVED EQUAL.
- 5. EXISTING PIPE SHALL BE CORED ONLY TO GAIN ACCESS.

<u>DIRECT CONNECTION TO</u> STORM SEWER DETAIL



HEAVY DUTY
MAT'L ASTM A48 CL35
MACHINED BEARING SURFACE
COVER WT: 125 LBS (56.7 kg)


WATER COVER DETAIL

1 1/2" (38.1 mm) 1 ½" (38.1 mm) LETTERS (RECESSED FLUSH) 0000 SANITARY (SEWER) 2 1/2" (63.5 mm) 0000 (26.6 mm) (38.1 mm) 22 3/4" DIA CONCEALED PICKHOLE DETAIL (44.5 mm) (577.9 mm) +.000' .180" -.*005** +.000 -.005" (6.1 mm) GROOVE DETAIL

HEAVY DUTY
MAT'L ASTM A48 CL35
MACHINED BEARING SURFACE
COVER WT: 125 LBS (56.7kg)

MANHOLE COVER WITH GROOVED GASKET SEAL & CONCEALED PICKHOLES TO REDUCE SURFACE WATER INFLOW.

SANITARY COVER DETAIL



POST NOTES: EACH POST SHALL BE SET IN CONCRETE MIN. 42" DEPTH

WOOD NOTES:

ALL WOOD SHALL BE CEDAR

GENERAL NOTE:

CONTRACTOR TO SUBMIT SHOP DRAWING OF PROPOSED MATERIAL AND SAMPLES OF TYPICAL POST AND RAIL FOR APPROVAL PRIOR TO INSTALLATION

3-RAIL SPLIT RAIL FENCE DETAIL

FILE NAME =	DESIGNED —	REVISED —
DETAILSH.DWG	DRAWN	REVISED
	CHECKED	REVISED —
	DATE —	REVISED —



VILLAGE OF
HOFFMAN ESTATES
1900 Hassell Road, Hoffman Estates, IL 60169
Phone Number: 847 252-5800

Higgins Road Bicycle and Pedestrian Project
Village Detail Sheet

SCALE: NONE | SHEET NO. 1 OF 1 SHEETS | STA. TO STA.

COMB. C&G REMOVAL

2'

DEPRESS CURB PER
STANDARD 424001 TYPE B
AND STANDARD 606001

COMB. C&G NOTED ON PLANS

PCC SIDEWALK APPROACH (TYP)

PROPOSED DEPRESSED CURB & GUTTER EXIST. CURB & GUTTER NOT DEPRESSED

<u>TYPICAL PCC SIDEWALK</u> <u>APPROACH FOR BIKE PATH</u>