



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

September 13, 2022

SUBJECT Various Routes
Project HSIP-761C(975)
Section Dist 8 Guardrail 2024-2
Madison & Jersey Counties
Contract No. 76R79
Item No. 5, September 23, 2022 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised Schedule of Prices.
2. Revised page i of the Table of Contents.
3. Revised page 7 of the Special Provisions.
4. Revised sheets 1 and 3-4 of the plans.
5. Add sheets 6A and 11A of the plans.

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

MTS

TABLE OF CONTENTS

LOCATION OF PROJECT	1
DESCRIPTION OF PROJECT	1
SUBMITTAL OF EEO/LABOR DOCUMENTATION	2
GUARDRAIL REMOVAL AND REPLACEMENT	4
MOBILE BARRIER TRAILER	4
REMOVE IMPACT ATTENUATORS, NO SALVAGE.....	5
TRAFFIC BARRIER TERMINAL, TYPE 1	5
TRAFFIC CONTROL PLAN	6
TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	6
STATUS OF UTILITIES TO BE ADJUSTED	7
TRAFFIC BARRIER TERMINAL TYPE 6A (MODIFIED).....	7
COMPENSABLE DELAY COSTS (BDE).....	8
CONSTRUCTION AIR QUALITY – DIESEL RETROFIT (BDE).....	11
DISADVANTAGED BUSINESS ENTERPRISE PARTICIPATION (BDE)	13
STEEL COST ADJUSTMENT (BDE).....	21
SUBCONTRACTOR AND DBE PAYMENT REPORTING (BDE)	23
SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE)	24
TRAINING SPECIAL PROVISIONS (BDE)	24
IDOT TRAINING PROGRAM GRADUATE ON-THE-JOB TRAINING SPECIAL PROVISION.....	27
WEEKLY DBE TRUCKING REPORTS (BDE).....	29
WORK ZONE TRAFFIC CONTROL DEVICES (BDE)	29
WORKING DAYS (BDE)	31



STATUS OF UTILITIES TO BE ADJUSTED

NO UTILITIES TO BE ADJUSTED

The above represents the best information of the Department and is only included for the convenience of the bidder. The applicable provisions of Sections 102 and 103 and Articles 105.07 and 107.20 of the Standard Specifications for Road and Bridge Construction shall apply.

If any utility adjustment or removal has not been completed when required by the Contractor's operation, the Contractor should notify the Engineer in writing. A request for an extension of time will be considered to the extent the Contractor's operations were affected.

TRAFFIC BARRIER TERMINAL TYPE 6A (MODIFIED)

Description This work shall consist of furnishing and erecting a Traffic Barrier Terminal, Type 6A (Modified), the field adjustments of guardrail lengths, drilling of mounting holes, regalvanizing of all exposed metal surfaces, and any other items needed to complete the work as shown on the plans. This work shall conform to the application portion of Section 631 of the Standard Specifications and Standard 631032 of the highway standards.

This work shall also include the shop manufacturing of the GUARDRAIL CONNECTION PLATE ASSEMBLY as shown in the plan details.

The terminal shall be installed according to the manufacturer's specifications and shall include all necessary transitions between the terminal and the items to which it is attached.

All bolts, nuts, block-outs, galvanizing, or any other items needed to complete this work shall be included, and no other compensation will be allowed.

Method of Measurement The method of measurement shall be in accordance with Article 631.12 of the Standard Specifications.

Basis of Payment This work will be paid for at the contract unit price per EACH for TRAFFIC BARRIER TERMINAL TYPE 6A (MODIFIED).

