\circ

0

0

0

STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION

| RTE. | SECTION | COUNTY | SHEETS | NO. | | 74 | (10-7)BR | CHAMPAIGN | 20 | 1 | | ILLINOIS | CONTRACT NO. 70G16

FOR INDEX OF SHEETS, SEE SHEET NO. 2 FOR SUMMARY OF QUANTITIES SEE SHEET NO. 3

TRAFFIC DATA

SN 010-0180 over FAI-74 and carrying TR 258

Leg "A" Leg "B"

2022 ADT = 28,700 75

PV % = 72 10%

SU % = 3.20%

MU % = 24 70%


FUNCTIONAL CLASSIFICATION
Interstate Local

Leg "A" is 1-74 under SN 010-0180 Leg "B" is TR 258 over SN 010-0180

PROPOSED HIGHWAY PLANS

FAI ROUTE 74 (I-74)
SECTION (10-7)BR
BRIDGE REMOVAL / DEMOLITION
CHAMPAIGN COUNTY

C-95-059-22 AT TR258 2 MILES WEST OF ST. JOSEPH



GROSS LENGTH = 32 FT. = 0.006 MILE

NET LENGTH = 32 FT. = 0.006 MILE

N A S

FULL SIZE PLANS HAVE BEEN PREPARED USING STANDARD
ENGINEERING SCALES, REDUCED SIZED PLANS WILL NOT

CONFORM TO STANDARD SCALES. IN MAKING MEASUREMENTS ON REDUCED PLANS, THE ABOVE SCALES MAY BE USED.

J.U.L.I.E.
JOINT UTILITY LOCATION INFORMATION FOR EXCAVATORS
1-800-892-0123 OR 811
ST. JOSEPH TOWNSHIP

PROJECT ENGINEER: RYAN CARROLL SQUAD LEADER: SAMUEL MEGLI DESIGNER: ERIC HOY PHONE NUMBER: 217–465–4181 CONTRACT NO. 70G16

P-95-018-22



STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUBMITTED

6/29

2022

Versil Q. Darrett Swa

REGIONAL ENGINEER

August 19, 2022

ENGINEER OF DESIGN AND ENVIRONMENT

August 19, 2022

DIRECTOR OF HIGHWARS PROJECT IMPLEMENTATION

PRINTED BY THE AUTHORITY OF THE STATE OF ILLINOIS

INDEX OF SHEETS

DESCRIPTION	SHE	ET	NO.
COVER	1		
INDEX OF SHEETS, GENERAL NOTES, LIST OF STANDARDS & COMMITMENTS	2		
SUMMARY OF QUANTITIES	.3		
EXISTING TYPICAL SECTIONS	4		
PLAN SHEET	5		
TRAFFIC CONTROL AND PROTECTION	6	to	7
GENERAL PLANS & ELEVATION S.N. 010-0180	8		
GENERAL NOTES AND BILL OF MATERIAL S.N. 010-0180	9		
S.N. 010-0180 EXISTING STRUCTURE PLANS	10	to	17
D5 DETAIL 70103710 TRAFFIC CONTROL FOR RAMPS (PARTIAL AND FULL CLOSURES)	18		
D5 DETAIL /02000000 TRAFFIC CONTROL AND PROTECTION DEVICES (ROAD AND SIDEROAD/STREET CLOSJRES)	19		
D5 DETAIL X7011005 TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR (UTILIZING ENTRACE AND EXIT RAM	PS) 20		

LIST OF STANDARDS

STANDARD NO.	<u>DESCRIPTION</u>
000001-08	STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
001006	DECIMAL OF AN INCH AND OF A FOOT
701400-11	APPROACH TO LANE CLOSURE, FREEWAY/EXPRESSWAY
701401-13	LANE CLOSURE, FREEWAY/EXPRESSWAY
701428-01	TRAFFIC CONTROL, SETUP AND REMOVAL, FREEWAY/EXPRESSWAY
701451-05	RAMP CLOSURE FREEWAY/EXPRESSWAY
701901-08	TRAFFIC CONTROL DEVICES
720001-01	SIGN PANEL MOUNTING DETAILS
720006-04	SIGN PANEL ERECTION DETAILS
720011-01	METAL POSTS FOR SIGNS, MARKERS AND DELINEATORS

GENERAL NOTES

G.N.-100A

ELECTRONIC FILES AND/OR ELECTRONIC SURVEY INFORMATION INCLUDING CADD FILES WILL NOT BE AVAILABLE TO THE CONTRACTOR.

G.N.-105.09A ALL ELEVATIONS SHOWN IN THE PLANS ARE BASED ON NORTH AMERICAN VERTICAL DATUM OF 1988. (NAVD 88)

COMMITMENTS

THERE ARE NO COMMITMENTS FOR THIS CONTRACT

USER NAME = Leslie.Hoy	DESIGNED -	REVISED -
	DRAWN -	REVISED -
PLOT SCALE = 40.0000 / in.	CHECKED -	REVISED -
PLOT DATE = 6/28/2022	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

\ildot-pw.bentley.com:PWIDOT\Documents\IDOT Offices\District 5\Projects\D570G16\CADData\CA

LOCATION OF WORK:

FAI 74 (I-74) INTERSTATE

RURAL

FUNDING BREAKOUT: CONSTRUCTION TYPE CODE: CHAMPAIGN COUNTY 100% STATE 0044

	CODE NO.	ITEM	UNIT	TOTAL QUANTITY	S.N.010-0180 QUANTITY
	50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	1	1
			_		
	50157300	PROTECTIVE SHIELD	SQ YD	404	404
			_		
	67100100	MOBILIZATION	L SUM	1	1
	70107025	CHANGEABLE MESSAGE SIGN	CAL DA	 	28
	70107025	CHANGEABLE MESSAGE STON	CAL DA		28
	70200100	NIGHTTIME WORK ZONE LIGHTING	L SUM	1	1
	X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1
	Z0016702	DETOUR SIGNING	L SUM	1	1
			_		
			_		
			_		
			_		
* DE	NOTES SPECIALTY	ITEM			

 USER NAME
 = Leslie.Hoy
 DESIGNED
 REVISED

 DRAWN
 REVISED


 PLOT SCALE
 = 40.0000 '/ in.
 CHECKED
 REVISED


 PLOT DATE
 = 6/28/2022
 DATE
 REVISED


STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

IDOL OTTRES(DISTIRE 3/FLU)ects(D3/0010)twDDdtajtwD3Tleets(D3/0010-5)T

EL: \$MODELNAME\$ NAME: pw://lidot.pw/bentley.com.pv//IDO








SCALE: N/A

SHEET 1 OF 2 SHEETS STA.

PLOT DATE = 6/28/2022

DATE



USER NAME = Leslie.Hoy	DESIGNED -	REVISED -
	DRAWN -	REVISED -
PLOT SCALE = 40.0000 / in.	CHECKED -	REVISED -
PLOT DATE = 6/28/2022	DATE -	REVISED -

STATE OF ILLINOIS **DEPARTMENT OF TRANSPORTATION**


SECTION TRAFFIC CONTROL AND PROTECTION (10-7)BR (TEMPORARY DETOUR) SHEET 2 OF 2 SHEETS STA.

CHAMPAIGN 20 7 CONTRACT NO. 70G16


SCALE: N/A

Existing Structure: S.N. 010-0180 was built in 1959 as FAI Route 74, Section 10-7HB. It was built as a 4 simple span P.P.C. "I" beam structure. The substructure consists of open stub abutments and multiple round columned piers. The abutments are founded on one row of piles with every other battered. The piers are supported by spread footings. The Back to Back dimension measures 184'-6" while the Out to Out width measures 32'-6". The existing structure has a 9" curb and a 2'-0" saftey walk. The minimum vertical under clearance is 14'-9". Township Road 258 is currently closed and FAI 74 traffic will be detoured during construction.

Salvage: One 58 foot steel W36x150 girder installed on the deck of the existing structure to support the damaged beam of the existing structure shall be salvaged. See Special Provisions.



ELEVATION



GENERAL PLAN & ELEVATION

TR 258 OVER

F.A.I. RTE 74-SECTION 10-7HB

CHAMPAIGN COUNTY

STATION 645+81

STRUCTURE NO. 010-0180

USER NAME = Leslie.Hoy	DESIGNED -	REVISED -		GENERAL PLAN & ELEVATION			F.A.I. RTF	SECTION	COUNTY	TOTAL SHEET	
	DRAWN -	REVISED -	STATE OF HUNDIS		74	(10-7)BR	CHAMPAIGN	20 8			
PLOT SCALE = 40.0000 / in.	CHECKED -	REVISED -	DEPARTMENT OF TRANSPORTATION	S.N. 010–0180					CONTRACT	NO. 70G16	
PLOT DATE = 6/28/2022	DATE -	REVISED -		SCALE: N/A SHEET 1 OF 10 SHEETS STA		STA.	TO STA.		ILLINOIS FED. A	ID PROJECT	

STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION

GENERAL NOTES

Removal of Existing Superstructures includes all structure components from face to face of abutments above the abutment seats and pier caps. The handrail and guardrail terminals attached to the deck are also included in this item.

The Contractor is advised that the existing PPC I beams are in a deteriorated condition with reduced load carrying capacity. It is the Contractor's responsibility to account for the conditions of the beams when developing construction procedures for removal of the Superstructure.

If the Contractor's procedures for existing PPC I beam removal involves the placement of heavy equipment on the existing deck, a detailed procedure shall be provided which includes calculations, sealed by an Illinois Licensed Structural Engineer, verifying the adequacy of the existing structure, for the proposed loads. Cost included with Removal of Existing Superstructures. See Section 501 of the Standard Specifications.

Protective Shield is included for protection of live vehicular traffic during any saw cutting activities only and for protection of the roadway during Superstructure removal with FAI 74 closed. If the Contractor's removal procedures show this can be accomplished during FAI 74 closures and the roadway protected by other means, the protective shield may be omitted. The Contractor is responsible for any damage to the FAI 74 roadway.

Existing Structure Information is included with the Contract Letting Documents under Plans and Special Provisions in the "Additional Information" folder.

INDEX OF SHEETS

- 1. General Plan and Elevation
- 2. General Notes & Bill of Material
- 3. 10. Existing Structure Plans


TOTAL BILL OF MATERIAL

ITEM	UNIT	QUANTITY
Removal of Existing Superstructures	Each	1
Protective Shield	Sq. Yd.	404


STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION


SCALE: N/A

| F.A.I. | SECTION | COUNTY | SHEET | NO. 70 | SHEET | STA. | TO STA. | SHEET | SHEET



MODEL: \$MODELNAMES FILE NAME: overvillet.com beenley con





*4 Cables Equally Spaced **A Cables Equally Spaced **Drill 1"Ø holes in curb for hanger cables. **Drill 1"Ø holes in curb for hanger cables. **A Cables Support Beam **A Cables Equally Spaced **Pier 2** **Pier 3** **A Cables Equally Spaced **A Cables in curb for hanger cables.

WEST FASCIA LONGITUDINAL SECTION TEMPORARY SLAB SUPPORT SYSTEM

Note.


Blocking and any necessary shims shall be placed under the steel beam at all cable locations after the steel beam has been set on the end blocking and allowed to deflect under its own weight.


* Cables may need to be adjusted at locations where concrete has spalled off.

SECTION AT END BLOCKING

DESIGNED - VHV	EXAMINED	Timoti A And at	DATE - JANUARY 21, 2020		SUPPORT DETAILS	F.A.I. SECTION	COUNTY TOTAL SHEET SHEETS NO.
CHECKED - ATH	_	ENGINEER OF STRUCTURAL SERVICES		STATE OF ILLINOIS	SN 010-0180	74	CHAMPAIGN
DRAWN - daburdell	PASSED	& Carl Program	REVISED -	DEPARTMENT OF TRANSPORTATION	2M 010-0190		CONTRACT NO. 21I503
CHECKED - VHV ATH	_	ENGINEER OF BRIDGES AND STRUCTURES	REVISED -		SHEET NO. 2 OF 2 SHEETS	ILLINOIS FED	D. AID PROJECT


JSER NAME = Leslie.Hoy DESIGNED -REVISED SECTION COUNTY S.N. 010-0180 EXISTING STRUCTURE PLANS STATE OF ILLINOIS DRAWN REVISED CHAMPAIGN 20 11 (10-7)BR (FOR INFORMATION ONLY) CHECKED REVISED **DEPARTMENT OF TRANSPORTATION** CONTRACT NO. 70G16 PLOT DATE = 6/28/2022 SCALE: N/A SHEET 4 OF 10 SHEETS STA. TO STA. REVISED DATE






CROSS SECTION SPAN 2

(Looking South) Note A: PPC I-Beams to be repaired as detailed.



BEAM ELEVATION AT REPAIR A

(Looking East) Hatched areas indicate areas to be repaired.



SUGGESTED FORM DETAIL

PRELOADING FOR PPC I-BEAM REPAIRS

REPAIR PROCEDURES FOR BEAMS 1 & 6 (SPAN 2)

(Service Moment) Location * Moment Span From Distance (kip-ft) 1 C Pier 2 24'-9" ±465

* The magnitude of the moments to be applied were obtained by assuming a simple span behavior between the fascia and first interior beams (2002 AASHTO 3.23.2.3.1.2) for Live Load + Impact. The effect of the proposed preload system shall be determined using the same assumption.

6 @ Pier 2 | 24'-8" | ±465


1. The damaged area of the beam shall be cleaned of all loose and spalled concrete, and sealant. Hand tools shall be used for the removal of concrete adjacent to the prestressing strands. While a 15 pound chipping hammer may be used away from prestressing strands, extreme care shall be taken not to damage the exposed prestressing strands. Any exposed portions of the strands shall be sandblasted.


2. Using the same tools, remove the existing concrete to sound concrete along the edges of the damaged area to a depth of I'' min. to $I_Z^{I''}$ max. The edges shall be saw cut 34" deep or less.


3. Power driven pins as shown in Detail A shall be placed at 9" alternate centers along damaged length of beam at locations shown in Detail A. Use wire ties in areas where the strands are exposed as shown in Detail A. Place I" x 1" x 18 gauge welded wire fabric in repair areas and attach it to the pins or strands with wire ties. The clearance between the finished surface of the new concrete and the welded wire fabric shall be 1" minimum. All beams involved in this work shall be rebuilt to their original dimensions.

4. All surfaces of the existing concrete in the areas to be repaired shall be prepared in accordance with Art. 503.09 (b) of the Standard Specs. The concrete beam to be repaired must be at a temperature of at least 50° F. or higher.

5. The repair shall be made using a concrete meeting all the requirements specified in Section 1020 of the Standard Specifications for Class PS Concrete for precast prestressed concrete members, except the maximum size of the aggregate shall be $\frac{1}{2}$ ". Place the lower form on the bottom of the beam and compact by vibrating (or other approved methods) the concrete mix into the voids. After accessible voids have been filled and compacted, the top vertical form shall be raised into position and the remaining voids filled and compacted. The sloping upper surface shall be finished to the configuration of the existing PPC I-Beam flange.







Beams 1 & 6, Span 2

SCALE: N/A


The cost of Preloading, concrete removal, Class PS Concrete, power driven pins, wire ties, wire mesh, epoxy bonding agent, Epoxy Crack Sealing and all other work required to perform repairs on Beams 1 & 6 in Span 2 shall be included in the cost of PPC I-Beam Repairs.


CHECKE DAB ORAWN baliva PASSED ACM Proy REVISED STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION SHEET 2 OF 2 SHEETS ACM Proy REVISED ILLINOIS FED. AID PROJECT ILLINOIS FED. AID PRO			2025 2 2025		PPC I-BEAM REPAIR DETAILS	F.A.I. SECTION	ION COUNTY SHEETS
CHECKED DAB ORAWN baliva PASSED A Call Party REVISED DEPARTMENT OF TRANSPORTATION SHEET 2 OF 2 SHEETS ILLINOIS FED. AID PROJECT			DATEAPRIL 7, 2015	STATE OF ILLINOIS		74	Champer 4
SHEET 2 OF 2 SHEETS ILLNOIS FED. AID PROJECT	CHECKED DAB	ACIN -	REVISED		SN 010-0180		CONTRACT NO.
	CHECKED VHV DAB	ACTING ENGINEER OF BRIDGES AND STRUCTURES	REVISED		SHEET 2 OF 2 SHEETS	Ti.	LLINOIS FED. AID PROJECT

USER NAME = Leslie.Hoy	DESIGNED -	REVISED -
	DRAWN -	REVISED -
PLOT SCALE = 40.0000 / in.	CHECKED -	REVISED -
PLOT DATE = 6/28/2022	DATE -	REVISED -


STATE OF ILLINOIS **DEPARTMENT OF TRANSPORTATION**

S.N. 010-0180 EXISTING STRUCTURE PLANS	F.A.I. RTE.	SECTION	ON COUNTY		
(FOR INFORMATION ONLY)		(10-7)BR	CHAMPAIGN	20	13
			CONTRACT	NO. 70	0G16
SHEET 6 OF 10 SHEETS STA. TO STA.		ILLINOIS FED. A	ID PROJECT		





ODEL: \$MODELNAME\$



CHECKED

DATE

PLOT DATE = 6/28/2022

REVISED


REVISED

(FOR INFORMATION ONLY) SHEET 9 OF 10 SHEETS STA. TO STA.

SCALE: N/A

(10-7)BR CHAMPAIGN 20 16 CONTRACT NO. 70G16


DEPARTMENT OF TRANSPORTATION



MODEL: \$MODELNAMES

APPLICATION NO. 1

DAY OPERATION ONLY PARTIAL RAMP CLOSURE



GENERAL NOTES

CONSTRUCTION OPERATIONS SHALL BE CONFINED TO AN AREA NARROW ENOUGH THAT A MINIMUM OF 10' (3 m) OF PAVEMENT SHALL BE OPEN TO TRAFFIC AT ALL TIMES.

FULL WIDTH PAVEMENT ON THE RAMPS SHALL BE OPEN TO TRAFFIC AT NIGHT.

WHEN NO WORK IS BEING PERFORMED, THE FLAGGER WILL NOT BE REQUIRED. IF THE FLAGGER IS NOT PRESENT, THE FLAGGER SIGNS SHALL BE REMOVED OR COVERED.

ALL SIGNS SHALL BE POST MOUNTED IF WORK IN THE AREA EXCEEDS FOUR DAYS OF DAYTIME OPERATIONS.

LONGITUDINAL DIMENSIONS MAY BE ADJUSTED SLIGHTLY TO FIT FIELD CONDITIONS.

ALL VEHICLES, EQUIPMENT, WORKERS (EXCEPT FLAGGER) AND THEIR ACTIVITIES ARE RESTRICTED AT ALL TIMES TO ONE SIDE OF THE PAVEMENT UNLESS OTHERWISE AUTHORIZED BY THE DISTRICT ENGINEER.

PIPE UNDERDRAINS HMA RESURFACING

SYMBOLS

SIGN ON PORTABLE OR PERMANENT SUPPORT

W/STEADY BURNING LIGHTS

WORK AREA

o (APPLICATION NO. 1) TYPE I OR II BARRICADES OR DRUMS @ 50' (15 m) CTS.

(APPLICATION NO. 1) FLAGGER PLACED AS DIRECTED BY THE ENGINEER

TYPICAL APPLICATIONS

PAVEMENT PATCHING


(APPLICATION NO. 2) TYPE I OR II BARRICADES OR DRUMS @ 25' (7.5 m) CTS.

TRAFFIC CONTROL FOR ALL RAMPS SHALL BE IN ACCORDANCE WITH THE APPROPRIATE APPLICATION OF PLAN DETAIL TRAFFIC CONTROL FOR RAMPS AND WILL NOT BE PAID FOR SEPARATELY, BUT SHALL BE INCLUDED IN THE CONTRACT LUMP SUM PRICES FOR TRAFFIC CONTROL AND PROTECTION, STANDARD 701401 AND TRAFFIC CONTROL AND PROTECTION, STANDARD 701406.

APPLICATION NO. 2

RAMP CLOSURE

CLASS III BARRICADES WITH RAMP CLOSED SIGNS & FLASHING LIGHTS



GENERAL NOTES

STEADY BURN LIGHTS ARE NOT REQUIRED FOR DAYTIME OPERATIONS.

CONTACT THE DISTRICT TRAFFIC OPERATIONS ENGINEER AT 217-465-4181, ONE WEEK PRIOR TO CLOSING THE RAMP.

Note: All dimensions are in INCHES (millimeters) unless otherwise shown.


DISTRICT 5 DETAIL NO. 70103710

USER NAME = Leslie.Hoy	DESIGNED -	REVISED - 11/06					F.A.I.	SECTION	COUNTY	TOTAL	SHI
	DRAWN -	REVISED -	STATE OF ILLINOIS	TRAFFIC CONTROL FOR RAMPS				(10-7)BR	CHAMPAIGN	20	1
PLOT SCALE = 40.0000 / in.	CHECKED -	REVISED -	DEPARTMENT OF TRANSPORTATION						CONTRACT	T NO. 70	G 1
PLOT DATE = 6/28/2022	DATE -	REVISED -		SCALE: N/A	SHEET 1 OF 1 SHEETS STA	TO STA.		TILLINOIS FED	VID DROIECT		_

s/IDOT Offices/District 5/Projects/D570G16/CAD

ROAD CLOSURE

SIDEROAD / STREET CLOSURE



GENERAL NOTES

- 1. TYPE III BARRICADES SHALL BE AS SHOWN ON STANDARD 701901 "TYPICAL APPLICATIONS OF TYPE III BARRICADES CLOSING A ROAD". EACH TYPE III BARRICADE SHALL HAVE TWO FLASHING AMBER LIGHTS MOUNTED ABOVE IT.
- 2. IF THE ROAD IS OPEN TO LOCAL TRAFFIC OR EXCEEDS 1000' (300 m), ANOTHER SET OF TYPE III BARRICADES, EQUIPPED AS IN NOTE 1 ABOVE, SHALL BE PLACED AT EACH END OF THE WORK AREA.
- 3. WHEN A STOP CONDITION EXISTS, NO SIGNS ARE REQUIRED IN ADVANCE OF THE "STOP" SIGN WHEN THE ROAD IS CLOSED WITHIN 100' (30 m) OF THE INTERSECTION.
- 4. STANDARD 701901 SHALL APPLY FOR THE
- 5. IF A TYPE III BARRICADE WITH AN ATTACHED SIGN PANEL WHICH MEETS NCHRP 350 IS NOT AVAILABLE. THE SIGNS MAY BE MOUNTED ON AN NCHRP 350 TEMPORARY SIGN SUPPORT DIRECTLY IN FRONT OF THE BARRICADE.

- 6. REFLECTORIZED STRIPING SHALL APPEAR ON BOTH SIDES OF THE TY III BARRICADES IF ROAD IS OPEN TO LOCAL TRAFFIC.
- 7. ALL SIGNS SHALL BE POST MOUNTED IF THE CLOSURE TIME EXCEEDS FOUR DAYS.
- 8. A MINIMUM OF TWO FLASHING LIGHTS SHALL BE USED AT NIGHT ON EACH APPROACH IN ADVANCE OF THE WORK AREA. FLASHING LIGHTS SHALL BE INSTALLED ABOVE THE FIRST TWO SIGNS IN THE SERIES.
- 9. LONGITUDINAL DIMENSIONS MAY BE ADJUSTED SLIGHTLY TO FIT FIELD CONDITIONS.
- 10. FORMS BT. 725 AND BT. 726 ARE REQUIRED.
- PLACEMENT & DESIGN OF TYPE III BARRICADES. 11. WHEN A SIDEROAD INTERSECTS THE HIGHWAY ON WHICH WORK IS BEING PERFORMED, ADDITIONAL TRAFFIC DEVICES SHALL BE ERECTED AND PROVIDED AS DIRECTED BY THE ENGINEER.
 - 12. AN ADDITIONAL SIGN MAY BE REQUIRED AT A MAJOR INTERSECTING ROAD IN ADVANCE OF THE CLOSURE. THE ADDITIONAL SIGN SHALL GIVE THE DISTANCE TO THE BARRICADE IN MILES OR FRACTIONS OF A MILE.

FLASHING LIGHT FLAGGER WITH TRAFFIC CONTROL SIGN (WHILE WORK IS BEING PERFORMED) -**₩**20-3(0)48 W20-3(0)48 CONE (DAYLIGHT HOURS ONLY), DRUM, 0 W21-1100(0)-48 W21-1100(0)-48 TYPE I OR TYPE II BARRICADE CLOSED CLOSED . BARRICAD BARRICADE AHEAD WORK AREA AHEAD <── TRAFFIC FLOW W20-7(0)-48 STOP W20-7(0)-48 W20-7a(0)-48 STOP W20-7a(0)-48 CLOSED . FLAGMAN AHEAD W20-5(0)-48 SEE NOTE #2 FLAGMAN AHEAD V20-5(0)-48 100' (30.0 lm) MAX MAINLINE ROUTE (UNDER CONSTRUCTION SEE NOTE #9) RIGHT OR LEFT RIGHT OR LEFT CLOSED CLOSED CLOSED CLOSED LEFT HALF RIGHT HALF MAJOR STREET MINOR STREET CLOSED CLOSED HALF CLOSED HALF CLOSED W21-1100(0)48 BARRICADE CLOSED CLOSED AHEAD

GENERAL NOTES

- 1. TYPE III BARRICADES SHALL BE AS SHOWN ON "TYPICAL APPLICATIONS OF TYPE III BARRICADES CLOSING A ROAD". EACH TYPE III BARRICADE SHALL HAVE TWO FLASHING AMBER LIGHTS MOUNTED ABOVE IT.
- 2. WHERE A STOP CONDITION EXISTS, AS SHOWN ABOVE, WARNING SIGNS MAY BE OMITTED IN ADVANCE OF THE "STOP" SIGN.
- 3. STANDARD 701901 SHALL APPLY FOR THE PLACEMENT & MANUFACTURE OF TYPE III BARRICADES.

SCALE: N/A

- 4. ALL SIGNS SHALL BE POST MOUNTED IF THE CLOSURE TIME EXCEEDS FOUR DAYS.
- 5. ONE FLASHING LIGHT IS REQUIRED ABOVE EACH ADVANCE WARNING SIGN DURING HOURS OF DARKNESS.
- LONGITUDINAL DIMENSIONS MAY BE ADJUSTED SLIGHTLY TO FIT FIELD CONDITIONS
- 7. FORMS BT 725 AND BT 726 ARE REQUIRED.
- THE MAINLINE ROUTE TEMPORARY TRAFFIC CONTROL SHALL BE IN ACCORDANCE WITH THE PLANS, SPECIAL PROVISIONS AND STANDARD SPECIFICATIONS.

SYMBOLS

TYPE III BARRICADE (SEE NOTE)

ALL FLAGGERS REQUIRED AT SIDE ROADS AND ENTRANCES REMAINING OPEN TO TRAFFIC AND/OR ADDITIONAL BARRICADES REQUIRED BY THE ENGINEER TO CLOSE SIDE ROADS AND ENTRANCES WILL BE PAID FOR ACCORDING TO ARTICLE 109.04.

> Note: All dimensions are in INCHES (millimeters) unless otherwise shown.

DISTRICT 5 DETAIL NO. 70200000

JSER NAME = Leslie.Hoy DESIGNED REVISED 11/06 DRAWN REVISED 12/07 HECKED REVISED PLOT DATE = 6/28/2022 DATE REVISED

STATE OF ILLINOIS

TRAFFIC CONTROL & PROTECTION DEVICES (ROAD & SIDEROAD / STREET CLOSURES) SHEET 1 OF 1 SHEETS STA.

(10-7)BR CHAMPAIGN 20 19 CONTRACT NO. 70G16

DEPARTMENT OF TRANSPORTATION

