





- BASED ON CONTROLLER CABINET TYPE IV WITH BASE DIMENSIONS OF 26" x 44" (660mm x 1118mm).
   ADJUST PLATFORM SIZE TO FIT CABINET BASE DIMENSIONS BEING SUPPLIED.
- 2. BASED ON UNINTERRUPTIBLE POWER SUPPLY CABINET WITH BASE DIMENSIONS OF 16"  $\times$  25" (406mm  $\times$  635mm). ADJUST PLATFORM SIZE TO FIT CABINET BASE DIMENSIONS BEING SUPPLIED.
- 3. PLATFORM SIZE FOR CONTROLLER CABINET TYPE IV.
- 4. PLATFORM SIZE FOR CONTROLLER CABINET TYPE IV AND UNINTERRUPTIBLE POWER SUPPLY CABINET.
- 5. DRILLED HOLES THROUGH THE PLATFORM BASE TO MATCH THE CONTROLLER CABINET BOLT TEMPLATE. FASTEN THE CONTROLLER CABINET TO THE PLATFORM WITH CARRIAGE BOLTS, WASHERS AND NUTS.
- 6. FASTEN ALL SUPPORT WOOD FRAMING TO THE WOOD POSTS WITH 2 LAG SCREWS FOR EACH CONNECTION.

# TEMPORARY SIGNAL CONTROLLER WOOD SUPPORT PLATFORM

CABLE SLACK LENGTH	FEET	METER
HANDHOLE	6.5	2.0
DOUBLE HANDHOLE	13.0	4.0
SIGNAL POST	2.0	0.6
MAST ARM	2.0	0.6
CONTROLLER CABINET	1.5	0.5
FIBER OPTIC AT CABINET	13.0	4.0
ELECTRIC SERVICE AT (CABINET OR SERVICE LOCATION)	1.5	0.5
GROUND CABLE (SIGNAL POST, MAST ARM, CABINET)	1.5	0.5
GROUND CABLE (BETWEEN FRAME AND COVER)	5.0	1.6

CABLE SLACK

VERTICAL CABLE LENGTH	FEET	METER
MAST ARM POLE ( MAST ARM MOUNTED SIGNAL HEAD)		
(L = MAST ARM LENGTH - DISTANCE TO SIGNAL HEAD FROM END OF ARM)	20.0+L	6.0+L
BRACKET MOUNTED (MAST ARM POLE OR SIGNAL POLE)	13.0	4.0
PEDESTRIAN PUSH BUTTON	6.0	2.0
SERVICE INSTALLATION POLE MOUNT TO SERVICE DROP	13.5	4.1
SERVICE INSTALLATION POLE MOUNT TO GROUND	13.5	4.1
SERVICE INSTALLATION GROUND MOUNT	6.0	2.0
FOUNDATION (SIGNAL POST, MAST ARM POLE, CONTROLLER CABINET, SERVICE-GROUND MOUNT)	3.0	1.0
. 이 사람이 가는 그들은 사람이 가장 하는 사람이 되었다. 그는 그 그 그 그 그 것이 되었다. 그는 것은 사람이 없는 것이 없는 것이다. 그는 것이 없는 것이다.		

VFRTI	CAL	CABLE	l F	NGTH

FOUNDATION	DEPTH
TYPE A - Signal Post	4'-0" (1.2m)
TYPE C - CONTROLLER W/ UPS	4'-0" (1.2m)
TYPE D - CONTROLLER	4'-0" (1.2m)
SERVICE INSTALLATION, GROUND MOUNT, TYPE A - SQUARE	4'-0" (1.2m)

### DEPTH OF FOUNDATION

Mast Arm Length	① Foundation Depth	Foundation Diameter	Spiral Diameter	Quantity of Rebars	Size of Rebars
Less than 30' (9.1 m)	10'-0" (3.0 m)	30" (750mm)	24" (600mm)	8	6(19)
Greater than or equal to	13'-6" (4.1 m)	30" (750mm)	24" (600mm)	8	6(19)
30' (9.1 m) and less than 40' (12.2 m)	11'-0" (3.4 m)	36" (900mm)	30" (750mm)	12	7(22)
Greater than or equal to 40' (12.2 m) and less than 50' (15.2 m)	13'-0'' (4.0 m)	36" (900mm)	30" (750mm)	12	7(22)
Greater than or equal to 50' (15.2 m) and up to 55' (16.8 m)	15'-0" (4.6 m)	36" (900mm)	30" (750mm)	12	7(22)
Greater than or equal to 56' (16.8 m) and less than 65' (19.8 m)	21'-0" (6.4 m)	42" (1060mm)	36" (900mm)	16	8(25)
Greater than or equal to 65' (19.8 m) and up to 75' (22.9 m)	25'-0" (7.6 m)	42 <sup>3</sup> " (1060mm)	36" (900mm)	16	8(25)

# NOTES:

- These foundation depths are for sites which have cohesive soils (clayey silt, sandy clay, etc.) along
  the length of the shaft, with an average Unconfined Compressive Strength (Qu) > 1.0 tsf (100 kpa).
  This strength shall be verified by boring data prior to construction or with testing by the Engineer
  during foundation drilling. The Bureau of Bridges & structures should be contacted for a revised
  design if other conditions are encountered.
- 2. Combination most arm assemblies under 55 feet (16.8 m) shall use 36" (900 mm) diameter foundations.
- 3. Combination mast arm assemblies under 56 feet (16.8 m) through 75 feet (22.9 m) shall use 42" (1060 mn diameter foundations.
- 4. For most arm assemblies with dual arms refer to state standard 878001.

# DEPTH OF MAST ARM FOUNDATIONS, TYPE E

	이 그런 사람들이 하고 한 환경을 가는 사고를 받고 했다.		하는 하는 말이 되었다. 그 사는 사람들은 사람들은 사람들이 되었다. 그는 사람들이 되었다. 이 사람들이 되었다.		
FILE NAME =	USER NAME = qureshiya DESIGNED	- DAG REVISED -		DISTRICT ONE	RTE. SECTION COUNTY TOTAL SHEET NO.
c:\pw_work\pwidot\qureshiya\dØ111256\Dis	otd.dgn DRAWN	- BCK REVISED -	STATE OF ILLINOIS	STANDARD TRAFFIC SIGNAL DESIGN DETAILS	3887 A-R-N-1 KANE 77 58
	PLOT SCALE = 50.0000 // IN. CHECKED	- DAD REVISED -	DEPARTMENT OF TRANSPORTATION		TS-05 CONTRACT NO. 62914
나는 현실 하는 경기를 가지면 하루 하는 사람	PLOT DATE = 3/10/2010 DATE	- 10-28-09 REVISED -		SCALE: NONE SHEET NO. 5 OF 6 SHEETS STA. TO STA.	FED. ROAD DIST. NO. 1   ILLINOIS   FED. AID PROJECT