

NOTES:

- 1. USE BLACK LETTERING ON ORANGE BACKGROUND.
- 2. ERECT SIGNS IN ADVANCE OF THE LOCATION FOR THE "ROAD CONSTRUCTION AHEAD" SIGN AT LOCATIONS AS DIRECTED BY THE ENGINEER.
- 3. ERECT SIGN (1) WITH INSTALLED PANEL (2) ONE WEEK PRIOR TO THE START OF CONSTRUCTION.
- 4. REMOVE PANEL (2) SOON AFTER THE START OF CONSTRUCTION.
- 5. SEE SPECIAL PROVISION FOR "TEMPORARY INFORMATION SIGNING" FOR ADDITIONAL INFORMATION.
- 6. ONE SIGN ASSEMBLY EQUALS 25.70 SQ. FT. (2.3 SQ. M.)
- 7. SHALL BE PAID FOR AS TEMPORARY INFORMATION SIGNING.

ALL DIMENSIONS ARE IN INCHES (MILLIMETERS) UNLESS OTHERWISE SHOWN.

		the control of the second of the control of the con		
FILE NAME =	USER NAME = qureshiya	DESIGNED -	REVISED - R. MIRS 09-15-97	Γ
c:\pw_work\pwidot\qureshiya\d0111256\Dist	td.dgn	DRAWN -	REVISED - R. MIRS 12-11-97	
[일본] 하시아 시작으로 보다 하다.	PLOT SCALE = 50.0000 '/ IN.	CHECKED -	REVISED -T. RAMMACHER 02-02-99	
	PLOT DATE = 3/10/2010	DATE -	REVISED - C. JUCIUS 01-31-07	

	STATI	E OF	ILLINOIS		
DEPA	RTMENT	OF 1	ranspo	RTATION	

٦		ARTERIAL R	AD	 	F.A.U. SECTION	COUNTY TOTAL SHEET
				and the state of t	3887 A-R-N-1	KANE 77 66
		INFORMATION	SIGN		TC-22	CONTRACT NO. 62914
. 1	SCALE: NONE	SHEET NO. 1 OF 1 SHEETS	STA.	TO STA.	FED. ROAD DIST. NO. 1 ILLINOIS FED. AT	ID PROJECT