## GENERAL ELECTRICAL PLAN NOTES

- THIS PROJECT INCLUDES THE INSTALLATION OF ELECTRICAL CONDUIT WITHIN THE PROPOSED BRIDGE PARAPET ON THE NORTH AND SOUTH SIDES OF THE BRIDGE.
- THE CONTRACTOR SHALL SUBMIT FOR THE RESIDENT ENGINEER'S REVIEW WITHIN 30 DAYS AFTER CONTRACT EXECUTION, EIGHT COPIES OF APPROVED MANUFACTURER'S PRODUCT DATA AND DETAILED SHOP DRAWINGS TO THE RESIDENT ENGINEER.
- THE QUANTITIES OF RACEWAY WHERE INDICATED IN THESE PLANS ARE APPROXIMATIONS ONLY. THE CONTRACTOR SHALL FIELD VERIFY ALL LENGTHS AND SHALL INSTALL RACEWAYS IN COMPLETE COMPLIANCE WITH THE SPECIFIED REQUIREMENTS.
- ALL NEW CONDUIT AND JUCTION BOXES ARE ILLUSTRATED DIAGRAMMATICALLY; THE ACTUAL LOCATION IN THE FIELD MUST MEET THE APPROVAL OF THE ENGINEER.
- THE CONTRACTOR SHALL NOTIFY J.U.L.I.E. TO LOCATE AND MARK/STAKE ALL UNDERGROUND UTILITIES. THE CONTRACTOR SHALL NOTIFY THE VILLAGE OF LISLE TO LOCATE AND MARK/STAKE ALL VILLAGE OWNED UNDERGROUND UTILITIES.
- JUNCTION BOX AND CONDUIT INSTALLATION SHALL CONFORM TO THE LATEST IDOT STANDARDS, NEC AND LOCAL CODES.
- ALL ELECTRICAL EQUIPMENT AND PRODUCTS SHALL BE U/L LISTED AND LABELED.
- THE CONTRACTOR SHALL SUBMIT FULL SIZED COMPLETE AND ACCURATE "RECORD DRAWINGS" TO THE ENGINEER FOR REVIEW. COMMENT, AS SPECIFIED. "REPORDUCIBLE RECORD DRAWINGS" § BE SUBMITTED AT LEAST 7 DAYS BEFORE SCHEDULING A FINAL INSPECTION.

Order managed in	BILL OF MATERIALS		A COMPANY
ITEM NO.	DESCRIPTION	UNIT	QUANTITY
81200240	CONDUIT EMBEDDED IN STRUCTURE, 2 1/2" DIA, PVC	FOOT	330
81304700	JUNCTION BOX EMBEDDED IN STRUCTURE 18"X18"X6"	EACH	4

AMES Engineering, Inc. Consulting Engineers

1341 Warren Avenue Downers Grove, IL 60515

COUNTY TOTAL SHEET NO.

DUPAGE 45 19

CONTRACT NO. 63468

FILE NAME =	USER NAME = pociecha	DESIGNED	-	LP	REVISED -
W:\871-002 Short Phase II\CADD_Sheets\El	otrical\871-002-NOTES.dgn	DRAWN	-	LP	REVISED -
	PLOT SCALE = 20.0000 '/ IN.	CHECKED	-	JP	REVISED -
	PLOT DATE = 7/31/2010	DATE	-	08/02/2010	REVISED -
					<del></del>

STATI	E OF	ILLINOIS
DEPARTMENT	OF	TRANSPORTATION