STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION





Notes:

CHECKED AJS

DRAWN KAS

All material for bracing shall be hot dip galvanized according to AASHTO M111 unless otherwise noted. Two hardened washers are required for each set of oversized holes.

All holes shall be ${}^{l5}_{l6}$ " ϕ unless otherwise noted. ${}^{5}_{l6}$ " x 3" x 3" plate washers are required over all slotted holes.

All bolts shall be galvanized according to AASHTO M232. Bracing shall be installed as beams are erected and tightened as soon as possible during erection.







See bearing details for pintle hole locations when required.

<u>NOTES</u>

Inserts for ${}^{3}_{4}$ " ϕ threaded dowel rods, when specified, are to be two strut, ferrule type for interior beams and single ferrule, flared loop type for exterior beams. Prestressing steel shall be uncoated high strength, low relaxation 7-wire strand, Grade 270. The nominal diameter shall be ${}^{1}_{2}$ " and the nominal cross-sectional area shall be 0.153 sq. in.

Reinforcement bars shall conform to ASTM A 706, Grade 60. (See Special Provisions). A minimum 2¹2" ¢ lifting pin shall be used to engage the lifting loops during handling. The top and bottom plates shall be AASHTO M270 Grade 50. The bottom plates and studs shall be galvanized according to AASHTO M111. Threaded rods shall be ASTM F 1554 Grade 55.



BAR G4

BILL OF MATERIAL

BAR G5

Item	Unit	Total
Furnishing and Erecting Precast Prestressed Concrete I-Beams, 54''	Ft.	642

54" P.P.C	<u>C. I-BEAM BEAM DETAILS (2 OF 2</u>	2)
	<u>S.N. 090-0177</u>	
5	STRAND ASSOCIATES, INC.	

SHEET NO. 12		F.A.P. RTE.	SECTION	COU	COUNTY		SHEET NO.
		693	(119 BR-2)BR	TAZE	WELL	65	29
22	SHEETS	CONTRACT NO. 68660					660
		FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT					