

SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
704	(1)N&TS-1	McLEAN	497	14
STA. N/A		TO STA. N/A		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
CONTRACT NO. 70514				

			Funding		80% Federal	80% Federal	80% Federal	80% Federal	80% State	80% Federal	80% Federal	80% Federal	100% City	80% Federal	80% Federal	100% City	80% Federal	100% City
			Breakout		20% State	20% State	20% State	10% State	20% City	10% State	13% State	20% City		20% State	20% City		20% State	
			URBAN															
			Construction															
			Code		0004	0040	0040	0021	0038	0021	0021	0021	0021	0021	0021	0043	0021	0021
				TOTAL QTY	ROADWAY	RETAINING WALL S.N. 057-W001	RETAINING WALL S.N. 057-W002	SIDEWALK	BIKE PATH	** SEE BELOW	*** SEE BELOW	**** SEE BELOW	EMERGENCY PREEMPTION	INTERCONNECT	INTERCONNECT	UTILITY ADJUSTMENTS	COMBINATION LIGHTING	COMBINATION LIGHTING
*	M6300101	STEEL PLATE BEAM GUARD RAIL, TYPE A, 1.83M POSTS	METER	523.07	523.07													
	M6320030	GUARDRAIL REMOVAL	METER	394	394													
	M6640110	CHAIN LINK FENCE, 1.5 METER	METER	95.3	95.3													
	M6690200	NON-SPECIAL WASTE DISPOSAL	CU M	163	163													
	M7030100	SHORT-TERM PAVEMENT MARKING	METER	310	310													
	M7030210	TEMPORARY PAVEMENT MARKINGS- LETTERS AND SYMBOLS	SQ M	6.42	6.42													
	M7030220	TEMPORARY PAVEMENT MARKING - LINE 100MM	METER	9,200	9,200													
	M7031000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ M	346	346													
*	M7200100	SIGN PANEL - TYPE 1	SQ M	14.76	14.76													
*	M7200200	SIGN PANEL - TYPE 2	SQ M	0.9	0.9													
*	M7300100	WOOD SIGN SUPPORT	METER	124.3	124.3													
*	M7800100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ M	19.1	19.1													
	M7800105	THERMOPLASTIC PAVEMENT MARKING - LINE 100MM	METER	2,276	2,276													
	M7800125	THERMOPLASTIC PAVEMENT MARKING - LINE 300MM	METER	156.3	156.3													
	M7800140	THERMOPLASTIC PAVEMENT MARKING - LINE 600MM	METER	41.4	41.4													
*	M7802100	POLYUREA PAVEMENT MARKING TYPE II - LETTERS AND SYMBOLS	SQ M	100.7	100.7													
	M7802070	POLYUREA PAVEMENT MARKING TYPE II - LINE 100MM	METER	6,320	5,990				330									
	M7802090	POLYUREA PAVEMENT MARKING TYPE II - LINE 300MM	METER	677.5	677.5													
*	M7802160	POLYUREA PAVEMENT MARKING TYPE II - LINE 600MM	METER	89.5	89.5													
	M7830100	PAVEMENT MARKING REMOVAL	SQ M	99	99													
*	M8100260	CONDUIT IN TRENCH, 50MM DIA., PVC	METER	1,467						233	222	224		570	218			
*	M8100270	CONDUIT IN TRENCH, 65MM DIA., PVC	METER	98						20	52	26						
*	M8102075	CONDUIT PUSHED, 75MM DIA., PVC SCHEDULE 80	METER	345													220	125
*	M8100300	CONDUIT IN TRENCH, 100MM DIA., PVC	METER	62						44	4	14						
*	M8101050	CONDUIT PUSHED, 50MM DIA., GALVANIZED STEEL	METER	132						14		18		100				
*	M8101070	CONDUIT PUSHED, 75MM DIA., GALVANIZED STEEL	METER	137						51	51	35						
*	M8101090	CONDUIT PUSHED, 100MM DIA., GALVANIZED STEEL	METER	213						107	37	69						
*	M8170040	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 6	METER	990													650	340

* SPECIALTY ITEMS

- ** VETERANS & MORRIS TRAFFIC SIGNALS
- *** VETERANS & GREENWOOD TRAFFIC SIGNALS
- **** MORRIS & SIX POINTS TRAFFIC SIGNALS

REVISI
NAME DATE

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION	
NAME	DATE	SUMMARY OF QUANTITIES SHEET 9 OF 12	
		DRAWN BY	
		CHECKED BY	
		DATE 05-27-09	

SUMMARY OF QUANTITIES