

SCHEDULE OF QUANTITIES

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
704	(1)N&TS-1	McLEAN	497	56
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
CONTRACT NO. 70514				

PORTLAND CEMENT CONCRETE PAVEMENT 230 mm (JOINTED)		M4202235
LOCATION		SQ M
STA. 0+013.771 TO STA. 0+392.471, SIX POINTS ROAD		6205
STA. 0+427.548 TO STA. 0+673.930, SIX POINTS ROAD		2177
TOTAL		8382

PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 150 MM		M4230150
LOCATION	OFFSET	SQ M
STA. 0+069.6, MORRIS AVENUE	LT	46
STA. 0+078.2, MORRIS AVENUE	RT	52
STA. 0+186.0, MORRIS AVENUE	RT	105
STA. 0+363.6, MORRIS AVENUE	RT	92
STA. 0+491.1, MORRIS AVENUE	RT	131
STA. 0+504.1, MORRIS AVENUE	LT	81
STA. 0+526.5, MORRIS AVENUE	LT	99
STA. 0+543.7, MORRIS AVENUE	LT	98
STA. 0+548.0, MORRIS AVENUE	RT	99
STA. 0+591.3, MORRIS AVENUE	LT	152
STA. 0+019.5, SIX POINTS ROAD	RT	17
STA. 0+033.8, SIX POINTS ROAD	LT	18
STA. 0+050.0, SIX POINTS ROAD	RT	16
STA. 0+051.5, SIX POINTS ROAD	LT	60
STA. 0+080.9, SIX POINTS ROAD	LT	99
STA. 0+080.9, SIX POINTS ROAD	RT	16
STA. 0+111.9, SIX POINTS ROAD	LT	65
STA. 0+142.7, SIX POINTS ROAD	LT	34
STA. 0+166.3, SIX POINTS ROAD	RT	55
STA. 0+171.0, SIX POINTS ROAD	LT	18
STA. 0+187.4, SIX POINTS ROAD	RT	39
STA. 0+226.9, SIX POINTS ROAD	RT	23
STA. 0+240.3, SIX POINTS ROAD	RT	77
STA. 0+359.3, SIX POINTS ROAD	LT	212
STA. 0+463.3, SIX POINTS ROAD	RT	116
STA. 0+487.3, SIX POINTS ROAD	RT	39
STA. 3+961.1, SZAREK STREET	RT	31
STA. 5+031.6, MCKAY STREET	LT	65
STA. 0+895.0, SPRINGFIELD ROAD	LT	52
STA. 0+933.7, SPRINGFIELD ROAD	LT	72
STA. 0+989.2, SPRINGFIELD ROAD	RT	196
STA. 1+052.0, SPRINGFIELD ROAD	LT	88
STA. 1+055.4, SPRINGFIELD ROAD	RT	162
CUL-DE-SAC, SPRINGFIELD ROAD	LT	61
STA. 7+112.3, GREENWOOD AVENUE	LT	115
STA. 7+145.4, GREENWOOD AVENUE	LT	65
STA. 10+007.4, GREENWOOD AVENUE	RT	32
STA. 10+094.8, GREENWOOD AVENUE	RT	117
STA. 10+172.6, GREENWOOD AVENUE	RT	90
STA. 10+212.5, GREENWOOD AVENUE	RT	55
STA. 10+264.3, GREENWOOD AVENUE	RT	44
STA. 10+323.3, GREENWOOD AVENUE	RT	68
STA. 10+415.4, GREENWOOD AVENUE	RT	110
STA. 10+513.0, GREENWOOD AVENUE	RT	43
STA. 10+520.8, GREENWOOD AVENUE	RT	43
STA. 10+541.2, GREENWOOD AVENUE	RT	53
STA. 10+565.6, GREENWOOD AVENUE	RT	97
STA. 10+609.8, GREENWOOD AVENUE	RT	59
STA. 10+636.4, GREENWOOD AVENUE	RT	79
STA. 10+655.2, GREENWOOD AVENUE	RT	92
STA. 10+701.0, GREENWOOD AVENUE	RT	53
STA. 10+726.7, GREENWOOD AVENUE	RT	51
STA. 10+779.1, GREENWOOD AVEUNE	RT	24
TOTAL		3876

PORTLAND CEMENT CONCRETE SIDEWALK 100 mm		M4240100
LOCATION		SQ M
STA. 0+073.6 TO STA. 0+123.2, MORRIS AVE.		60.5
STA. 0+136.7 TO STA. 0+236.2, MORRIS AVE.		121.5
STA. 0+421.4 TO STA. 0+499.2, MORRIS AVE.		95.0
STA. 0+509.1 TO STA. 0+521.5, MORRIS AVE.		15.0
STA. 0+531.4 TO STA. 0+537.7, MORRIS AVE.		7.5
TOTAL		299.5

DETECTIBLE WARNINGS		M4248000
LOCATION	TYPE	SQ M
STA. 0+122.850, LT, MORRIS AVE.	A	0.72
STA. 0+137.500, LT, MORRIS AVE.	A	0.72
STA. 0+235.440, LT, MORRIS AVE.	A	1.10
STA. 0+245.090, LT, MORRIS AVE.	A	1.10
STA. 2+336.770, 25.100 M RT, VETERANS PARKWAY	A	1.10
STA. 2+337.700, 12.100 M RT, VETERANS PARKWAY	A	1.10
STA. 2+337.700, 4.100 M RT, VETERANS PARKWAY	A	1.10
STA. 2+337.700, 7.100 M LT, VETERANS PARKWAY	A	1.10
STA. 0+386.000, LT, MORRIS AVE.	A	1.10
STA. 0+423.700, LT, MORRIS AVE.	B	1.10
STA. 0+425.000, 7.8 M LT, MORRIS AVE.	A	1.10
STA. 0+425.000, 1.4 M LT, MORRIS AVE.	A	1.10
STA. 0+425.000, 15.0 M RT, MORRIS AVE.	A	1.10
STA. 0+552.100, LT, MORRIS AVE.	B	0.72
STA. 0+568.900, LT, MORRIS AVE.	B	0.72
		14.98

HOT MIX ASPHALT SURFACE REMOVAL, 30MM		M4400730
STATION		SQ M
2+205.5 TO 3+050.4 VETERANS PARKWAY	S. BOUND	6221
2+205.5 TO 3+050.4 VETERANS PARKWAY	N. BOUND	7041
TOTAL		13262

PAVEMENT REMOVAL		M4402000
LOCATION		SQ M
MORRIS AVE SOUTH OF VETERANS PKWY		1,793
MORRIS AVE NORTH OF VETERANS PKWY		3,736
SPRINGFIELD RD WEST OF MORRIS AVE		1,658
SPRINGFIELD RD EAST OF MORRIS AVE		2,531
SIX POINTS RD WEST OF MORRIS AVE		2,916
SIX POINTS RD EAST OF MORRIS AVE		1,055
GREENWOOD AVE WEST OF MORRIS AVE		1,238
GREENWOOD AVE EAST OF MORRIS AVE		6,194
SZAREK ST		407
MCKAY ST		359
TOTAL		21,887

DRIVEWAY PAVEMENT REMOVAL		M4402010
STATION	OFFSET	SQ M
0+069.6 MORRIS AVE., PCC	LT	51
0+078.2 MORRIS AVE., PCC	RT	12
0+193.0 MORRIS AVE., PCC	RT	100
0+411 TO 0+513.9 MORRIS AVE., PCC	LT	2304
0+538.2 TO 0+549.2 MORRIS AVE., PCC	LT	44
0+578.3 TO 0+603.2 MORRIS AVE., PCC	LT	209
0+240.3 SIX POINTS ROAD, PCC	RT	106
10+094.8 GREENWOOD AVE., PCC	RT	158
1+172.6 GREENWOOD AVE., PCC	RT	126
10+415.4 GREENWOOD AVE., PCC	RT	139
10+609.8 GREENWOOD AVE., PCC	RT	25
STA. 16+581.980, SPRINGFIELD ROAD, PCC	LT	29
TOTAL		3303

COMBINATION CURB AND GUTTER REMOVAL		M4402040
STATION	OFFSET	METER
2+386.3 TO 2+539.8 VETERANS PARKWAY	RT	168
0+022.0 TO 0+124.2 MORRIS AVE.	LT	105
0+022.0 TO 0+237.5 MORRIS AVE.	RT	216
0+132.8 TO 0+226.8 MORRIS AVE.	LT	98
0+372 TO 0+378 MORRIS AVE.	RT	12
0+394.3 TO 0+395.3 MORRIS AVE.	RT	3
0+561 TO 0+563 MORRIS AVE.	LT	8
0+015.1 TO 0+016.2 SIX POINTS ROAD	LT	7
3+965.2 TO 3+984.6 SZAREK ST.	LT	24
3+957.8 TO 3+993.5 SZAREK ST.	RT	37
5+010.9 TO 5+050.5 MCKAY ST.	LT	40
5+010.7 TO 5+050.5 MCKAY ST.	RT	40
TOTAL		758

SIDEWALK REMOVAL		M4402050
STATION	OFFSET	SQ M
0+073.6 TO 0+123.5 MORRIS AVE.	LT	69
0+132.0 TO 0+220.7 MORRIS AVE.	LT	112
0+569.4 TO 0+570.9 MORRIS AVE.	LT	1
0+476.3 TO 0+477.2 SIX POINTS ROAD	RT	1
16+587.6 TO 16+622.0 SPRINGFIELD ROAD	LT	40
TOTAL		223

MEDIAN REMOVAL		M4402420
STATION		SQ M
2+861.0 TO 3+050.4, VETERANS PARKWAY		190.4
TOTAL		190.4

GUTTER OUTLET REMOVAL		M4402350
LOCATION	OFFSET	METER
STA. 16+419.1 TO STA. 16+428.2, SPRINGFIELD ROAD	RIGHT	10
TOTAL		10

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION SCHEDULE OF QUANTITIES DRAWN BY MAC CHECKED BY PMH DATE 05-27-09
NAME	DATE	

SCHEDULE OF QUANTITIES