

**SCHEDULE OF QUANTITIES**

F.A. RTE. 704	SECTION (1)N&TS-1	COUNTY McLEAN	TOTAL SHEETS 497	SHEET NO. 58
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
CONTRACT NO. 70514				

THERMOPLASTIC PAVEMENT MARKING  
VETERANS PARKWAY

STATION TO STATION	LETTERS AND SYMBOLS										
	LEFT OR RIGHT ARROW	LANE LINE SKIP DASH WHITE 100 mm	LANE LINE DOTTED WHITE 100 mm	EDGE LINE SOLID YELLOW 100 mm	EDGE LINE SOLID WHITE 100 mm	LANE LINE SOLID WHITE 100 mm	CROSSWALK SOLID WHITE 150 mm	CROSSWALK SOLID WHITE 300 mm	STOP BAR SOLID WHITE 600 mm	MEDIAN SOLID WHITE 150 mm	MEDIAN SOLID WHITE 300 mm
	SQ M	M	M	M	M	M	M	M	M	M	M
<b>Veterans Parkway, Northbound</b>											
2+205.0 TO 2+335.0		32.5									
2+205.0 TO 2+305.0					100						
2+236.8 TO 2+280.3			10.9								
2+280.3 TO 2+335.0						54.7					
2+280.3	1.47										
2+329.2	1.47										
2+335.0									11.3		
2+336.2 TO 2+338.6							23.9	24			
2+419.2 TO 2+707.4		72.0									
2+456.9 TO 2+585.5					128.6						
2+486.0 TO 2+670.0				184							
2+585.5 TO 2+630.8			11.3								
2+630.8 TO 2+705.5						74.7					
2+638.0	1.47										
2+664.5	1.47										
2+691.0	1.47										
2+707.4								8.4			
2+705.5 TO 2+714.9									26.2	14.9	
2+736.7 TO 3+050.4		78.4									
2+760.7 TO 3+050.4					289.7						
<b>Veterans Parkway, Southbound</b>											
2+205.0 TO 2+336.5		32.9									
2+205.0 TO 2+336.5					131.5						
2+336.5 TO 2+338.9							24.1	24.0			
2+338.9 TO 2+356.6					18.5						14.2
2+408.7									10.9		
2+408.7 TO 2+646.9					238.2						
2+408.7 TO 3+050.4		160.4									
2+408.7 TO 2+486.4						77.7					
2+414.5	1.47										
2+438.4	1.47										
2+462.4	1.47										
2+486.4	1.47										
2+486.4 TO 2+563.0			19.2								
2+646.9 TO 2+672.3										51.2	79.2
2+648.8 TO 3+050.4					401.6						
2+738.6									10.8		
2+738.6 TO 3+050.4		78.0									
2+738.6 TO 2+803.0						64.4					
2+744.1	1.47										
2+763.7	1.47										
2+783.3	1.47										
2+803.0	1.47										
2+803.0 TO 2+869.3			16.6								
<b>TOTAL</b>	<b>19.11</b>	<b>454.2</b>	<b>58</b>	<b>184</b>	<b>1308.1</b>	<b>271.5</b>	<b>48</b>	<b>48</b>	<b>41.4</b>	<b>77.4</b>	<b>108.3</b>

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION  SCHEDULE OF QUANTITIES  DRAWN BY MAC CHECKED BY PMH DATE 05-27-09
NAME	DATE	

**SCHEDULE OF QUANTITIES**