

| | | | | |
|---------------------|-----------|---------------------------|--------------|-----------|
| F.A. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| 704 | (1)N&TS-1 | McLEAN | 497 | 61 |
| STA. | | TO STA. | | |
| FED. ROAD DIST. NO. | | ILLINOIS FED. AID PROJECT | | |
| CONTRACT NO. 70514 | | | | |

| STATION TO STATION | TEMPORARY STAGE | LETTERS AND SYMBOLS | | LINES | | | | | |
|-------------------------------------|-----------------|---------------------|--|-------------------------------|-------------------------------|------------------------------|-------------------------------|------------------------------|-----------------------------|
| | | LEFT OR RIGHT ARROW | LANE LINE SOLID YELLOW 100 mm (DOUBLE) | LANE LINE SOLID YELLOW 100 mm | EDGE LINE SOLID YELLOW 100 mm | EDGE LINE SOLID WHITE 100 mm | LANE LINE DOTTED WHITE 100 mm | LANE LINE SOLID WHITE 100 mm | STOP BAR SOLID WHITE 600 mm |
| | | SQ M | M | M | M | M | | M | M |
| Veterans Parkway, Northbound | | | | | | | | | |
| 2+205.5 TO 2+351 | STAGE 2 | | | | | 145.5 | | | |
| 2+233 TO 2+278.5 | STAGE 2 | | | | | | 11.4 | | |
| 2+278.5 TO 2+351 | STAGE 2 | | | | | | | 72.5 | |
| 2+278.5 | STAGE 2 | 1.47 | | | | | | | |
| 2+300.3 | STAGE 2 | 1.47 | | | | | | | |
| 2+322.6 | STAGE 2 | 1.47 | | | | | | | |
| 2+345.5 | STAGE 2 | 1.47 | | | | | | | |
| 2+386 TO 3+050 | STAGE 2 | | | | 664 | | | | |
| 2+710 TO 2+735 | STAGE 3 | | | 25 | | | | | |
| Veterans Parkway, Southbound | | | | | | | | | |
| 2+435.0 TO 3+051.0, LT | STAGE 1 | | | | | 616 | | | |
| 2+205 TO 2+365 | STAGE 2 | | | | 160 | | | | |
| 2+392 TO 3+050 | STAGE 2 | | | | 658 | | | | |
| 2+278.5 | STAGE 2 | 1.47 | | | | | | | |
| 2+300.3 | STAGE 2 | 1.47 | | | | | | | |
| 2+322.6 | STAGE 2 | 1.47 | | | | | | | |
| 2+345.5 | STAGE 2 | 1.47 | | | | | | | |
| 2+484 TO 2+540.5 | STAGE 2 | | | | | | 14.1 | | |
| 2+392 TO 2+484 | STAGE 2 | | | | | | | 92 | |
| 2+435.1 TO 3+050 | STAGE 2 | | | | | 614.9 | | | |
| 2+698 TO 2+870 | STAGE 3 | | | 172 | | | | | |
| MORRIS AVENUE | | | | | | | | | |
| 0+014 TO 0+135 | STAGE 1 | | | | | 121 | | | |
| 0+006 TO 0+238 | STAGE 2 | | | | | 244 | | | |
| 0+005 TO 0+233 | STAGE 2 | | 456 | | | | | | |
| 0+513.6 TO 0+649 | STAGE 2 | | | | | 135.4 | | | |
| 0+009.3 TO 0+240 | STAGE 3 | | 461.4 | | | | | | |
| 0+027 TO 0+116.7 | STAGE 3 | | | | | 89.7 | | | |
| 0+142 TO 0+218.6 | STAGE 3 | | | | | 76.6 | | | |
| 0+013 TO 0+243 | STAGE 3 | | | | | 237 | | | |
| 0+494 TO 0+668, LT | STAGE 3 | | | | | 174 | | | |
| 0+494.0 TO 0+660.5 | STAGE 3 | | 333 | | | | | | |
| 0+523.6 TO 0+644, RT | STAGE 3 | | | | | 120.4 | | | |
| 0+009.3 TO 0+111 | STAGE 4 | | 203.4 | | | | | | |
| 0+022 TO 0+115, LT | STAGE 4 | | | | | 108 | | | |
| 0+115.0 TO 0+134, LT | STAGE 4 | | | | | 28 | | | |
| 0+310.0 | STAGE 4 | | | | | | | | 6.6 |
| 0+395.3 | STAGE 4 | | | | | | | | 3.6 |
| 0+427.8 | STAGE 4 | | | | | | | | 8 |
| 0+396.0 TO 0+676.5 | STAGE 4 | | 447.4 | | | | | | |
| 0+427.8 TO 0+676.5 | STAGE 4 | | | | | 280.5 | | | |
| 0+310 TO 0+395.3, RT | STAGE 4 | | | | | 366 | | | |
| 0+310 TO 0+676 | STAGE 4 | | 732 | | | | | | |
| 0+511 TO 0+676 | STAGE 4 | | | | | 165 | | | |
| GREENWOOD AVENUE | | | | | | | | | |
| 10+200 TO 10+250 | STAGE 2 | | 100 | | | | | | |
| 10+200 TO 10+250, RT | STAGE 2 | | | | | 50 | | | |
| 10+200 TO 10+347, LT | STAGE 2 | | | | | 147 | | | |
| 10+392 TO 10+631.2 | STAGE 2 | | 478.4 | | | | | | |
| 10+392 TO 10+631.9, RT | STAGE 2 | | | | | 239.9 | | | |
| 10+392 TO 10+704, LT | STAGE 2 | | | | | 312 | | | |
| 9+992.7 TO 10+261.3 | STAGE 3 | | 537.2 | | | | | | |
| 9+993 TO 10+255, RT | STAGE 3 | | | | | 262.3 | | | |
| 9+993 TO 10+261.3, LT | STAGE 3 | | | | | 268.6 | | | |
| TOTAL | | 11.76 | 3748.8 | 197 | 1482 | 4801.8 | | 164.5 | 18.2 |

| REVISIONS | | ILLINOIS DEPARTMENT OF TRANSPORTATION |
|-----------|------|---------------------------------------|
| NAME | DATE | |
| | | SCHEDULE OF QUANTITIES |
| | | |
| | | |
| | | |
| | | |
| | | DRAWN BY |
| | | CHECKED BY |
| | | DATE 03-31-09 |

SCHEDULE OF QUANTITIES