

CODE NO	ITEM	UNIT	TOTAL QUANTITY	FAP - RURAL 10% STATE 90% FED	S.N. 057-2047 STA. 363+70 FAP - RURAL 10% STATE 90% FED	S.N. 057-2048 STA. 0+76.3 FAP - RURAL 10% STATE 90% FED	S.N. 057-2049 STA. 388+50 FAP - RURAL 10% STATE 90% FED
20100500	TREE REMOVAL, ACRES	ACRE	4.25	4.25			
20200100	EARTH EXCAVATION	CU YD	31,261.0	31,261.0			
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	153.0	153.0			
20400800	FURNISHED EXCAVATION	CU YD	17,122.0	17,122.0			
20700220	POROUS GRANULAR EMBANKMENT	CU YD	525.0	525.0			
20800150	TRENCH BACKFILL	CU YD	50.0	50.0			
20900110	POROUS GRANULAR BACKFILL	CU YD	11.0	11.0			
21301052	EXPLORATION TRENCH 52" DEPTH	FOOT	3,385.0	3,385.0			
* 25000200	SEEDING, CLASS 2	ACRE	8.0	8.0			
* 25000310	SEEDING, CLASS 4	ACRE	5.5	5.50			
* 25000350	SEEDING, CLASS 7	ACRE	13.5	13.5			
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	722.0	722.0			
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	722.0	722.0			
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	722.0	722.0			
* 25100115	MULCH, METHOD 2	ACRE	12.75	12.75			
* 25100630	EROSION CONTROL BLANKET	SQ YD	3,450.0	3,450.0			
25301800	SEEDLINGS	UNIT	3.0	3.0			
28000305	TEMPORARY DITCH CHECKS	FOOT	529.0	529.0			
28000400	PERIMETER EROSION BARRIER	FOOT	3,031.0	3,031.0			
28000500	INLET AND PIPE PROTECTION	EACH	2.0	2.0			
28100107	STONE RIPRAP, CLASS A4	SQ YD	303.0	303.0			
28100201	STONE RIPRAP, CLASS A1	TON	665.0		197.0	313.0	155.0
28200200	FILTER FABRIC	SQ YD	1,271.0	303.0	287.0	455.0	226.0
30201500	LIME	TON	258.0	258.0			
30200650	PROCESSING MODIFIED SOIL 12"	SQ YD	11,442.0	11,442.0			
31101900	SUB-BASE GRANULAR MATERIAL, TYPE C	TON	505.0	505.0			
35101400	AGGREGATE BASE COURSE, TYPE B	TON	250.0	250.0			
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	556.0	556.0			
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	2,164.0	2,164.0			
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	6,261.0	6,261.0			
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	1,025.0	1,025.0			
40800010	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	61.0	61.0			
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	131.0	131.0			
44000100	PAVEMENT REMOVAL	SQ YD	8,577.0	8,577.0			
44004250	PAVED SHOULDER REMOVAL	SQ YD	1,167.0	1,167.0			
48101200	AGGREGATE SHOULDERS, TYPE B	TON	914.0	914.0			
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	1,471.0	1,471.0			
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1.0		1.0		

CODE NO	ITEM	UNIT	TOTAL QUANTITY	FAP - RURAL 10% STATE 90% FED	S.N. 057-2047 STA. 363+70 FAP - RURAL 10% STATE 90% FED	S.N. 057-2048 STA. 0+76.3 FAP - RURAL 10% STATE 90% FED	S.N. 057-2049 STA. 388+50 FAP - RURAL 10% STATE 90% FED
50100400	REMOVAL OF EXISTING STRUCTURES NO. 2	EACH	1.0	1.0			
50100500	REMOVAL OF EXISTING STRUCTURES NO. 3	EACH	1.0	1.0			
50105220	PIPE CULVERT REMOVAL	FOOT	86.0	86.0			
50200100	STRUCTURE EXCAVATION	CU YD	2,056.0		757.2	766.1	532.7
51500100	NAME PLATES	EACH	3.0		1.0	1.0	1.0
54001001	BOX CULVERT END SECTION, CULVERT NO. 1	EACH	2.0		2.0		
54001002	BOX CULVERT END SECTION, CULVERT NO. 2	EACH	2.0			2.0	
54001003	BOX CULVERT END SECTION, CULVERT NO. 3	EACH	2.0				2.0
54011203	PRECAST CONCRETE BOX CULVERTS 12' X 3'	FOOT	194.0			194.0	
54011206	PRECAST CONCRETE BOX CULVERTS 12' X 6'	FOOT	108.0		108.0		
54021203	PRECAST CONCRETE BOX CULVERTS 12' X 3' (M273)	FOOT	78.0				78.0
54213450	END SECTIONS 15"	EACH	2.0	2.0			
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	2.0	2.0			
542A1063	PIPE CULVERTS, CLASS A, TYPE 2 18"	FOOT	95.0	95.0			
542D0220	PIPE CULVERTS, CLASS D, TYPE 1 15"	FOOT	74.0	74.0			
61100605	MISCELLANEOUS CONCRETE	CU YD	2.7	2.7			
61101017	STORM SEWERS PROTECTED, CLASS A, 15"	FOOT	145.0	145.0			
* 63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	1,125.0	1,125.0			
* 63000025	STEEL PLATE BEAM GUARD RAIL, ATTACHED TO STRUCTURES	FOOT	75.0	75.0			
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	2.0	2.0			
* 63100169	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) FLARED	EACH	6.0	6.0			
63200310	GUARDRAIL REMOVAL	FOOT	365.0	365.0			
63500120	DELINEATOR REMOVAL	EACH	7.0	7.0			
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	31.0	31.00			
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	7.0	7.0			
67100100	MOBILIZATION	L SUM	1.0	1.0			
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1.0	1.0			
70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1.0	1.0			
70300220	TEMPORARY PAVEMENT MARKING-LINE 4"	FOOT	7,432.0	7,432.0			
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	2,477.0	2,477.0			
* 72000100	SIGN PANEL - TYPE 1	SQ FT	4.0	4.0			
* 72900100	METAL POST - TYPE A	FOOT	12.5	12.5			
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	7,432.0	7,432.0			
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	44.0	44.0			
* 78200405	GUARDRAIL MARKERS	EACH	21.0	21.0			
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	8.0	8.0			
* A2002656	TREE, CARYA ILLINOENSIS (PECAN), 2" CALIPER, BALLED AND BURLAPPED	EACH	15.0	15.0			
* A2002616	TREE, CARYA CORDIFORMIS (BITTERNUT HICKORY), 2" CALIPER, BALLED AND BURLAPPED	EACH	15.0	15.0			

FILE NAME =	USER NAME = keysrb	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ci:\pw_work\pwidot\keysrb\d0101441\057052-shr-500.dgn		DRAWN -	REVISED -						71	121R	MCLEAN	87	4
	PLOT SCALE = 100.0000 / IN.	CHECKED -	REVISED -						CONTRACT NO. 70592				
	PLOT DATE = 8/9/2010	DATE -	REVISED -		SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT		