

SUMMARY OF QUANTITIES					CONSTRUCTION AND SAFETY TYPE CODE					
CODE NO.	ITEM	SP. PROV.	UNIT	80% FED. 20% STATE TOTAL QUANTITIES	0005 ROADWAY	0011 STRUCTURE				
48203100	HOT-MIX ASPHALT SHOULDERS		TON	34	34					
50100100	REMOVAL OF EXISTING STRUCTURES		EACH	1		1				
50105220	PIPE CULVERT REMOVAL		FOOT	17	17					
50200100	STRUCTURE EXCAVATION		CU YD	341		341				
50300100	FLOOR DRAINS		EACH	26		26				
50300225	CONCRETE STRUCTURES		CU YD	290.6		290.6				
50300255	CONCRETE SUPERSTRUCTURE		CU YD	719.0		719.0				
50300260	BRIDGE DECK GROOVING		SQ YD	1965		1965				
50300280	CONCRETE ENCASEMENT		CU YD	11.2		11.2				
50300300	PROTECTIVE COAT		SQ YD	2569		2569				
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL		L SUM	1		1				
50500505	STUD SHEAR CONNECTORS		EACH	6588		6588				
50800105	REINFORCEMENT BARS		POUND	4940		4940				
50800205	REINFORCEMENT BARS, EPOXY COATED		POUND	250,850		250,850				
50800515	BAR SPLICERS		EACH	2356		2356				
51201600	FURNISHING STEEL PILES HP12X53		FOOT	900		900				
51202305	DRIVING PILES		FOOT	900		900				
51203600	TEST PILE STEEL HP12X53		EACH	2		2				
51204650	PILE SHOES		EACH	32		32				
51500100	NAME PLATES		EACH	1		1				
* 51603000	DRILLED SHAFT IN SOIL		CU YD	135.1		135.1				
* 51604000	DRILLED SHAFT IN ROCK		CU YD	28.8		28.8				
52000110	PREFORMED JOINT STRIP SEAL		FOOT	68		68				
52000220	FINGER PLATE EXPANSION JOINT, 6"		FOOT	64		64				
52000600	FABRIC REINFORCED ELASTOMERIC TROUGH		FOOT	76		76				
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I		EACH	18		18				
52100020	ELASTOMERIC BEARING ASSEMBLY, TYPE II		EACH	18		18				
52100530	ANCHOR BOLTS, 1 1/4"		EACH	48		48				
52100510	ANCHOR BOLTS 3/4"		EACH	24		24				
52100520	ANCHOR BOLTS, 1"		EACH	12		12				
542D5479	PIPE CULVERTS, CLASS D, TYPE 1 EQUIVALENT ROUND-SIZE 24"		FOOT	40	40					
54215547	METAL END SECTIONS 12"		EACH	2	2					
54215769	METAL END SECTIONS, EQUIVALENT ROUND-SIZE 24"		EACH	2	2					