

## LEGEND

- 1 EXISTING CONTINUOUSLY REINFORCED P.C.C. PAVEMENT 8"
- ② EXISTING STABILIZED SUB-BASE 4"
- 3 EXISTING AGGREGATE SHOULDERS, TYPE B
- THE EXISTING WIDTH OF SHOULDERS ADJACENT TO THE
  PAVEMENT SHALL BE SLOPED SO THAT THE ALGEBRAIC
  DIFFERENCE BETWEEN THE PAVEMENT AND THE SHOULDER
  WILL NOT BE GREATER THAN 0.07 FT/FT
- 5 EXISTING HOT-MIX ASPHALT SHOULDERS 8"
- 6 EXISTING PIPE UNDERDRAIN 4" (STANDARD 2327)
- TEXISTING HOT-MIX ASPHALT, VARIABLE DEPTH
- 8 PROPOSED HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"
- 9 PROPOSED HOT-MIX ASPHALT SURFACE, 1 1/2"
- (1) PROPOSED LEVELING BINDER, VARIES 3/4" TO 5"
- 11) PROPOSED AGGREGATE WEDGE SHOULDER, TYPE B

FILE NAME =	USER NAME = owenbj	DESIGNED -	REVISED -	
ci\pw_work\pwidot\owenbj\oms66748\d876c	33-sht-plan.dgn	DRAWN -	REVISED -	
	PLOT SCALE = 50.0000 '/ IN.	CHECKED -	REVISED -	ĺ
	PLOT DATE = 8/10/2010	DATE -	REVISED -	L

STATE OF ILLINOIS						
DEPARTMENT	OF	TRANSPORTATION				

											_	
	INDEX OF SHEETS, HIGHWAY STANDARDS,							F.A.I SECTION		COUNTY TOTAL SHE		SHEET NO.
GENERAL NOTES, AND COMMITMENTS								255 82-7HB-I		ST. CLAIR	43	3
								CONT		CONTRACT	NO.	76C33
SCALE:	SHEET NO.	OF	SHEETS	STA.		TO STA.	FED.	ROAD DIST. NO.	ILLINOIS FED. A	ID PROJECT		