



NOTES:

- 1. It Shall be the responsibility of the Contractor to verify all dimensions and conditions existing in the field prior to construction and ordering materials.
- 2. The concrete shall be constructed as shown in accordance with Section 503 of the "Standard Specifications for Road and Bridge Construction".
- 3. All exposed edges of concrete walls shall have a 3/4" x 45° chamfer, except as shown otherwise. Chamfers on vertical edges shall be continued a minimum of one foot below finished ground level.
- Stair tread edges shall be protected with Balco, Inc. Model P-200 or equal installed according to manufactures instructions.
- Reinforcement bars shall all be epoxy coated.
- 6. See Landscape Architect sheet 137 for handrail detail.
- Refer to Electrical Plan sheet 41 for lighting insets. Provide box-out in sidewalls for flush panels.
- Stair Tread Nosings shall be installed in two halves to allow for a scored or sawed contraction joint along the centerline of the stairs. The joint shall be sealed with a premium polyurethane sealant in accordance with the Standard Specifications.



ELEVATION



FRONT ELEVATION SECTION B-B

NORTH STAIRS AT BOAT HOUSE PLAN AND ELEVATION PEDESTRIAN RIVERWALK ALONG THE ROCK RIVER WINNEBAGO COUNTY SECTION NO. 06-00543-00-BT STATION 213+11.51

	DESIGNED	СТВ	
	CHECKED	AAG	
	DRAWN	JAW	
	CHECKED	JWH	



SHEET NO. 2 5 SHEETS

100				
F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
	06-00543-00-BT	WINNEBAGO	148	47
		CONTRACT N	0.	85521
FED POAD	DIST NO ILLINOIS	EED AID BBO IE	СТ	