

TOTAL BILL OF MATERIALS

·	SP WALL No. 24 AND LOOKOUT No. 4 SLAB				
<u>A TION</u> walk	ITEM	UNITS	TOTAL		
rian	Structure Excavation	Cu. Yd.	270		
	Concrete Structures	Cu. Yd	95.2		
<u>ONS</u>	Protective Coat	Sq. Yd.	112.7		
Edition	Stud Shear Connectors	Each	328		
Lation	Precast Concrete Lagging	Sq. Ft.	1,078		
<u>S</u>	Furnishing Soldier Piles (W 14x99)	Foot	416		
	Drilling and Setting Soldier Piles in Soil	Cu. Ft.	761		
Concrete)	Drilling and Setting Soldier Piles in Rock	Cu. Ft.	1185		
) teel)	Reinforcement Bars (Epoxy Coated)	Pound	8,125		
	Geocomposite Wall Drain	Sq. Yd.	50.2		
crete)	Form Liner Textured Surface	Sq. Ft.	1,080		
1)					

GENERAL NOTES

12

15.

10. The approximate embedment depth for the soldier pile tip is as provided on the plans and considers a penetration into competent rock of 5.5 feet (minimum) based on the soil boring information and uniaxial compressive rock strength value of 4,000 PSI (minimum) as provided by Terracon Consultants, Inc. The actual top of rock elevation, which qualifies as competent rock meeting the minimum requirements of the design, shall be determined and field verified by the Geotechnical Engineer during the drilling operation at each soldier pile location. Final pile tip elevations shall be a minimum of 5.5 feet below actual top of competent rock elevations.

All exposed edges shall have a $\frac{3}{4}$ " x 45° chamfer, except as shown otherwise. Chamfers on vertical edges shall be continued a minimum of one foot below finished ground level.

Exposed surfaces of concrete shall be given a "rubbed finish" except where form liner is specified.

Contractor shall be responsible for dewatering in accordance 13. with the erosion control plan at no additional cost to the contract.

14. Backfill behind wall shall be placed to the lines and grades as shown on the plans. The Contractor shall take care to ensure the use of suitable material and proper compaction of all fill areas. Compaction shall be performed with a loose thickness of no more than 8" and each lift shall be compacted to a density equal to or greater than 95% standard proctor maximum dry density (ASTM D-698) taking care not to over compact the soil directly behind the wall. Moisture shall be within -2 to +3 percent of optimum. No heavy equipment shall be allowed within 6 feet of the wall during backfilling and compaction. Compaction shall be by hand method, "walk behind", equipment in the areas within 6 feet of the face of the wall.

Backfill of wall behind precast panels must be completed before placement of cast-in-place concrete face. Refer to Precast Panel Details, sheet for additional notes.

	BHORED BHORED BHORED BHORED BHORED BHORE BHOR	PL AL SECTIO S	RAL PLAN SP WALL EDESTRIAN ONG THE R WINNEBAGO DN NO. 06– TATION 211- STATION 21	<u>No. 24</u> <u>RIVERWALK</u> <u>COCK RIVER</u> <u>COUNTY</u> 00543-00- +87.04 TO	
1	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1		and the second		TOTAL SHEETS	SHEET NO. 99
1		SECTION	COUNTY	148	