

CODE NO.	ITEM	UNIT	TOTAL QUANTITY URBAN	CONSTRUCTION CODE		
				80% FEDERAL 20% STATE	80% FEDERAL 20% STATE	100% STATE
				ROADWAY	ROADWAY	ROADWAY
				COOK COUNTY	KANE COUNTY	
				0005	0005	0005
20200100	EARTH EXCAVATION	CU YD	68	63.5	4.5	
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	234	203	31	
25200110	SODDING, SALT TOLERANT	SQ YD	234	203	31	
40600290	BITUMINOUS MATERIALS (TACK COAT)	POUND	50562	43888	6674	
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	190	165	25	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	504	504		
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	535	276	259	
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	749	650	99	
40603200	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-4.75, N50	TON	3004	2607	397	
40604172	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, IL-9.5, MIX "E", N70	TON	7444	6461	983	
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	4441	3855	586	
42400800	DETECTABLE WARNINGS	SQ FT	489	447	42	
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	63317	63317		
44000600	SIDEWALK REMOVAL	SQ FT	4028	3496	532	

* SPECIALTY ITEM

MODEL: Default
FILE: Main: p:\ulidect-pw-bentley.com\PROJECTS\DOT Offices\District: 1\Projects\10221\CADD\data\Design\10221-shh-500.dgn

USER NAME = alramahij	DESIGNED -	REVISED -
	DRAWN -	REVISED -
PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED -
PLOT DATE = 8/13/2021	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**IL ROUTE 19 (IRVING PARK RD)
SUMMARY OF QUANTITIES**

SCALE: SHEET 3 OF 45 SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1321	2021-016-R5&SW	COOK/KANE	45	3
CONTRACT NO. 62N52				
ILLINOIS FED. AID PROJECT				

 REVISED SHEET 10/19/2021

CODE NO.	ITEM	UNIT	TOTAL QUANTITY URBAN	CONSTRUCTION CODE		
				80% FEDERAL 20% STATE	80% FEDERAL 20% STATE	100% STATE
				ROADWAY	ROADWAY	ROADWAY
				COOK COUNTY	KANE COUNTY	
				0005	0005	0005
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	1615	1402	213	
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	4549	3795	754	
X0320050	CONSTRUCTION LAYOUT (SPECIAL)	L SUM	1	0.5	0.5	
X4400100	PORTLAND CEMENT CONCRETE SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	3134	1371	1763	
X4400501	COMBINATION CURB AND GUTTER REMOVAL AND REPLACEMENT LESS THAN OR EQUAL TO 10 FEET	FOOT	350	304	46	
X6030310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	35	35		
Z0004562	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	1050 1235	911 1096	139	△
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	798 399	329	70	△
Z0018600	DRAINAGE STRUCTURES TO BE RECONSTRUCTED	EACH	20	20		
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	51.4	25.7	25.7	
Z0033700	LONGITUDINAL JOINT SEALANT	FOOT	31534	29733	1801	
∅ Z0076600	TRAINEES	HOURS	500	500		
∅ Z0076604	TRAINEES - TRAINING PROGRAM GRADUATE	HOURS	500	500		

* SPECIALTY ITEM

△ REVISED SHEET 10/19/2021

∅ 0042

MODEL: Default
FILE: Main: p:\ulidect-pw-bentley.com\PROJECTS\DOT Offices\District 1\Projects\10221\CAD\data\Design\10221-sh-500.dgn

USER NAME = alramahij	DESIGNED -	REVISED -
	DRAWN -	REVISED -
PLOT SCALE = 100.0000 ' / in.	CHECKED -	REVISED -
PLOT DATE = 8/13/2021	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**


**IL ROUTE 19 (IRVING PARK RD)
SUMMARY OF QUANTITIES**

SCALE: SHEET 7 OF 45 SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1321	2021-016-R5&SW	COOK/KANE	45	7
			CONTRACT NO. 62N52	
ILLINOIS FED. AID PROJECT				



POPLAR CREEK



LEGEND

xx.xx'

EXISTING LENGTH

=====

PROPOSED SIDE CURB

()

EXISTING ELEVATION/SLOPE



PROPOSED SIDEWALK



DETECTABLE WARNINGS



SIDEWALK REMOVAL
REPLACE W/TOPSOIL & SOD

MODEL: Default
 FILE: \\nas01-pw-bentley.com\PWDOT\Documents\DOT_Offices\Bharat_IIP\Projects\110221\ICAD\Draws\Drawings\110221-Sub-detail.dgn

USER NAME = alramahij	DESIGNED -	REVISED - JA 10-18-2021
	DRAWN -	REVISED -
PLOT SCALE = 10.0000' / in.	CHECKED -	REVISED -
PLOT DATE = 10/18/2021	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SIDEWALK DETAIL PLAN
IL 19 (IRVING PARK RD) - IL 25 TO IL 59

SCALE: SHEET OF SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1321	2021-016-R5&SW	COOK/KANE	45	27B
CONTRACT NO. 62N52				
ILLINOIS FED. AID PROJECT				

ADDED ENTIRE SHEET

