

## NOTES:

- 1. USE BLACK LETTERING ON ORANGE BACKGROUND.
- 2. ERECT SIGNS IN ADVANCE OF THE LOCATION FOR THE "ROAD CONSTRUCTION AHEAD" SIGN AT LOCATIONS AS DIRECTED BY THE ENGINEER.
- 3. ERECT SIGN (1) WITH INSTALLED PANEL (2) ONE WEEK PRIOR TO THE START OF CONSTRUCTION.
- 4. REMOVE PANEL 2 SOON AFTER THE START OF CONSTRUCTION.
- 5. SEE SPECIAL PROVISION FOR "TEMPORARY INFORMATION SIGNING" FOR ADDITIONAL INFORMATION.
- 6. ONE SIGN ASSEMBLY EQUALS 25.70 SQ. FT. (2.3 SQ. M.)
- 7. SHALL BE PAID FOR AS TEMPORARY INFORMATION SIGNING.

ALL DIMENSIONS ARE IN INCHES (MILLIMETERS) UNLESS OTHERWISE SHOWN.

## ARTERIAL ROAD INFORMATION SIGN

CONSULTING ENGINEERS 1560 WALL ST, SUITE 222 NAPERVILLE, ILLINOIS 60563 PH <sub>4</sub> (630) 577-9100	USER NAME = \$USER\$	DESIGNED - MJY		STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	DISTRICT ONE DETAIL SHEETS I-55 WEST FRONTAGE ROAD OVER (I & M) CANAL		F.A.I. RTE. SECTION	COUNTY	TOTAL	SHEET NO.
		DRAWN - ST	REVISED -				55 86 B-3-R	WILL	38	38
	PLOT SCALE = \$SCALE\$	CHECKED - MJY	REVISED -				D-91-097-09	CONTRACT	NO. 6	OF53
	PLOT DATE = \$DATE\$	DATE - 07/08/2009	REVISED -		SCALE: NONE	SHEET NO. 38 OF 38 SHEETS STA, 1097+00 TO STA, 1101+50	FED. ROAD DIST. NO. ILLINOIS FED.	AID PROJECT		