


PRE-CONSTRUCTION STAGE, STAGE 1, STAGE 2 AND AFTER

ALL PROPOSED GEOMETRICS ARE BUILT AND OPEN TO TRAFFIC



| GEOMETRICS AS NEEDED. | NOTE 1: THE GREEN AND YELLOW LEFT TURN ARROW SECTIONS IN THE 5-SECTION SIGNAL HEADS FOR THE NORTHBOUND AND SOUTHBOUND DIRECTION OF TRAFFIC SHALL BE BAGGED AND DISCONNECTED AT THE CONTROLLER DURING CONSTRUCTION STAGE 3. THE PHASE DESIGNATION DIAGRAM SHALL BE MODIFIED AS SHOWN IN THE PLANS AND AS DIRECTED BY THE ENGINEER. THESE SECTIONS SHALL BE RECONN AND UNBAGGED WHEN PROPOSED ROADWAY GEOMETRICS ARE BUILT AND OPEN TO TRAFFIC. THE PHASE DESIGNATION DIAGRAM SHALL BE MODIFIED FOR THE PROPOSED GEOMETRICS AS NEEDED. | ECTED |
|-----------------------|--|-------|
|-----------------------|--|-------|

NOTE 2: THESE 3-SECTION SIGNAL HEADS WITH RED, YELLOW, AND GREEN LEFT TURN ARROW INDICATIONS ARE NEEDED IN CONSTRUCTION STAGE 3 AND SHALL BE ACTIVATED ONLY DURING THIS CONSTRUCTION STAGE. THESE SIGNAL HEADS SHALL BE DISCONNECTED AND REMOVED AFTER CONSTRUCTION STAGE 3.



| F.A.U. RTE. | SECTION | | COUNTY | TOTAL SHEETS | SHEET NO |
|---------------------|---------|----------|--------|-----------------|-------------|
| 2578 | 532B-1 | | DuPAGE | 117 | 43 |
| STA. TO STA. | | | | | |
| FED. ROAD DIST. NO. | | ILLINOIS | FED. A | ID PROJECT: | |

CONTRACT * 62881

SCHEDULE OF QUANTITIES

| QUANTITY | UNIT | ITEM |
|----------|------|--|
| 262 | FOOT | CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL |
| 27 | FOOT | CONDUIT IN TRENCH, 4" DIA., GALVANIZED STEEL |
| 126 | FOOT | CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL |
| 3 | EACH | HANDHOLE |
| 1 | EACH | HEAVY-DUTY HANDHOLE |
| 348 | FOOT | TRENCH AND BACKFILL FOR ELECTRICAL WORK |
| 217 | FOOT | DETECTOR LOOP, TYPE 1 |
| 1 | EACH | TEMPORARY TRAFFIC SIGNAL INSTALLATION |
| 1 | EACH | REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT |
| 3 | EACH | REMOVE EXISTING HANDHOLE |
| 152 | FOOT | PREFORMED DETECTOR LOOP |

TEMPORARY CABLE DIAGRAM LEGEND

| R | TEMPORARY TRAFFIC SIGNAL SECTION OR PEDESTRIAN SIGNAL SECTION 12" (300mm) |
|----------------|---|
| \boxtimes | EXISTING TEMPORARY CONTROLLER CABINET |
| $\overline{+}$ | EXISTING TEMPORARY SERVICE INSTALLATION |
| (5) | INDICATES NUMBER OF CONDUCTORS IN CABLE. |

AWG WIRE UNLESS OTHERWISE NOTED.

EMERGENCY VEHICLE LIGHT DETECTOR •-CONFIRMATION BEACON


VEHICLE DETECTOR, INDUCTION LOOP

PEDESTRIAN PUSHBUTTON DETECTOR 0 12" (300mm) PEDESTRIAN SIGNAL SECTION

VIDEO CAMERA ASSEMBLY

GROUND ROD AT ELECTRIC SII SERVICE INSTALLATION

GROUND ROD AT TRAFFIC SIGNAL CONTROLLER



TEMPORARY CABLE PLAN

ALL CONSTRUCTION STAGES

GANDHI AND ASSOCIATES, INC.

ENGINEERS AND PLANNERS 6035 N. NORTHWEST HIGHWAY SUITE 306 CHICAGO, ILLINOIS 60631 TEL. (773) 774-5910



ILLINOIS DEPARTMENT OF TRANSPORTATION

PARTIAL TEMPORARY TRAFFIC SIGNAL CABLE PLAN, PHASE DESIGNATION DIAGRAM, EMERGENCY VEHICLE PREEMPTION SEQUENCE, ILLINOIS ROUTE 53 AT SPRING LAKE DRIVE/MEDINAH DRIVE

SCALE: N.T.S DATE: 05/18/2007 DRAWN BY: KGP/RDP DESIGNED BY: PKG CHECKED BY:

COMPANY:]:*projects*projects 2006*il_rte_53_springlake-medinah_patrick*07_rte53_spr_lk_cd_temp.dgn 10 kM7 2007 10:83:00

ILLINOIS DEPARTMENT OF TRANSPORTATION 201 WEST CENTER COURT SCHAUMBURG, ILLINOIS 60196-1096

ENERGY SUPPLY CONTACT: MR. ROBERT BEATTY
PHONE: (630) 691-4721

ENERGY COSTS TO:

%OPERATION

2260.0

PRE-CONSTRUCTION STAGE, STAGE 1, STAGE 2 AND AFTER

ALL PROPOSED GEOMETRICS ARE BUILT AND OPEN TO TRAFFIC