

SEQUENCE OF CONSTRUCTION:

- 1. CLOSE EXISTING VALVE.
- 2. REMOVE EXISTING HYDRANT.
- 3. INSTALL HYDRANT EXTENSION AND NEW VALVE.
- 4. RELOCATE EXISTING HYDRANT.
- 5. OPEN EXISTING VALVE, REMOVE BOX.
- 6. BACKFILL.
- 7. FLUSH AND TEST FOR CHLORIDE RESIDUAL AND PROVIDE TEST.

ALL WORK TO BE DONE IN ACCORDANCE WITH ARTICLE 564 OF THE STANDARD SPECIFICATIONS. NEW VALVE AND BOX SHALL BE SAME MAKE AND MODEL AS EXISTING.

FIRE HYDRANT TO BE MOVED

ALL DIMENSIONS ARE IN INCHES (MILLIMETERS) UNLESS

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION	
NAME	DATE	ILLINOIS DEPARTMEN	II OF TRANSPORTATION
R. SHAH	09/09/94		
R. SHAH 10/25/94		FIRE HYDRANT TO BE MOVED	
		SCALE: VERT. NONE HORIZ.	DRAWN BY CHECKED BY
			DDEOO OZ (DD)

PLOT FILE PLOT USER

CONTRACT NO. COUNTY TOTAL SHEETS

TO STA.

FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT