



EXISTING TIMBER STEPS TO BE REMOVED  
COST TO BE INCLUDED IN THE COST OF  
REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL

EXISTING TIMBER STEPS TO BE REMOVED  
COST TO BE INCLUDED IN THE COST OF  
REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL

16' - WOOD POST AND RAIL FENCE, 3.5' (TYP.)  
(5:1 TAPER AWAY FROM TRAIL)

WETLAND 2 (50' BUFFER)

WETLAND 3 (100' BUFFER)

EXISTING AT-GRADE TIMBER CROSSING  
TO BE REMOVED BY OTHERS

EXISTING SIDE TRAIL  
REGRADE, PLACE TOPSOIL 6"  
& LANDSCAPE

TAPER TO MEET  
APPROACH SLAB

AGGREGATE SURFACE  
COURSE, TY. A

EXIST. PRAIRIE  
PATH R.O.W.

10' x 12.5' APPROACH SLAB

AGGREGATE SURFACE COURSE, TY. A

CONSTRUCTION LIMITS (TYP.)

P.I. STA. 101+55.15

EXIST. PRAIRIE PATH R.O.W.

STA. 103+00  
MEET EXIST.  
TRAIL

STA. 97+00  
MEET EXIST.  
TRAIL

EXIST. PRAIRIE PATH R.O.W.

2' WIDE x 20' LONG x 6" DEEP (TYP.)  
5 SQ YD STONE RIPRAP, CLASS A1 & FILTER FABRIC

EXIST. PRAIRIE PATH R.O.W.

WETLAND 4 (100' BUFFER)

WETLAND LIMIT (TYP.)

☉ TRACK E.J. & E. RAILROAD

WETLAND 5 (50' BUFFER)

**WETLAND BUFFER NOTE:**

DUE TO THE WETLAND BUFFER SIZE AND THE CLOSE PROXIMITY  
OF THE WETLANDS, ALL WETLAND BUFFERS OVERLAP.  
THE ENTIRE PROJECT AND THE RAILROAD RIGHT-OF-WAY  
ARE WITHIN THE WETLAND BUFFER.  
AS SUCH, NO WETLAND BUFFERS ARE SHOWN ON THE PLANS.

FILE NAME = 98-00313-shr-contour.dgn  
PLOT DATE = 8/4/2009

**CHRISTIAN-ROGE & ASSOCIATES, INC.**  
ENGINEERS-PLANNERS-SURVEYORS  
211 WEST WACKER DRIVE  
CHICAGO, ILLINOIS 60606  
PHONE: (312)372-2023 FAX: (312)372-5274

DESIGNED - S.J.P.	REVISED -
DRAWN - A.C.S.	REVISED -
CHECKED - E.J.M.	REVISED -
DATE - AUGUST 3, 2009	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SITE AND GRADING PLAN  
IL PRAIRIE PATH OVER E.J. & E. RAILROAD**

SCALE: 1" = 20' SHEET NO. 1 OF 1 SHEETS STA. 97+00 TO STA. 103+00

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	98-00313-00-BR	DuPAGE	25	8
CONTRACT NO. 63178				

FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT