### INDEX OF SHEETS

- COVER SHEET
- SUMMARY OF QUANTITIES, GENERAL NOTES AND TYPICAL CROSS SECTIONS
- PLAN AND PROFILE 3.
- CROSS SECTIONS
- CONSTRUCTION DETAILS

## **HIGHWAY STANDARDS**

000001-05 STANDARD SYMBOLS. ABBREVIATIONS AND PATTERNS

TEMPORARY EROSION CONTROL SYSTEMS

424001-05 CURB RAMPS FOR SIDEWALKS 602301-02 INLET - TYPE A

604036-02 **GRATE TYPE 8** 


CONCRETE CURB & COMBINATION CONCRETE CURB & GUTTER 606001-04

OFF-RD OPERATIONS, 2L, 2W, 15' TO 24" FROM PAVEMENT EDGE

URBAN LANE CLOSURE, 2L, 2W, UNDIVIDED 701501-05

701901-01 TYPICAL PAVEMENT MARKINGS

DESIGN DESIGNATION - RATHJE ROAD ADT 7,000 (2030) - COLLECTOR PV=6,650 SU=280 MU=70 2005 ADT - 2,000 2030 ADT - 7.000 EXISTING SPEED LIMIT - 30 MPH PROPOSED SPEED LIMIT - 30 MPH DESIGN PERIOD - 20 YEARS DESIGN SPEED LIMIT - 35 MPH STREET CLASSIFICATION - CLASS II ROAD



FULL SIZE PLANS HAVE BEEN PREPARED USING STANDARD ENGINEERING SCALES, REDUCED SIZED PLANS WILL NOT CONFORM TO STANDARD SCALES, IN MAKING MEASUREMENTS ON REDUCED PLANS, THE ABOVE SCALES MAY BE USED.

JOINT UTILITY LOCATION INFORMATION FOR EXCAVATION

1 - 800 - 892 - 0123 or 811

CONTRACT NO. 63260

STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION **DIVISION OF HIGHWAYS** 

# PLANS FOR PROPOSED FEDERAL AID HIGHWAY


**RATHJE ROAD (FAU 4304) SIDEWALK EXTENSION** 

**CORNING AVE. TO NORTH STREET** 

**PROJECT: ARA-9003(362)** 

**SECTION NO.: 09-00046-00-SW** 


JOB NO.: C-91-677-09 VILLAGE OF PEOTONE **WILL COUNTY** 



# PROJECT LOCATION

GROSS LENGTH= 741.18 FEET = 0.14 MILES NET LENGTH=  $\overline{741.18}$  FEET =  $\overline{0.14}$  MILES

ILLINOIS FED. AID PROJECT ARA-9003(362) CONTRACT #63260





#### DESCRIPTION OF IMPROVEMENT

PRINTED BY THE AUTHORITY OF THE STATE OF ILLINOIS

THIS IMPROVEMENT CONSISTS OF EARTH EXCAVATION, SIDEWALK, LANDSCAPING, AND ALL INCIDENTAL WORK AS NECESSARY TO COMPLETE THE IMPROVEMENT SHOWN HEREIN AND AS DESCRIBED IN THE SPECIFICATIONS.

PREPARED BY OR UNDER THE DIRECT SUPERVISION OF:

