

SECTION	VILLAGE	TOTAL SHEETS	SHEET NO
08-00035-00-SW	WAUCONDA	9	.3
ILLINOIS PROJECT: SRTS - 4008 (028)			
Typical Sections			
CONTRACT NO: 63262			

Legend

- Curb Removal Limits Shall Include 12 Inches In Front And Back Of New Curb To Subgrade Elevation; Cost of Excavation/Disposal to be included in Price of Curb Removal
   Proposed Driveway Pavement Removal
- 2 Proposed PCC Sidewalk, 6"
- (3) Proposed SubBase Granular Material, 3"
- (4) Proposed HMA Driveway Pavement
- 5 Proposed Aggregate Base Course, Ty B (Crushed)
- 6 Proposed Earth Excavation
- Proposed PCC Sidewalk, 5"
- (8) Suitable Excavated Material Backfill
- Proposed Landscaping:
   Topsoil Furnish And Place, 4"
   Seeding, Class 1
   Mulch, Method 3
- (10) Existing Curb
- (11) Proposed Curb Removal
- a) Hot Mix Asphalt Binder Course, IL-19.0, N50, 24"
  b) Hot Mix Asphalt Surface Course, Mix C, N50, 14"
- (13) Proposed Combination Concret Curb & Gutter, TypB-6.12

## ILLINOIS DEPARTMENT OF TRANSPORTATION

## TYPICAL SECTIONS

SCALE: NOT TO SCALE

DATE: 06/11/09

DRAWN BY: CZ

CHECKED BY: RJD