## **COMBINATION CONCRETE CURB & GUTTER** TYPE B-6.12 (MODIFIED)


CAST IRON MANHOLE FRAME AND LID, NEENAH FOUNDRY NO. R-1713 OR EQUAL WITH WORD "STORM," "SANITARY," OR "WATER" CAST INTO LID MINIMUM OF 2" AND MAXIMUM OF 6" OF PRECAST REINFORCED CONCRETE ADJUSTMENT RINGS KEYED JOINT WITH O-RING OR MASTIC SEAL PRECAST REINFORCED CONCRETE SECTIONS FABRICATED IN ACCORDANCE WITH A.S.T.M.

## STRUCTURE RECONSTRUCTION


3/4" PREMOLDED, NON-EXTENDING - JOINT FILLER AT EXPANSION JOINT. SEE NOTES FOR LOCATIONS. EXPANSION JOINT FILLER TO CONFORM WITH CURB AND GUTTER CROSS SECTION. TRIM ANY EXCESS. GREASED PLASTIC EXPANSION CAP 3/4"DIA. -18" EPOXY COATED SMOOTH DOWEL BAR. TWO (2) NOTE:

EXPANSION JOINTS ARE TO BE
CONSTRUCTED AT ALL PC'S AND PT'S
OF INTERSECTION RETURNS AND ALL
OTHER SHORT RADIUS SECTIONS,
CONSTRUCTION JOINTS & AS EACH PER JOINT CONCRETE CURB AND **GUTTER SECTION** DIRECTED BY THE ENGINEER.

TYPICAL CURB AND GUTTER **EXPANSION JOINT** 



A.D.A. RAMP



## **CAST-IN-PLACE DETECTABLE WARNING**

TTANCOCK	USER NAME	DESIGNED	TG	REVISED
ENGINEERING		DRAWN	TG/LEV	REVISED
◆ Civil Engineers 9933 Rosecuti Road Westbester, Black 60154-2780  ◆ Municipal Consultants Phone: 7888664800	PLOT SCALE	CHECKED	JG	REVISED
◆ Municipal Consultants Phone: 708-065-0300 ◆ Established 1911 Fax: 708-065-1212	PLOT DATE	DATE	08/12/09	REVISED
4 Listabiliano 1/11	<u> </u>			11211020

**STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION** 

PETALLO				ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
DETAILS			1026	09-00113-00-RS	COOK	14	8	
						CONTRACT	NO. 63	290
OF	1 SHEETS	STA	ATS OT	EED 2010	DIGT NO 4 HILLINGIG FED	UD DDG IFOT .		