

018-64264 dan 09/29/2009 9: 37: 00 AM

TOTAL DILL		1 LIVIA	<u>_</u>	
ITEM	UNIT	SUPER	SUB	TOTAL
Porous Granular Embankment (Special)	Cu. Yd.		159	159
Concrete Removal	Cu. Yd.		38	38
Slope Wall Removal	Sq. Yd.		605	605
Removal of Existing Concrete Deck	Éach	1		1
Protective Shield	Sq. Yd.	235		235
Structure Excavation	Cu. Yd.		190	190
Floor Drains	Each	12		12
Concrete Structures	Cu. Yd.		91.3	91.3
Concrete Superstructure	Cu. Yd.	331.5		331.5
Bridge Deck Grooving	Sq. Yd.	871		871
Protective Coat	Sq. Yd.	1057		1057
Furnishing and Erecting Structural Steel	Pound	4960		4960
Stud Shear Connectors 🛛 \Lambda 👝 🗠	Each	3003		3003
Cleaning and Painting Steel Bridge No. 2	L. Sum			1
Containment and Disposal of Lead	L. Sum			1
Paint Cleaning Residues (No. 2)	L. Sum			
Reinforcement Bars, Epoxy Coated	Pound	78,040	6,020	84,060
Bar Splicers	Each	630	110	740
Slope Wall 4 Inch	Sq. Yd.		600	600
Temporary Sheet Piling	Sq. Ft.		483	483
Name Plates	Each	1		1
Preformed Joint Strip Seal	Foot	88		88
Elastomeric Bearing Assembly, Type I	Each		14	14
Anchor Bolts, 1''	Each		28	28
Concrete Sealer	Sq. Ft.		404	404
Geocomposite Wall Drain	Sq. Yd.		71	71
Pipe Underdrains for Structures, 4''	Foot		164	164
Jacking and Cribbing	Each		14	14



Г NO.2	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.			
	74	37-4HB-1	HENRY	148	95			
HEETS			CONTRACT	NO. 64	264			
	ILLINOIS FED. AID PROJECT							