

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QTY	ACNHI						
				80% FED. 20% STATE RDWY 1000ZA	ACBRF			ACNHI		
					006-0170 006-0171 X581-5B	006-0172 006-0173 X081-2A	006-0174 006-0175 X081-2A	006-0133 SFTY-2A	006-0127 SFTY-2A	006-0129 SFTY-2A
50800515	BAR SPLICERS	EACH	504		176	160	168			
51100100	SLOPE WALL 4 INCH	SQ YD	920		920					
51201600	FURNISHING STEEL PILES HP12X53	FOOT	4486			4486				
51201800	FURNISHING STEEL PILES HP14X73	FOOT	13393		6807		6586			
51202305	DRIVING PILES	FOOT	17879		6807	4486	6586			
51203600	TEST PILE STEEL HP12X53	EACH	8			8				
51203800	TEST PILE STEEL HP14X73	EACH	20		12		8			
51205200	TEMPORARY SHEET PILING	SQ FT	523		523					
51500100	NAME PLATES	EACH	6		2	2	2			
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	56		56					
52100020	ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	28		28					
52100530	ANCHOR BOLTS, 1 1/4"	EACH	168		168					
52100540	ANCHOR BOLTS, 1 1/2"	EACH	16				16			
54215547	METAL END SECTIONS 12"	EACH	8	8						
58700300	CONCRETE SEALER	SQ FT	820		820					
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	549		176	189	184			
59300100	CONTROLLED LOW-STRENGTH MATERIAL	CU YD	2.5						1	1.5
60100945	PIPE DRAINS 12"	FOOT	349	349						
60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	859		270	333	256			
60900515	CONCRETE THRUST BLOCKS	EACH	8	8						
61000115	TYPE E INLET BOX, STANDARD 610001	EACH	8	8						
* 63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	7880	7880						
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	12	12						
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	24	24						
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	6	6						
* 63100169	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) FLARED	EACH	12	12						
63200310	GUARDRAIL REMOVAL	FOOT	10341	10341						
63500105	DELINEATORS	EACH	236	236						
63500120	DELINEATOR REMOVAL	EACH	236	236						
63801205	TEMPORARY MODULAR CLARE SCREEN	FOOT	39565	39565						

* SPECIALTY ITEMS

FILE NAME =	USER NAME = braboygo	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwork\pwork\braboygo\d0112648\d368908-shd-details.DGN	DRAWN -	REVISED -	I-80			**	BUREAU	344	5	
PLOT SCALE = 50.7353' / IN.	CHECKED -	REVISED -	CONTRACT NO. 66908							
PLOT DATE = Sep 07, 2009 - 02:17:18 PM	DATE -	REVISED -	[ILLINOIS] FED. AID PROJECT							
SCALE: _____		SHEET NO. ___ OF ___ SHEETS		STA. _____ TO STA. _____						

**06-[7BR&BR-1,7VB-M,6BR&6,7 RS-1 & I]