

PAVEMENT MARKING QUANTITIES

LOCATION DESCRIPTION	ALIGNMENT	FROM		TO		THPL PVT MK LINE 4 (FOOT)	PREF PL PM TB LINE 6 (FOOT)	POLYUREA PM T1 LN 4 (FOOT)	POLYUREA PM T1 LN 6 (FOOT)	PAVT MRKING GRVING (FOOT)	RAISED REFL PAVT MKR (EACH)	RAISED REF PVT MKR BR (EACH)
		STATION	OFFSET	STATION	OFFSET							
I-80 WB - INSIDE EDGE LINE	I-80	3458+00.0	32.0 LT	3461+94.9	32.0 LT	395						
I-80 WB - CENTER LINE	I-80	3458+00.0	44.0 LT	3461+94.9	44.0 LT		99				10	
I-80 WB - OUTSIDE EDGE LINE	I-80	3458+00.0	56.0 LT	3461+94.9	56.0 LT	395						
I-80 WB - INSIDE EDGE LINE (BRUSH CREEK BRIDGE)	I-80	3461+94.9	32.0 LT	3466+11.8	32.0 LT			417		417		
I-80 WB - CENTER LINE (BRUSH CREEK BRIDGE)	I-80	3461+94.9	44.0 LT	3466+11.8	44.0 LT				104	104		12
I-80 WB - OUTSIDE EDGE LINE (BRUSH CREEK BRIDGE)	I-80	3461+94.9	56.0 LT	3466+11.8	56.0 LT			417		417		
I-80 WB - INSIDE EDGE LINE	I-80	3466+11.8	32.0 LT	3469+25.0	32.0 LT	313						
I-80 WB - CENTER LINE	I-80	3466+11.8	44.0 LT	3469+25.0	44.0 LT		78			842	8	
I-80 WB - OUTSIDE EDGE LINE	I-80	3466+11.8	56.0 LT	3469+25.0	56.0 LT	313				93		
I-80 EB - INSIDE EDGE LINE	I-80	3454+00.0	32.0 RT	3462+41.7	32.0 RT			842		842		
I-80 EB - CENTER LINE	I-80	3454+00.0	44.0 RT	3462+41.7	44.0 RT				210	370		22
I-80 EB - OUTSIDE EDGE LINE	I-80	3454+00.0	56.0 RT	3462+41.7	56.0 RT			842		93		
I-80 EB - INSIDE EDGE LINE (BRUSH CREEK BRIDGE)	I-80	3462+41.7	32.0 RT	3466+11.8	32.0 RT			370		370		
I-80 EB - CENTER LINE (BRUSH CREEK BRIDGE)	I-80	3462+41.7	44.0 RT	3466+11.8	44.0 RT				93	463		10
I-80 EB - OUTSIDE EDGE LINE (BRUSH CREEK BRIDGE)	I-80	3462+41.7	56.0 RT	3466+11.8	56.0 RT			370		116		
I-80 EB - INSIDE EDGE LINE	I-80	3466+11.8	32.0 RT	3470+75.0	32.0 RT			463		463		
I-80 EB - CENTER LINE	I-80	3466+11.8	44.0 RT	3470+75.0	44.0 RT				116			12
I-80 EB - OUTSIDE EDGE LINE	I-80	3466+11.8	56.0 RT	3470+75.0	56.0 RT			463				
TOTAL						1416	177	4184	523	4589	18	56

PAVEMENT REMOVAL

LOCATION DESCRIPTION	ALIGNMENT	OFFSET DIRECTION	FROM	TO	PAVEMENT REM (SQ YD)
I-80 EB - MAINLINE FULL-DEPTH	I-80	RT	3454+00.0	3461+00.0	1877
I-80 EB - MAINLINE FULL-DEPTH	I-80	RT	3466+11.8	3470+75.0	1235
TOTAL					3112

GUARDRAIL REMOVAL

LOCATION DESCRIPTION	ALIGNMENT	FROM		TO		GUARDRAIL REMOVAL (FOOT)
		STATION	OFFSET	STATION	OFFSET	
I-80 EB - OUTSIDE SHOULDER	I-80	3456+29.4	68.1 RT	3462+41.7	60.3 RT	613
I-80 EB - OUTSIDE OVER BRIDGE	I-80	3462+41.7	60.3 RT	3466+11.8	59.2 RT	370
I-80 EB - OUTSIDE SHOULDER	I-80	3466+11.8	59.2 RT	3467+52.6	68.5 RT	141
I-80 EB - INSIDE SHOULDER	I-80	3461+18.6	5.9 LT	3462+41.7	26.7 RT	128
I-80 EB - INSIDE OVER BRIDGE	I-80	3462+41.7	26.7 RT	3466+11.8	28.4 RT	370
I-80 EB - INSIDE SHOULDER	I-80	3466+11.8	28.4 RT	3466+27.2	28.3 RT	15
I-80 WB - OUTSIDE OVER BRIDGE	I-80	3462+02.8	59.4 LT	3466+11.8	59.3 LT	409
I-80 WB - OUTSIDE SHOULDER	I-80	3466+11.8	59.3 LT	3469+62.6	72.3 LT	351
I-80 WB - INSIDE OVER BRIDGE	I-80	3462+21.8	28.3 LT	3466+11.8	28.6 LT	390
I-80 WB - INSIDE SHOULDER	I-80	3466+11.8	28.6 LT	3467+38.6	2.6 LT	130
TOTAL						2919

REMOVAL OF GUARDRAIL ON BRIDGE WILL BE PAID FOR AS GUARDRAIL REMOVAL

BRIDGE APPROACH SHOULDER DRAINS

LOCATION DESCRIPTION	ALIGNMENT	OFFSET DIRECTION	PAVEMENT REM (SQ YD)	TYPE E INLET BOX, STD (EACH)	PIPE DRAIN, 12" (FOOT)	CONCRETE THRUST BLOCKS (EACH)	METAL END SECTIONS, 12" (EACH)
I-80 EB - SN 006-0170	I-80	RT	365	2	93	2	2
I-80 WB - SN 006-0171	I-80	LT	365	4	168	4	4
TOTALS			730	6	261	6	6

PAVED SHOULDER REMOVAL

LOCATION DESCRIPTION	ALIGNMENT	OFFSET DIRECTION	FROM	TO	PAVED SHLD REMOVAL (SQ YD)
I-80 EB - INSIDE SHOULDER	I-80	RT	3454+00.0	3461+06.0	318
I-80 EB - OUTSIDE SHOULDER	I-80	RT	3058+20.0	3462+41.7	770
I-80 EB - INSIDE SHOULDER	I-80	RT	3466+11.8	3470+75.0	204
I-80 EB - OUTSIDE SHOULDER	I-80	RT	3466+11.8	3470+75.0	439
TOTAL					1730

TYLIN INTERNATIONAL

USER NAME = #USER#	DESIGNED - CAC	REVISED -
PLOT SCALE = #SCALE#	DRAWN - CAC	REVISED -
PLOT DATE = 8/17/2009	CHECKED - JDF	REVISED -
	DATE - 08/14/2009	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

F.A.I. ROUTE 80 (I-80)  
SCHEDULE OF QUANTITIES  
REMOVAL/MISCELLANEOUS QUANTITIES SHEET 1 OF 3

F.A.I. RTE. 80	SECTION *	COUNTY	TOTAL SHEETS NO. 344	SHEET NO. 21
SCALE:		SHEET NO. OF SHEETS	STA. TO STA.	
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
CONTRACT NO. 66908				

\* 06-17BR & BR-1,TVB-M, 6BR & 6, 7 RS-1 & 11