

REVISED

DATE

## **DETOUR SIGNING PLAN** PYATTS PROPOSED BRIDGE IMPROVEMENTS SIGN LEGEND MAX. WIDTH XX'-XX'' X MILES AHEAD 1.7" 15.9" 6" 22.7"

## DETOUR NOTES

- 1. THE CONTRACTOR SHALL FURNISH THE POSTS AND ERECT THE SIGNS AT THE LOCATIONS DIRECTED BY THE ENGINEER. ALL SIGNS SHALL BE POST MOUNTED
- 2. THE ABOVE NOTED WORK, INCLUDING SIGN, POSTS, HARDWARE AND LABOR SHALL BE INCLUDED IN THE CONTRACT UNIT PRICE, EACH, FOR TRAFFIC CONTROL AND PROTECTION, STD 701321 AND NO OTHER COMPENSATION WILL BE ALLOWED.
- 3. THE WIDTH SHOWN ON THE W12-I103 SIGN SHALL BE 11'-0" FOR STAGE 1 AND 11'-6" FOR STAGE 2 OR AS DIRECTED BY THE ENGINEER. THE "X" MILES AHEAD WILL BE DETERMINED BY THE ENGINEER.

## W12-I103

8" | 6" 22" | 8"

10.9" 26.2" 10.9"

34.6′′

SERIES D ALPHABET. NO BORDER. BLACK ON WHITE.

	DETOUR SIGNING								SECTION	COUNTY	TOTAL	SHEET NO.
	AND ROAD CLOSURE							865	16B-2	PERRY	47	11
-		AND HOND OLOGORE								CONTRACT	NO.	78064
- 1	SCALE:	SHEET	٧0.	0F	SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT				