

TEMPORARY DITCH CHECKS

PLACEMENT OF TEMPORARY STRAW BALE DITCH CHECK IN DRAINAGEWAY




POINTS A SHOULD BE HIGHER THAN POINT B

SPACING BETWEEN TEMPORARY DITCH CHECKS



- L = THE DISTANCE SUCH THAT POINTS A AND B ARE OF EQUAL ELEVATION
- B = THE LOW POINT IN CENTER OF CHECK

SEEDING & MULCHING



GENERAL NOTES

IN GENERAL, ALL EARTH SURFACES DISTURBED DURING CONSTRUCTION OPERATIONS SHALL BE SEEDED AND MULCHED UPON COMPLETION OF ALL GRADING OPERATIONS.

FERTILIZER NUTRIENTS AND LIMESTONE SHALL BE APPLIED TO ALL SEEDED AREAS.


THE RATES OF APPLICATION OF FERTILIZER, MULCH AND LIME-STONE SHALL BE AS SPECIFIED IN THE SPECIAL PROVISIONS.

SECTIONS 250 AND 251 OF THE STANDARD SPECIFICATIONS SHALL GOVERN THIS WORK EXCEPT AS SPECIFIED HEREIN OR AS NOTED IN THE SPECIAL PROVISIONS.

DETAILS OF CONCRETE COLLAR

REVISIONS
REDRAWN 2-15REVISED 8-15REVISED 6-3REVISED 6-3REVISED 6-3-

BUTT JOINT



IOINT

EXISTING
BOX
CULVERT

OF PIPE

8"


SIDE VIEW

END VIEW

SCALE:

REMOVE PORTION OF EXIST

HEADWALL DOWN TO 12" BELOW FINISHED GRADE.



THE CONCRETE COLLAR SHALL BE PAID FOR AT THE CONTRACT UNIT PRICE PER CUBIC YARD FOR **CONCRETE COLLAR,** AS SHOWN ON THE PLANS, WHICH PRICE SHALL INCLUDE THE REMOVAL OF SUCH PORTIONS OF THE EXISTING HEADWALLS AS MAY BE REQUIRED.

CLASS SI CONCRETE SHALL BE USED THROUGHOUT.

877

| REVISIONS | REDRAWN | 2-15 | REVISED | REVIS

FILE NAME = USER NAME = \$USER\$ DESIGNED - REVISED
\$FILEL\$

PLOT SCALE = \$SCALE\$ CHECKED - REVISED
PLOT DATE = \$DATE\$ DATE - REVISED -

STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION

DETAILS

IL 141 OVER TRIBUTARY TO CANE CREEK

SHEET NO. OF SHEETS STA. TO STA.