

SUMMARY OF QUANTITIES

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
6371	93-00295-03-PV	MCLEAN	109	4
STA.		TO STA.		
ILLINOIS F.A. PROJ. NO. M-5227(046)				
CONTRACT NO. 91351				

SUMMARY OF QUANTITIES								
CODE NO.	ITEM	SAFETY CODE		2A		1F	Y060	Y060
		CONSTRUCTION CODE	TOTAL QUANTITY	HAMILTON ROAD (CITY)	MAIN STREET (CITY)	TRAFFIC SIGNALS (CITY & STATE)		
* 20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	92	74	18			
* 20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	66	66				
△ 20101200	TREE ROOT PRUNING	EACH	8	8				
△ 20101350	TREE PRUNING (OVER 10 INCH DIAMETER)	EACH	8	8				
20200100	EARTH EXCAVATION	CU YD	12726	11350	1376			
* 20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	650	575	75			
20800150	TRENCH BACKFILL	CU YD	6622	2530	34		944	3114
* 20900330	GRANULAR BACKFILL	TON	1333	1179	154			
* 21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	1950	1725	225			
△* 21101505	TOPSOIL EXCAVATION AND PLACEMENT	CU YD	2255	2151	104			
△* 21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	500	500				
△* 25000110	SEEDING, CLASS 1A	ACRE	4.2	4.0	0.2			
△ 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	378	360	18			
△ 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	378	360	18			
△ 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	378	360	18			
△* 25100125	MULCH, METHOD 3	ACRE	3.2	3.0	0.2			
△* 25100630	EROSION CONTROL BLANKET	SQ YD	5000	5000				
△ 25200100	SODDING	SQ YD	50	50				
△ 25200200	SUPPLEMENTAL WATERING	UNIT	1	1				
* 25300910	SALVAGING AND TRANSPLANTING TREES, SPECIAL	EACH	3	3				
△* 28000255	TEMPORARY EROSION CONTROL SEEDING	ACRE	4.2	4.0	0.2			
28000400	PERIMETER EROSION BARRIER	FOOT	3675	3335	340			
28000500	INLET AND PIPE PROTECTION	EACH	4	4				
* 28000510	INLET FILTERS	EACH	53	44	9			
31200500	STABILIZED SUB-BASE - HOT-MIX ASPHALT, 4"	SQ YD	15153	15153				
35100500	AGGREGATE BASE COURSE, TYPE A 6"	SQ YD	2817	2817				
35101100	AGGREGATE BASE COURSE, TYPE A 12"	SQ YD	16878	15153	1725			
35300400	PORTLAND CEMENT CONCRETE BASE COURSE 9"	SQ YD	1250		1250			
35800100	PREPARATION OF BASE	SQ YD	900	900				
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	450	426	24			
* 40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	405	390	15			
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	980	740	240			
40600300	AGGREGATE (PRIME COAT)	TON	5		5			
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	1	1				
40600845	POLYMERIZED LEVELING BINDER (MACHINE METHOD), N90	TON	128		128			

* SEE SPECIAL PROVISIONS
 **NON-PARTICIPATING WORK
 △ SPECIALTY ITEMS

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

DATE : 6-09
 DRAWN BY : J.L.B.
 CHECKED BY : R.L.H.
 SCALE : NONE