

SUMMARY OF QUANTITIES

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
6371	93-00295-03-PV	MCLEAN	109	5
STA.		TO STA.		
ILLINOIS F.A. PROJ. NO. M-5227(046)				
CONTRACT NO. 91351				

SUMMARY OF QUANTITIES									
CODE NO.	ITEM	SAFETY CODE		2A	2A	1F	Y060	Y060	
		CONSTRUCTION CODE	UNIT	TOTAL QUANTITY	J000	I000			Y031
					HAMILTON ROAD (CITY)	MAIN STREET (CITY)	TRAFFIC SIGNALS (CITY & STATE)	WATER MAIN** CITY	SANITARY SEWER** CITY
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT		SQ YD	64	64				
* 40600990	TEMPORARY RAMP		SQ YD	393	393				
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70		TON	330	330				
40603545	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90		TON	192		192			
* 42000301	PORTLAND CEMENT CONCRETE PAVEMENT 8" (JOINTED)		SQ YD	13667	13667				
42001300	PROTECTIVE COAT		SQ YD	14926	14926				
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH		SQ YD	415	415				
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH		SQ YD	771	473	298			
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH		SQ FT	14169	11976	2193			
* 42400800	DETECTABLE WARNINGS		SQ FT	80	32	48			
44000100	PAVEMENT REMOVAL		SQ YD	5914	5914				
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"		SQ YD	576		576			
44000200	DRIVEWAY PAVEMENT REMOVAL		SQ YD	1516	1063	453			
44000300	CURB REMOVAL		FOOT	72		72			
44000500	COMBINATION CURB AND GUTTER REMOVAL		FOOT	2196	986	1210			
44000600	SIDEWALK REMOVAL		SQ FT	2910	399	2511			
44003100	MEDIAN REMOVAL		SQ FT	473	98	375			
44200962	CLASS B PATCHES, TYPE III, 9 INCH		SQ YD	25				25	
44201741	CLASS D PATCHES, TYPE II, 8 INCH		SQ YD	25				25	
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT		FOOT	1652	595	1057			
* 50105210	REMOVE EXISTING CULVERTS		FOOT	96	96				
* 54248515	CONCRETE COLLAR		EACH	15	9	6			
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"		FOOT	78	78				
550A0180	STORM SEWERS, CLASS A, TYPE 1 42"		FOOT	6	6				
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"		FOOT	1324	1316	8			
550A0360	STORM SEWERS, CLASS A, TYPE 2 15"		FOOT	785	785				
550A0380	STORM SEWERS, CLASS A, TYPE 2 18"		FOOT	16	6	10			
550A0410	STORM SEWERS, CLASS A, TYPE 2 24"		FOOT	1051	1051				
550A0430	STORM SEWERS, CLASS A, TYPE 2 30"		FOOT	653	653				
* 550B0010	STORM SEWERS, CLASS B, TYPE 1 4"		FOOT	20	20				
* 550B0030	STORM SEWERS, CLASS B, TYPE 1 8"		FOOT	89	89				
* 55100200	STORM SEWER REMOVAL 6"		FOOT	95	95				
* 55100500	STORM SEWER REMOVAL 12"		FOOT	285	275	10			
* 55100900	STORM SEWER REMOVAL 18"		FOOT	40	6	34			
* 55101800	STORM SEWER REMOVAL 42"		FOOT	6	6				

* SEE SPECIAL PROVISIONS
 **NON-PARTICIPATING WORK

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

DATE : 6-09
 DRAWN BY : J.L.B.
 CHECKED BY : R.L.H.
 SCALE : NONE