

# SUMMARY OF QUANTITIES

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
6371	93-00295-03-PV	MCLEAN	109	8
STA.		TO STA.		
ILLINOIS F.A. PROJ. NO. M-5227(046)				
CONTRACT NO. 91351				

SUMMARY OF QUANTITIES								
CODE NO.	ITEM	SAFETY CODE		2A		1F	Y060	Y060
		CONSTRUCTION CODE	TOTAL QUANTITY	J000	I000	Y031		
		UNIT		HAMILTON ROAD (CITY)	MAIN STREET (CITY)	TRAFFIC SIGNALS (CITY & STATE)	WATER MAIN** CITY	SANITARY SEWER** CITY
△*	81017530	CONDUIT IN TRENCH, 2 1/2" DIA., COILABLE NONMETALLIC CONDUIT	FOOT	160			160	
△*	81017535	CONDUIT IN TRENCH, 3" DIA., COILABLE NONMETALLIC CONDUIT	FOOT	47			47	
△*	81017555	CONDUIT IN TRENCH, 5" DIA., COILABLE NONMETALLIC CONDUIT	FOOT	10			10	
△*	81028060	CONDUIT, BORED AND PULLED, COILABLE NON-METALLIC CONDUIT 2"	FOOT	695			695	
△*	81028100	CONDUIT, BORED AND PULLED, COILABLE NON-METALLIC CONDUIT 4"	FOOT	230			230	
△*	81028120	CONDUIT, BORED AND PULLED, COILABLE NON-METALLIC CONDUIT 5"	FOOT	155			155	
△*	81306500	REMOVE EXISTING JUNCTION BOX	EACH	2			2	
△*	81400700	HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	15			15	
△*	81400720	DOUBLE HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	1			1	
△*	81702130	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 6	FOOT	1700			1700	
△	81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	581	130	321	130	
△	81900302	TRENCH AND BACKFILL WITH SCREENINGS OR SAND	FOOT	1490			1490	
△*	82102400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT	EACH	4			4	
△*	83600110	LIGHT POLE FOUNDATION (SPECIAL)	EACH	3	2	1		
△	84200700	LIGHTING FOUNDATION REMOVAL	EACH	3	2	1		
△*	84400105	RELOCATE EXISTING LIGHTING UNIT	EACH	3	2	1		
△*	85700305	FULL-ACTUATED CONTROLLER AND TYPE V CABINET, SPECIAL	EACH	1			1	
△*	86200200	UNINTERRUPTABLE POWER SUPPLY, STANDARD	EACH	1			1	
△*	87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	1450			1450	
△*	87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	1650			1650	
△*	87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	2375			2375	
△*	87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	2775			2775	
△*	87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	11600			11600	
△*	87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2C	FOOT	75			75	
△*	87704188	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 54 FT. (SPECIAL)	EACH	4			4	
△	87800100	CONCRETE FOUNDATION, TYPE A	FOOT	12			12	
△*	87800150	CONCRETE FOUNDATION, TYPE C	FOOT	4			4	
△*	87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	60			60	
△*	88040070	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3 SECTION, BRACKET MOUNTED	EACH	2			2	
△*	88040090	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	8			8	
△*	88040150	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	6			6	
△*	88040160	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, MAST ARM MOUNTED	EACH	6			6	
△	88200410	TRAFFIC SIGNAL BACKPLATE, LOUVERED, FORMED PLASTIC	EACH	22			22	
△*	88600100	DETECTOR LOOP, TYPE I	FOOT	1900			1900	
△*	88700200	LIGHT DETECTOR	EACH	4			4	

\*SEE SPECIAL PROVISIONS  
 \*\*NON-PARTICIPATING WORK  
 △ SPECIALTY ITEMS

ILLINOIS DEPARTMENT OF TRANSPORTATION

## SUMMARY OF QUANTITIES

DATE : 6-09  
 DRAWN BY : J.L.B.  
 CHECKED BY : R.L.H.