

SUMMARY OF QUANTITIES

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
6371	93-00295-03-PV	MCLEAN	109	10
STA.		TO STA.		
ILLINOIS F.A. PROJ. NO. M-5227(046)				
CONTRACT NO. 91351				

SUMMARY OF QUANTITIES						
CODE NO.	ITEM	SAFETY CODE		2A	2A	1F
		CONSTRUCTION CODE	J000	I000	Y031	Y060
		UNIT	TOTAL QUANTITY	HAMILTON ROAD (CITY)	MAIN STREET (CITY)	TRAFFIC SIGNALS (CITY & STATE)
Δ*	XX006533	PEDESTRIAN SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, BRACKET MOUNTED, COUNTDOWN TIMER	EACH	8		8
*	XX007744	CONCRETE ENCASEMENTS	EACH	1		1
*	Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1	
*	Z0022800	FENCE REMOVAL	FOOT	20	20	
*	Z0051500	REMOVING AND RESETTING STREET SIGNS	EACH	1	1	
Δ*	Z0059500	SANITARY SEWER, TYPE 2 6"	FOOT	116		116
Δ*	Z0059600	SANITARY SEWER, TYPE 2 8"	FOOT	663		663
Δ*	Z0060800	SANITARY SEWER, TYPE 3 6"	FOOT	479		479
Δ*	Z0060900	SANITARY SEWER, TYPE 3 8"	FOOT	1303		1303
Δ*	XX008164	DUCTILE IRON WATER MAIN 14" RESTRAINED JOINT TYPE	FOOT	14		14
*	XX008165	RESTRICTED DEPTH MANHOLES, 6'-DIAMETER, TYPE 37M GRATE	EACH	1	1	
Δ*	XX008166	HDPE WATER MAIN DIRECTIONAL DRILLING 14"	FOOT	120		120
Δ*	XX008167	CASING PIPE 4"	FOOT	40		40
Δ*	XX008168	CASING PIPE 18"	FOOT	22		22
Δ*	Z0023900	FILLING EXISTING WELLS	EACH	1	1	
Δ*	XX008169	PEDESTRIAN PUSH-BUTTON POST (SPECIAL)	EACH	4		4

*SEE SPECIAL PROVISIONS
 **NON-PARTICIPATING WORK
 Δ SPECIALTY ITEM

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

DATE : 6-09
 DRAWN BY : J.L.B.
 CHECKED BY : R.L.H.

SCALE : NONE