

SCHEDULE OF QUANTITIES

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
6371	93-00295-03-PV	MCLEAN	109	12
STA.		TO STA.		
ILLINOIS F.A. PROJ. NO. M-5227(046)				
CONTRACT NO. 91351				

42300400
PORTLAND CEMENT CONCRETE DRIVEWAY
PAVEMENT 8 INCH

STATION	TO STATION	SO YD
CITY - HAMILTON ROAD		
1002+97 LT. & RT.		15.5
254+00.0 LT. - C.E.		63.3
255+67.2 LT. - C.E.		47.7
256+17.8 LT. - C.E.		50.8
257+75.0 LT. - C.E.		63.3
258+73.8 RT. - C.E.		76.0
261+10.0 RT. - C.E.		156.5
CITY - HAMILTON ROAD SUBTOTAL		473.1
CITY - MAIN STREET		
297+24.0 RT. - C.E.		63.4
300+00.7 LT. - C.E.		136.4
302+07.2 LT. - C.E.		35.0
303+18.0 LT. - C.E.		63.1
CITY - MAIN STREET SUBTOTAL		297.9
TOTAL		771.0

60600505
CONCRETE CURB (SPECIAL)

STATION	TO STATION	FOOT
CITY - MAIN STREET		
C.E. - 300+00.7 LT.		65
TOTAL		65

60600605
CONCRETE CURB, TYPE B

STATION	TO STATION	FOOT
CITY - HAMILTON ROAD		
260+94.0 RT.	261+25.9 RT.	56
TOTAL		56

42400100
PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH

STATION	TO STATION	SO FT
CITY - HAMILTON ROAD		
240+69.6 RT.	300+09.8 RT.	10970.3
500+58.0 LT.	501+57.0 LT.	572.8
500+06.4 RT.	501+25.0 RT.	352.3
502+05 LT.	502+15 LT.	40.0
503+46 LT.	503+56 LT.	40.0
CITY - HAMILTON ROAD SUBTOTAL		11975.4
CITY - MAIN STREET		
294+16.0 RT.	298+26.0 RT.	2193.2
CITY - MAIN STREET SUBTOTAL		2193.2
TOTAL		14168.6

60604400
COMBINATION CONCRETE CURB AND GUTTER,
TYPE B-6.18

STATION	TO STATION	FOOT
CITY - HAMILTON ROAD		
240+85.0 RT.	249+19.6 RT.	844
249+45.6 RT.	252+50.6 RT.	328
252+16.8 RT.	262+55.4 RT.	1015
240+89.0 LT.	262+47.3 LT.	2182
C.E. - 258+73.6 RT.		32
C.E. - 261+10.0 RT.		133
TOTAL		4534

42400800
DETECTABLE WARNINGS

STATION	TO STATION	SO FT
CITY - HAMILTON ROAD		
249+18.2 RT.		8
249+47.07 RT.		8
252+49.12 RT.		8
252+79.59 RT.		8
CITY - HAMILTON ROAD SUBTOTAL		32
CITY - MAIN STREET		
298+23.69 RT.		16
298+28.22 LT.		16
299+36.82 RT.		8
299+46.00 LT.		8
CITY - MAIN STREET SUBTOTAL		48
TOTAL		80

60605400
COMBINATION CONCRETE CURB AND GUTTER,
TYPE B-6.24 (SPECIAL)

STATION	TO STATION	FOOT
CITY - MAIN STREET		
294+16.0 RT.	297+94.0 RT.	383
297+45.8 LT.	501+57.0 LT.	193
501+57.0 RT.	303+68.0 LT.	528
299+57.4 RT.	300+22.5 RT.	67
TOTAL		1171

60623100
CONCRETE MEDIAN, TYPE SM-6.12 (SPECIAL)

STATION	TO STATION	SO FT
CITY - MAIN STREET		
298+01.0 LT.	298+16.0 LT.	103.7
TOTAL		103.7

44300200
STRIP REFLECTIVE CRACK CONTROL TREATMENT

STATION	TO STATION	FOOT
CITY - HAMILTON ROAD		
500+38 LT. & RT.	501+57 LT. & RT.	595
CITY - MAIN STREET		
294+93 RT.	299+97 RT.	504
297+73 LT.	303+26 LT.	553
TOTAL		1652

60228000
MANHOLES, SANITARY

LOCATION	EACH	
CITY - HAMILTON ROAD		
241+00 LT.	1	
242+95 LT.	1	
245+37 LT.	1	
245+37 RT.	1	
248+15 RT.	1	
251+15 RT.	1	
254+15 RT.	1	
257+73 RT.	1	
TOTAL		8

FOR ADDITIONAL SCHEDULES OF QUANTITIES AND BILL OF MATERIALS SEE THE STAGE CONSTRUCTION AND MAINTENANCE OF TRAFFIC PLANS, REMOVALS/RELOCATIONS PLANS, PLAN AND PROFILE SHEETS, PAVEMENT MARKING PLANS, WATER MAIN PLANS, AND TRAFFIC SIGNAL PLANS.

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

DATE : 6-09
DRAWN BY : J.L.B.
CHECKED BY : R.L.H.

SCALE : NONE