

THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS (78000100)	
LOCATION	TURN ARROWS (SQ FT)
HAMILTON RD.	
500+87 LT.	15.6
501+43 LT.	15.6
MAIN ST.	
296+66 RT.	15.6
297+31 RT.	15.6
297+96 RT.	31.2
299+73 LT.	31.2
300+45.5 LT.	15.6
301+18 LT.	15.6
CITY TOTAL	156.0

EPOXY PAVEMENT MARKING - LETTERS AND SYMBOLS (78005100)		
LOCATION	TURN ARROWS (SQ FT)	DUAL LEFT TURN ARROWS (SQ FT)
HAMILTON RD.		
239+62 C		31.2
242+12 C		31.2
244+62 C		31.2
247+12 C		31.2
249+62 C		31.2
252+12 C		31.2
254+62 C		31.2
257+12 C		31.2
260+28 C	15.6	
260+88.5 C	15.6	
261+49 C	15.6	
262+10 C	15.6	
501+99 LT.	15.6	
502+55 LT.	15.6	
SUBTOTAL	93.6	249.6
CITY TOTAL		343.2

PAVEMENT MARKING REMOVAL (78300100)						
LOCATION	4" LINE (SQ FT)	6" LINE (SQ FT)	8" LINE (SQ FT)	12" LINE (SQ FT)	24" LINE (SQ FT)	TURN ARROWS (SQ FT)
HAMILTON RD.						
238+00 TO 240+90 LT. & RT.	398			63		
501+57 TO 503+49 LT. & RT.	240					78
MAIN ST.						
298+17 TO 299+53 LT. & RT.	27	134	14	14	72	16
SUBTOTAL	665	134	14	77	72	94
CITY TOTAL				1056		

THERMOPLASTIC PAVEMENT MARKING - LINE 4" (78000200)		
LOCATION	SOLID WHITE (FOOT)	SOLID YELLOW (FOOT)
MAIN ST.		
298+01 TO 298+16 LT.		34
296+66 TO 298+14 RT.	150	
299+55 TO 301+18 LT.	163	
SUBTOTAL	313	34
CITY TOTAL		347

EPOXY PAVEMENT MARKING - LINE 6" (78005130)					
LOCATION	SKIP-DASH YELLOW (FOOT)	SOLID YELLOW (FOOT)	DOUBLE YELLOW WIDE (FOOT)	SKIP-DASH WHITE (FOOT)	CROSSWALK WHITE (FOOT)
HAMILTON RD.					
236+24 TO 261+94 LT. & RT.				1250	
238+00 TO 258+85 LT. & RT.		4170			
238+04 TO 258+54 LT. & RT.	1040				
DICKERSON DR.					60
RODGERS RD.					60
258+85 TO 262+28 LT.			684		
262+28.8 TO 262+57.8 LT. & RT.					253
501+57 TO 503+49 LT.				386	
501+79 TO 503+49 LT. & RT.				70	
SUBTOTAL	1040	4170	1070	1320	373
CITY TOTAL			7973		

THERMOPLASTIC PAVEMENT MARKING - LINE 6" (78000400)			
LOCATION	DOUBLE YELLOW WIDE (FOOT)	SKIP-DASH WHITE (FOOT)	CROSSWALK WHITE (FOOT)
MAIN ST.			
298+19.6 TO 299+48.8 LT. & RT.			632
HAMILTON RD.			
500+69 TO 501+57 LT.	176		
500+99 TO 501+49 LT. & RT.		40	
SUBTOTAL	176	40	632
CITY TOTAL			848

EPOXY PAVEMENT MARKING - LINE 8" (78005140)	
LOCATION	SOLID WHITE (FOOT)
HAMILTON RD.	
260+28 TO 262+28 RT.	201
262+36.31 TO 262+53.65 LT.	40
501+57 TO 502+55 LT.	98
CITY TOTAL	339

THERMOPLASTIC PAVEMENT MARKING - LINE 8" (78000500)	
LOCATION	SOLID WHITE (FOOT)
MAIN ST.	
298+24.85 TO 298+55.9 RT.	63
299+13.2 TO 299+40.2 LT.	91
HAMILTON RD.	
500+69 TO 501+57 LT.	88
CITY TOTAL	242

EPOXY PAVEMENT MARKING - LINE 12" (78005150)	
LOCATION	DIAGONAL WHITE (FOOT)
HAMILTON RD.	
262+44.8 TO 262+53.5 LT.	16
CITY TOTAL	16

THERMOPLASTIC PAVEMENT MARKING - LINE 12" (78000600)	
LOCATION	DIAGONAL WHITE (FOOT)
MAIN ST.	
298+30 TO 298+55.9 RT.	40
299+13.2 TO 299+40.2 LT.	43
CITY TOTAL	83

EPOXY PAVEMENT MARKING - LINE 24" (78005180)	
LOCATION	STOP BAR WHITE (FOOT)
HAMILTON RD.	
DICKERSON DR.	12
RODGERS RD.	12
262+28 LT. & RT.	42
262+45 TO 262+51.4 LT.	7
CITY TOTAL	73

THERMOPLASTIC PAVEMENT MARKING - LINE 24" (78000650)	
LOCATION	STOP BAR WHITE (FOOT)
MAIN ST.	
298+14 RT.	49
299+55 LT.	55
HAMILTON RD.	
500+69 LT.	45
CITY TOTAL	149

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**PAVEMENT MARKING  
SCHEDULE OF QUANTITIES**

DATE : 6-09  
DRAWN BY : J.L.B.  
CHECKED BY : R.L.H.

SCALE : NONE