# STEEL PLATE BEAM GUARDRAIL

LOCATION	SIDE	REMOVAL QUANTITY (FOOT)	INSTALL QUANTITY (FOOT)
NORTHWEST RADIUS AT 4TH AND ELM	LT	25	25
TOTAL		25.0	25.0

## FURNISHING AND ERECTING RIGHT OF WAY MARKERS

LOCATION	OFFSET		METHOD A	METHOD B	
	LT	RT	EACH	EACH	
STA 13+18.75		23.89′		1	
STA 13+18.68		36.09′		1	
STA 14+00.46		36. 58′		1	
STA 14+00.46		34. 38'		1	
STA 14+75.41	43. 17'			. 1	
STA 13+68.49	43. 82'			1	
STA 13+68.39	25. 82'		***************************************	1	
TOTAL	ΤΟΤΔΙ			7	

### SIGN PANEL - TYPE 1

			SIGN PANEL - TYPE 1	METAL POST	TYPE B
LOCATION	SIDE	OFFSET	(3' X 3' STOP SIGN)	URBAN	RURAL
			SQ FT	FOOT	FOOT
STA 14+7902	RT	14.30	9.00	14.00	
STA 14+89.32	LT	33.64	9.00	14.00	
					· · · · · · · · · · · · · · · · · · ·
SUBTOTAL	SUBTOTAL		18	28	0
TOTAL			18	28	

DESIGNED -

DRAWN

CHECKED

DATE

REVISED

REVISED

REVISED

REVISED

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

#### CHAIN LINK FENCE

STATION TO STATION	SIDE	REMOVAL QUANTITY (FEET)	6' CHAIN LINK FENCE (FEET)	6' CHAIN LINK ATTACHED TO STRUCTURE (FEET)
NORTHWEST WINGWALL	LT			23
NORTH CULVERT HEADWALL	LT			34.5
NORTHEAST WINGWALL	LT			25. 3
NORTHEAST WINGWALL TO RADIUS AT NW CORNER OF 4TH AND ELM	LT		17.3	
SOUTHWEST WINGWALL	RT			27.5
SOUTH CULVERT HEADWALL	RT			35
SOUTHEAST WINGWALL	RT			16. 7
STA 13+77.57 TO STA 13+92.2	RT		14.7	
STA 13+77.57 TO STA 13+85		10		
TOTAL		10.00	32.00	162.00

## WOOD SIDEWALK

LOCATION	ON SIDE		WOOD SIDEWALK
		FEET	SQ FT
13+96, 33' RT TO 39.5' RT	RT	6	39
TOTALS			39

SCHEDULE OF QUANTITIES	RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEE NO.
DALLAS CITY CULVERT	4TH	05-00014-00-BR	HANCOCK	20	5
DALLAS CITT COLVERT			CONTRACT	NO. 9	3 4 9
		ILLINOIS FED. AI	D PROJECT		