

ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
FAS 898	05-00139-00-RS	SALINE	15	3
PROJECT NO. ARA-RS-898 (107)		CONTRACT NO. 99398		

RESURFACING SCHEDULE						
Location Station to Station	Length Feet	Prime Coat		Leveling Binder (MM)		Hot-Mix Asphalt Surface Course Tons
		Bituminous Materials Gallons	Aggregate Tons	Full Lift Tons	Crown/SE Correction Tons	
		NORTHBOUND (RIGHT) LANE				
-1+40 to 1+32.25	272.25	17.6	0.3	15.7	1.2	26.2
1+32.25 to 1+75.75	43.50	7.0	0.1			7.8
1+75.75 to 41+45.56	3969.81	144.5	2.1	229.0	92.9	381.8
41+45.56 to 43+54.44	208.88	33.5	0.5			37.4
43+54.44 to 53+27	972.56	60.3	0.9	54.2		94.5
53+27 to 65+79	1252.00	171.9	2.6			126.2
65+79 to 124+57	5878.00	208.6	3.2	339.0	244.3	565.5
124+57 to 132+16	759.00	26.1	0.3	43.8	20.2	73.0
132+16 to 142+23	1007.00	34.6	0.6	58.1	39.1	96.9
142+23 to 152+00	977.00	33.5	0.5	56.4	33.9	93.9
152+00 to -252+32.80				Station Equation (Begin reverse stationing)		
-252+32.80 to -248+19	413.80	14.2	0.3	23.9	16.8	39.8
-248+19 to -242+82.33	536.67	22.6	0.3	31.0	4.7	51.7
-242+82.33 to -241+65.67	116.66	18.6	0.3			20.9
-241+65.67 to -210+00	3165.67	112.8	1.7	182.6	119.2	304.4
-210+00 to -174+00	3600.00	127.7	1.9	207.6	92.9	346.3
Subtotals for NorthBound (Right) Lane		1033.5	15.6	1241.3	665.2	2266.3
SOUTHBOUND (LEFT) LANE						
-1+40 to 1+32.25	272.25	17.6	0.3	15.7	1.2	26.2
1+32.25 to 1+75.75	43.50	7.0	0.1			7.8
1+75.75 to 41+45.56	3969.81	144.5	2.1	229.0	50.2	381.8
41+45.56 to 43+54.44	208.88	33.5	0.5			37.4
43+54.44 to 53+27	972.56	60.3	0.9	56.1	8.2	94.5
53+27 to 65+79	1252.00	171.9	2.6			126.2
65+79 to 124+57	5878.00	208.6	3.2	339.0	164.4	565.5
124+57 to 132+16	759.00	26.1	0.3	43.8	10.8	73.0
132+16 to 142+23	1007.00	34.6	0.6	58.1	16.0	96.9
142+23 to 152+00	977.00	33.5	0.5	56.4	21.7	93.9
152+00 to -252+32.80				Station Equation (Begin reverse stationing)		
-252+32.80 to -248+19	413.80	14.2	0.3	23.9	7.0	39.8
-248+19 to -242+82.33	536.67	22.6	0.3	31.0	12.9	51.7
-242+82.33 to -241+65.67	116.66	18.6	0.3			20.9
-241+65.67 to -210+00	3165.67	112.8	1.7	182.6	102.6	304.4
-210+00 to -174+00	3600.00	127.7	1.9	207.6	136.7	346.3
Subtotals for SouthBound (Left) Lane		1033.5	15.6	1243.2	531.7	2266.3
TOTALS		2067.0	31.2	2484.5	1196.9	4532.6

NOTE: Quantities shown do not include materials for entrances, side roads, and mailbox turnouts.

HMA SURFACE REMOVAL 2"	
Bridge Location	Area (S.Y.)
Sta. 1+32 to Sta. 1+76	137
Sta. 41+46 to Sta. 43+54	647
Sta. 241+66 to Sta. 242+82	361
TOTAL	1,145

HMA SURF. REMOVAL - VAR. DEPTH	
Location	Area (S.Y.)
Sta. -0+50 to Sta. 0+50	864
TOTAL	864

HMA SURF. REMOVAL - BUTT JT.	
Location	Area (S.Y.)
Sta. -1+40 to Sta. -1+15	86
Sta. 174+00 to Sta. 173+75	61
TOTAL	147