



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

October 27, 2015

SUBJECT: FAP Route 372/373 (IL 171)
Project ACNHPP-000V(034)
Section 2013-037B-R
Cook County
Contract No. 60W75
Item No. 75, November 6, 2015 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Replaced the Schedule of Prices
2. Revised page iii of the Table of Contents to the Special Provisions
3. Revised page 198 of the Special Provisions
4. Deleted pages 199-223 of the Special Provisions
5. Revised sheets 9, 20, 266, 314, 317, 319, 352, 358, 443, 445, 453-456, 459, 470, 472, 530, 534-537, 552-561, 565, 567, 595, 598, 599 & 670 of the Plans

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

John D. Baranzelli, P.E.
Acting Engineer of Design and Environment

A handwritten signature in black ink, appearing to read 'Ted B. Walschleger' with 'P.E.' written to the right.

By: Ted B. Walschleger, P. E.
Engineer of Project Management

cc: John Fortmann, Region 1, District 1; Tim Kell; Catherine Batey;
D. Carl Puzey; Estimates
MS/kf

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60W75

State Job # - C-91-368-13

County Name - COOK - -

Code - 31 - -

District - 1 - -

Section Number - 2013-037B-R

Project Number
 ACNHPP-00V0/34 /
 *REVISED: OCTOBER 22, 2015

Route
 FAP 372
 FAP 373

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
K1005863	TREE ROOT PRUNING	EACH	15.000				
X0322433	LT TOWER SERVICE PAD	EACH	16.000				
X0322434	LT TOWER SERV PAD SPL	EACH	23.000				
X0322936	REMOV EX FLAR END SEC	EACH	4.000				
X0323586	PIPE DRAIN REMOVAL	FOOT	231.000				
X0323710	REMOV COND ATT TO STR	FOOT	12,022.000				
X0326232	FENDER SYSTEM	L SUM	1.000				
X0326796	CLEAN TROUGH	EACH	1.000				
X0326797	REATT GRDRL TO STRUC	EACH	2.000				
X0326865	POST MT FL BEACON INS	EACH	4.000				
X2501800	SEEDING CL 4 MOD	ACRE	3.000				
X5537800	SS CLEANED 12	FOOT	180.000				
X5538000	SS CLEANED 18	FOOT	219.000				
X5860110	GRANULAR BACKFILL STR	CU YD	669.000				
X6431120	REM IMP ATTEN SM	EACH	1.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60W75

State Job # - C-91-368-13

County Name - COOK - -

Code - 31 - -

District - 1 - -

Section Number - 2013-037B-R

Project Number
 ACNHPP-00V0/34 /
 *REVISED: OCTOBER 22, 2015

Route
 FAP 372
 FAP 373

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
X6700410	ENGR FLD OFF A SPL	CAL MO	13.000				
X7010216	TRAF CONT & PROT SPL	L SUM	1.000				
X7011015	TR C-PROT EXPRESSWAYS	L SUM	1.000				
X7030030	WET REF TEM TAPE T3 4	FOOT	31,302.000				
X7030040	WET REF TEM TAPE T3 6	FOOT	457.000				
X7030045	WET REF TEM TAPE T3 8	FOOT	1,138.000				
X7030050	WET REF TEM TPE T3 12	FOOT	344.000				
X7040125	PIN TEMP CONC BARRIER	EACH	201.000				
X7310110	BASE TEL SIN SUPP SP	EACH	3.000				
X8251388	LT CT BM 480V200D RS	EACH	2.000				
X8260110	NAVIGATION LT SYSTEM	L SUM	1.000				
X8420502	REM LT TOWER NO SALV	EACH	41.000				
X8420510	REM TOWER FDN	EACH	45.000				
Z0000300	ADJ ROCKER & SOLE PLT	EACH	8.000				
Z0001899	JACK & REM EX BEARING	EACH	7.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF PRICES
CONTRACT
NUMBER - 60W75

State Job # - C-91-368-13

County Name - COOK - -

Code - 31 - -

District - 1 - -

Section Number - 2013-037B-R

Project Number

ACNHPP-00V0/34 /

*REVISED: OCTOBER 22, 2015

Route

FAP 372

FAP 373

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
Z0001903	STRUCT STEEL REMOV	POUND	68,200.000				
Z0001905	STRUCT STEEL REPAIR	POUND	71,840.000				
Z0004552	APPROACH SLAB REM	SQ YD	887.000				
*DEL Z0007401	C&D LEAD PT CL RS N1	L SUM	1.000				
*DEL Z0007402	C&D LEAD PT CL RS N2	L SUM	1.000				
*DEL Z0007403	C&D LEAD PT CL RS N3	L SUM	1.000				
*DEL Z0007404	C&D LEAD PT CL RS N4	L SUM	1.000				
*DEL Z0007405	C&D LEAD PT CL RS N5	L SUM	1.000				
Z0010400	CLEANING BRIDGE SEATS	SQ FT	5,238.000				
Z0012754	STR REP CON DP = < 5	SQ FT	2,912.000				
Z0012755	STR REP CON DP OVER 5	SQ FT	591.000				
Z0013798	CONSTRUCTION LAYOUT	L SUM	1.000				
Z0016001	DECK SLAB REP (FD-T1)	SQ YD	29.300				
Z0016002	DECK SLAB REP (FD-T2)	SQ YD	54.400				
Z0016200	DECK SLAB REP (PART)	SQ YD	32.400				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60W75

State Job # - C-91-368-13

County Name - COOK - -

Code - 31 - -

District - 1 - -

Section Number - 2013-037B-R

Project Number
 ACNHPP-00V0/34 /
 *REVISED: OCTOBER 22, 2015

Route
 FAP 372
 FAP 373

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
Z0018002	DRAINAGE SCUPPR DS-11	EACH	22.000				
Z0018010	DRAINAGE SCUPPR DS-33	EACH	3.000				
Z0018500	DRAINAGE STR CLEANED	EACH	6.000				
Z0018700	DRAINAGE STR REMOVED	EACH	5.000				
Z0018800	DRAINAGE SYSTEM	L SUM	1.000				
Z0030850	TEMP INFO SIGNING	SQ FT	85.000				
Z0033020	LUM SFTY CABLE ASMBLY	EACH	39.000				
Z0033028	MAINTAIN LIGHTING SYS	CAL MO	13.000				
Z0034806	MODULAR EXP JT-SW 6	FOOT	66.500				
Z0046304	P UNDR FOR STRUCT 4	FOOT	420.000				
Z0048665	RR PROT LIABILITY INS	L SUM	1.000				
Z0064800	SELECTIVE CLEARING	UNIT	41.000				
Z0073002	TEMP SOIL RETEN SYSTM	SQ FT	2,542.000				
Z0073200	TEMP SHORING & CRIB	EACH	16.000				
Z0073400	TEMP SUPPORT SYSTEM	EACH	4.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60W75

State Job # - C-91-368-13

County Name - COOK - -

Code - 31 - -

District - 1 - -

Section Number - 2013-037B-R

Project Number

ACNHPP-00V0/34 /

*REVISED: OCTOBER 22, 2015

Route

FAP 372

FAP 373

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
Z0073510	TEMP TR SIGNAL TIMING	EACH	23.000				
Z0076600	TRAINEES	HOUR	1,000.000		0.800		800.000
Z0076604	TRAINEES TPG	HOUR	1,000.000		15.000		15,000.000
20100110	TREE REMOV 6-15	UNIT	15.000				
20100210	TREE REMOV OVER 15	UNIT	5.000				
20101000	TEMPORARY FENCE	FOOT	915.000				
20101100	TREE TRUNK PROTECTION	EACH	15.000				
20101300	TREE PRUN 1-10	EACH	25.000				
20101350	TREE PRUN OVER 10	EACH	25.000				
20200100	EARTH EXCAVATION	CU YD	2,455.000				
20400800	FURNISHED EXCAVATION	CU YD	393.000				
21101505	TOPSOIL EXC & PLAC	CU YD	969.000				
21101625	TOPSOIL F & P 6	SQ YD	8,041.000				
25000314	SEEDING CL 4B	ACRE	0.500				
25000400	NITROGEN FERT NUTR	POUND	260.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60W75

State Job # - C-91-368-13

County Name - COOK - -

Code - 31 - -

District - 1 - -

Section Number - 2013-037B-R

Project Number

ACNHPP-00V0/34 /

*REVISED: OCTOBER 22, 2015

Route

FAP 372

FAP 373

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
25000600	POTASSIUM FERT NUTR	POUND	260.000				
25000750	MOWING	ACRE	9.000				
25100630	EROSION CONTR BLANKET	SQ YD	13,989.000				
25200200	SUPPLE WATERING	UNIT	25.000				
28000250	TEMP EROS CONTR SEED	POUND	348.000				
28000305	TEMP DITCH CHECKS	FOOT	10,200.000				
28000315	AGG DITCH CHECKS	TON	44.000				
28000400	PERIMETER EROS BAR	FOOT	2,296.000				
28000510	INLET FILTERS	EACH	10.000				
28001100	TEMP EROS CONTR BLANK	SQ YD	6,663.000				
30300001	AGG SUBGRADE IMPROVE	CU YD	500.000				
30300112	AGG SUBGRADE IMPR 12	SQ YD	5,556.000				
31200500	STAB SUBBASE HMA 4	SQ YD	819.000				
35400500	PCC BASE CSE W 10	SQ YD	112.000				
35501332	HMA BASE CSE 12	SQ YD	532.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF PRICES
CONTRACT
NUMBER - 60W75

State Job # - C-91-368-13

County Name - COOK - -

Code - 31 - -

District - 1 - -

Section Number - 2013-037B-R

Project Number
ACNHPP-00V0/34 /
*REVISED: OCTOBER 22, 2015

Route
FAP 372
FAP 373

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
40600275	BIT MATLS PR CT	POUND	15,135.000				
40600982	HMA SURF REM BUTT JT	SQ YD	80.000				
40601005	HMA REPL OVER PATCH	TON	286.000				
40603085	HMA BC IL-19.0 N70	TON	427.000				
40603240	P HMA BC IL19.0 N90	TON	999.000				
40603340	HMA SC "D" N70	TON	332.000				
40603595	P HMA SC "F" N90	TON	753.000				
42000501	PCC PVT 10 JOINTED	SQ YD	676.000				
42001420	BR APPR PVT CON (PCC)	SQ YD	318.000				
44000100	PAVEMENT REM	SQ YD	7,789.000				
44000165	HMA SURF REM 4	SQ YD	9,145.000				
44000400	GUTTER REM	FOOT	50.000				
44002216	HMA RM OV PATCH 4	SQ YD	1,278.000				
44004250	PAVED SHLD REMOVAL	SQ YD	1,907.000				
44201761	CL D PATCH T1 10	SQ YD	426.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60W75

State Job # - C-91-368-13

County Name - COOK - -

Code - 31 - -

District - 1 - -

Section Number - 2013-037B-R

Project Number

ACNHPP-00V0/34 /

*REVISED: OCTOBER 22, 2015

Route

FAP 372

FAP 373

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
44201765	CL D PATCH T2 10	SQ YD	426.000				
44201769	CL D PATCH T3 10	SQ YD	213.000				
44201771	CL D PATCH T4 10	SQ YD	213.000				
48101620	AGGREGATE SHLDS B 10	SQ YD	3,472.000				
48203029	HMA SHOULDERS 8	SQ YD	3,712.000				
48203048	HMA SHOULDERS 12 3/4	SQ YD	40.000				
50102400	CONC REM	CU YD	167.700				
50104650	SLOPE WALL REMOV	SQ YD	1,304.000				
50104701	REM EX CONC DECK N1	EACH	1.000				
50104702	REM EX CONC DECK N2	EACH	1.000				
50104703	REM EX CONC DECK N3	EACH	1.000				
50104704	REM EX CONC DECK N4	EACH	1.000				
50104705	REM EX CONC DECK N5	EACH	1.000				
50105220	PIPE CULVERT REMOV	FOOT	1,608.000				
50157300	PROTECTIVE SHIELD	SQ YD	15,100.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF PRICES
CONTRACT
NUMBER - 60W75

State Job # - C-91-368-13

County Name - COOK - -

Code - 31 - -

District - 1 - -

Section Number - 2013-037B-R

Project Number
ACNHPP-00V0/34 /
*REVISED: OCTOBER 22, 2015

Route
FAP 372
FAP 373

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
50200100	STRUCTURE EXCAVATION	CU YD	1,398.000				
50300100	FLOOR DRAINS	EACH	98.000				
50300225	CONC STRUCT	CU YD	628.500				
*REV 50300255	CONC SUP-STR	CU YD	5,543.400				
50300260	BR DECK GROOVING	SQ YD	15,938.000				
50300280	CONCRETE ENCASEMENT	CU YD	5.600				
*REV 50300300	PROTECTIVE COAT	SQ YD	27,690.000				
50500105	F & E STRUCT STEEL	L SUM	1.000				
50500405	F & E STRUCT STEEL	POUND	6,840.000				
50500505	STUD SHEAR CONNECTORS	EACH	42,012.000				
*REV 50800205	REINF BARS, EPOXY CTD	POUND	1,428,550.000				
50800515	BAR SPLICERS	EACH	195.000				
50800530	MECHANICAL SPLICERS	EACH	36.000				
51100100	SLOPE WALL 4	SQ YD	1,565.000				
51100300	SLOPE WALL 6	SQ YD	48.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF PRICES
CONTRACT
NUMBER - 60W75

State Job # - C-91-368-13

County Name - COOK - -

Code - 31 - -

District - 1 - -

Section Number - 2013-037B-R

Project Number
ACNHPP-00V0/34 /
*REVISED: OCTOBER 22, 2015

Route
FAP 372
FAP 373

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
51201600	FUR STL PILE HP12X53	FOOT	1,127.000				
51201800	FUR STL PILE HP14X73	FOOT	281.000				
51202305	DRIVING PILES	FOOT	1,408.000				
51203600	TEST PILE ST HP12X53	EACH	9.000				
51203800	TEST PILE ST HP14X73	EACH	2.000				
51204650	PILE SHOES	EACH	46.000				
51500100	NAME PLATES	EACH	5.000				
51602000	PERMANENT CASING	FOOT	24.000				
51603000	DRILLED SHAFT IN SOIL	CU YD	45.200				
51604000	DRILLED SHAFT IN ROCK	CU YD	2.100				
52000020	PREF JOINT SEAL 1 3/4	FOOT	37.500				
52000030	PREF JOINT SEAL 2 1/2	FOOT	207.500				
52000050	PREF JOINT SEAL 4	FOOT	38.500				
52000110	PREF JT STRIP SEAL	FOOT	776.000				
52000212	FINGER PLT EXP JT 4	FOOT	73.500				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60W75

State Job # - C-91-368-13

County Name - COOK - -

Code - 31 - -

District - 1 - -

Section Number - 2013-037B-R

Project Number
 ACNHPP-00V0/34 /
 *REVISED: OCTOBER 22, 2015

Route
 FAP 372
 FAP 373

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
52000600	FAB REINF ELAS TROUGH	FOOT	110.000				
52100010	ELAST BEARING ASSY T1	EACH	17.000				
52100020	ELAST BEARING ASSY T2	EACH	13.000				
52100510	ANCHOR BOLTS 3/4	EACH	64.000				
52100520	ANCHOR BOLTS 1	EACH	12.000				
54215547	MET END SEC 12	EACH	8.000				
58700300	CONCRETE SEALER	SQ FT	3,520.000				
59000200	EPOXY CRACK INJECTION	FOOT	903.000				
59100100	GEOCOMPOSITE WALL DR	SQ YD	246.000				
60100060	CONC HDWL FOR P DRAIN	EACH	1.000				
60105000	PIPE DRAINS CS/AA 12	FOOT	244.000				
60107700	PIPE UNDERDRAINS 6	FOOT	328.000				
60108200	PIPE UNDERDRAIN 6 SP	FOOT	20.000				
60500040	REMOV MANHOLES	EACH	2.000				
60500060	REMOV INLETS	EACH	5.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60W75

State Job # - C-91-368-13

County Name - COOK - -

Code - 31 - -

District - 1 - -

Section Number - 2013-037B-R

Project Number
 ACNHPP-00V0/34 /
 *REVISED: OCTOBER 22, 2015

Route
 FAP 372
 FAP 373

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
60602500	CONC GUTTER TA	FOOT	50.000				
60900515	CONC THRUST BLOCKS	EACH	8.000				
61000225	TY F INLET BOX 610001	EACH	3.000				
61000335	TY G INLET BOX 610001	EACH	5.000				
63000001	SPBGR TY A 6FT POSTS	FOOT	5,070.500				
63100045	TRAF BAR TERM T2	EACH	8.000				
63100070	TRAF BAR TERM T5	EACH	1.000				
63100085	TRAF BAR TERM T6	EACH	13.000				
63100089	TRAF BAR TERM T6B	EACH	2.000				
63100167	TR BAR TRM T1 SPL TAN	EACH	2.000				
63100169	TR BAR TRM T1 SPL FLR	EACH	6.000				
63200310	GUARDRAIL REMOV	FOOT	5,974.000				
63301210	REM RE-E SPBGR TY A	FOOT	250.000				
63302000	REM RE-E T B TERM T2	EACH	1.000				
63302720	REM RE-E T B TERM T6B	EACH	1.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF PRICES
CONTRACT
NUMBER - 60W75

State Job # - C-91-368-13

County Name - COOK - -

Code - 31 - -

District - 1 - -

Section Number - 2013-037B-R

Project Number
ACNHPP-00V0/34 /
*REVISED: OCTOBER 22, 2015

Route
FAP 372
FAP 373

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
63500105	DELINEATORS	EACH	28.000				
63800920	MOD GLAR SCR SYS TEMP	FOOT	8,019.000				
64300450	IMP ATTN NRD TL3	EACH	1.000				
66201120	CONC SHLD CURB	FOOT	67.000				
66900200	NON SPL WASTE DISPOSL	CU YD	930.000				
66900450	SPL WASTE PLNS/REPORT	L SUM	1.000				
66900530	SOIL DISPOSAL ANALY	EACH	6.000				
67100100	MOBILIZATION	L SUM	1.000				
70103815	TR CONT SURVEILLANCE	CAL DA	210.000				
70106800	CHANGEABLE MESSAGE SN	CAL MO	32.000				
70300100	SHORT TERM PAVT MKING	FOOT	3,312.000				
70301000	WORK ZONE PAVT MK REM	SQ FT	11,765.000				
70400100	TEMP CONC BARRIER	FOOT	9,112.500				
70600250	IMP ATTN TEMP NRD TL3	EACH	1.000				
70600251	IMP ATTN TEMP NRN TL3	EACH	2.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60W75

State Job # - C-91-368-13

County Name - COOK - -

Code - 31 - -

District - 1 - -

Section Number - 2013-037B-R

Project Number

ACNHPP-00V0/34 /

*REVISED: OCTOBER 22, 2015

Route

FAP 372

FAP 373

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
72000100	SIGN PANEL T1	SQ FT	373.000				
72000200	SIGN PANEL T2	SQ FT	403.000				
72000300	SIGN PANEL T3	SQ FT	1,097.000				
72400100	REMOV SIN PAN ASSY TA	EACH	10.000				
72400200	REMOV SIN PAN ASSY TB	EACH	16.000				
72400310	REMOV SIGN PANEL T1	SQ FT	164.000				
72400320	REMOV SIGN PANEL T2	SQ FT	231.000				
72400330	REMOV SIGN PANEL T3	SQ FT	1,007.000				
72700100	STR STL SIN SUP BA	POUND	595.000				
72800100	TELES STL SIN SUPPORT	FOOT	467.000				
73000100	WOOD SIN SUPPORT	FOOT	318.000				
73100100	BASE TEL STL SIN SUPP	EACH	1.000				
73300100	OVHD SIN STR-SPAN T1A	FOOT	156.000				
73302200	OSS CANT 3CA 2-6X7-0	FOOT	90.000				
73400100	CONC FOUNDATION	CU YD	2.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60W75

State Job # - C-91-368-13

County Name - COOK - -

Code - 31 - -

District - 1 - -

Section Number - 2013-037B-R

Project Number

ACNHPP-00V0/34 /

*REVISED: OCTOBER 22, 2015

Route

FAP 372

FAP 373

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
73400200	DRILL SHAFT CONC FDN	CU YD	51.000				
73600100	REMOV OH SIN STR-SPAN	EACH	2.000				
73600200	REMOV OH SIN STR-CANT	EACH	2.000				
73700100	REM GR MT SIN SUPPORT	EACH	4.000				
73700200	REM CONC FDN-GR MT	EACH	4.000				
73700300	REM CONC FDN-OVHD	EACH	6.000				
78000100	THPL PVT MK LTR & SYM	SQ FT	498.000				
78000200	THPL PVT MK LINE 4	FOOT	27,744.000				
78000400	THPL PVT MK LINE 6	FOOT	1,525.000				
78000500	THPL PVT MK LINE 8	FOOT	6,727.000				
78000600	THPL PVT MK LINE 12	FOOT	3,586.000				
78000650	THPL PVT MK LINE 24	FOOT	220.000				
78008200	POLYUREA PM T1 LTR-SY	SQ FT	42.000				
78008210	POLYUREA PM T1 LN 4	FOOT	19,048.000				
78008230	POLYUREA PM T1 LN 6	FOOT	87.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60W75

State Job # - C-91-368-13

County Name - COOK - -

Code - 31 - -

District - 1 - -

Section Number - 2013-037B-R

Project Number

ACNHPP-00V0/34 /

*REVISED: OCTOBER 22, 2015

Route

FAP 372

FAP 373

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
78008240	POLYUREA PM T1 LN 8	FOOT	5,502.000				
78008250	POLYUREA PM T1 LN 12	FOOT	903.000				
78100100	RAISED REFL PAVT MKR	EACH	489.000				
78100105	RAISED REF PVT MKR BR	EACH	303.000				
78100200	TEMP RAIS REF PVT MKR	EACH	12.000				
78200200	BIDIR PRIS BAR REFL	EACH	323.000				
78200410	GUARDRAIL MKR TYPE A	EACH	111.000				
78200530	BAR WALL MKR TYPE C	EACH	693.000				
78201000	TERMINAL MARKER - DA	EACH	8.000				
78300100	PAVT MARKING REMOVAL	SQ FT	6,445.000				
78300200	RAISED REF PVT MK REM	EACH	12.000				
80300100	LOCATE UNDERGR CABLE	FOOT	25,000.000				
80400100	ELECT SERV INSTALL	EACH	2.000				
80400200	ELECT UTIL SERV CONN	L SUM	1.000				
81028190	UNDRGRD C GALVS 1 1/2	FOOT	80.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60W75

State Job # - C-91-368-13

County Name - COOK - -

Code - 31 - -

District - 1 - -

Section Number - 2013-037B-R

Project Number

ACNHPP-00V0/34 /

*REVISED: OCTOBER 22, 2015

Route

FAP 372

FAP 373

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
81028220	UNDRGRD C GALVS 3	FOOT	1,807.000				
81100320	CON AT ST 1 PVC GS	FOOT	145.000				
81100605	CON AT ST 2 PVC GALVS	FOOT	1,296.000				
81100705	CON AT ST 2.5 PVC GS	FOOT	170.000				
81200230	CON EMB STR 2 PVC	FOOT	3,331.000				
81300220	JUN BX SS AS 6X6X4	EACH	2.000				
81300550	JUN BX SS AS 12X12X6	EACH	17.000				
81300800	JUN BX SS AS 18X12X6	EACH	17.000				
81603081	UD 3#2#4GXLP USE 1.5 P	FOOT	30,082.000				
81603090	UD 3#4#6GXLP USE 1 1/4	FOOT	1,493.000				
81702110	EC C XLP USE 1C 10	FOOT	507.000				
81702130	EC C XLP USE 1C 6	FOOT	200.000				
81702140	EC C XLP USE 1C 4	FOOT	7,620.000				
81702150	EC C XLP USE 1C 2	FOOT	21,060.000				
81702220	EC C XLP USE 1C 350	FOOT	903.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60W75

State Job # - C-91-368-13

County Name - COOK - -

Code - 31 - -

District - 1 - -

Section Number - 2013-037B-R

Project Number
 ACNHPP-00V0/34 /
 *REVISED: OCTOBER 22, 2015

Route
 FAP 372
 FAP 373

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
82102400	LUM SV HOR MT 400W	EACH	39.000				
82105600	LUM SV HM HOR MT 400W	EACH	206.000				
82107200	UNDERPAS LUM 100W HPS	EACH	2.000				
83050715	LT P A 47.5MH 6DA	EACH	18.000				
83050825	LT P A 47.5MH 15DA	EACH	21.000				
83504700	LT TOWER 120MH LM 12	EACH	39.000				
83600365	LP F M 15BC 10" X 8'	EACH	21.000				
83700350	LT TOWER FDN 54D	FOOT	662.000				
83800205	BKWY DEV TR B 15BC	EACH	21.000				
84100110	REM TEMP LIGHT UNIT	EACH	6.000				
84200600	REM LT U NO SALV	EACH	49.000				
84200804	REM POLE FDN	EACH	22.000				
84301200	REM NAV OBS WL SYSTEM	L SUM	1.000				
84500110	REMOV LIGHTING CONTR	EACH	2.000				
84500120	REMOV ELECT SERV INST	EACH	2.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60W75

State Job # - C-91-368-13

County Name - COOK - -

Code - 31 - -

District - 1 - -

Section Number - 2013-037B-R

Project Number _____

ACNHPP-00V0/34 /

*REVISED: OCTOBER 22, 2015

Route _____

FAP 372

FAP 373

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
84500130	REMOV LTG CONTR FDN	EACH	2.000				
87301855	ELCBL C SERV 8 2C	FOOT	1,110.000				
87301900	ELCBL C EGRDC 6 1C	FOOT	110.000				
89000100	TEMP TR SIG INSTALL	EACH	2.000				
89502300	REM ELCBL FR CON	FOOT	12,556.000				
89502400	REM EX FB INSTAL COMP	EACH	3.000				

CONTRACT NUMBER

60W75

THIS IS THE TOTAL BID

\$ _____

NOTES:

1. Each PAY ITEM should have a UNIT PRICE and a TOTAL PRICE.
2. The UNIT PRICE shall govern if no TOTAL PRICE is shown or if there is a discrepancy between the product of the UNIT PRICE multiplied by the QUANTITY.
3. If a UNIT PRICE is omitted, the TOTAL PRICE will be divided by the QUANTITY in order to establish a UNIT PRICE.
4. A bid may be declared UNACCEPTABLE if neither a unit price nor a total price is shown.

MOWING 149

HOT MIX ASPHALT QUALITY CONTROL FOR PERFORMANCE (BMPR) 150

TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS) 154

KEEPING THE EXPRESSWAY OPEN TO TRAFFIC 158

KEEPING ARTERIAL ROADWAYS OPEN TO TRAFFIC (LANE CLOSURES ONLY)..... 160

FAILURE TO OPEN TRAFFIC LANES TO TRAFFIC..... 161

CONSTRUCTION RESTRICTION AT FEDEX PROPERTY 162

TEMPORARY TRAFFIC SIGNAL TIMINGS..... 162

TRAFFIC SIGNAL GENERAL REQUIREMENTS..... 164

GROUNDING OF TRAFFIC SIGNAL SYSTEMS 175

GROUNDING CABLE..... 176

ELECTRIC CABLE 177

LIGHT EMITTING DIODE (LED) SIGNAL HEAD AND OPTICALLY PROGRAMMED LED
 SIGNAL HEAD..... 177

CLEANING EXISTING DRAINAGE STRUCTURES 179

GUARDRAIL REMOVAL 180

BASE FOR TELESCOPING SIGN SUPPORT (SPECIAL)..... 180

BRIDGE APPROACH PAVEMENT CONNECTOR (PCC) 180

REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES..... 181

DRAINAGE SYSTEM 185

JACK AND REMOVE EXISTING BEARINGS 187

MODULAR EXPANSION JOINT..... 188

CLEANING AND PAINTING CONTACT SURFACE AREAS OF EXISTING STEEL
 STRUCTURES 192

DECK SLAB REPAIR 224

TEMPORARY SOIL RETENTION SYSTEM 229

PIPE UNDERDRAINS FOR STRUCTURES 231

STRUCTURAL REPAIR OF CONCRETE 232

SLIPFORM PARAPET..... 242

GRANULAR BACKFILL FOR STRUCTURES..... 247

BRIDGE DECK CONSTRUCTION 248

FABRIC REINFORCED ELASTOMERIC 251

COARSE AGGREGATE QUALITY (BDE)..... 252

The Contractor is responsible for the payment of any fines and undertaking any clean up activities mandated by State or federal environmental agencies for improper waste handling, storage, transportation, or disposal.

Contractor personnel shall be trained in the proper handling of hazardous waste, and the necessary notification and clean up requirements in the event of a spill. The Contractor shall maintain a copy of the personnel training records at each bridge site.

It is understood and agreed that the cost of all work outlined above, unless otherwise specified, has been included in the bid, and no extra compensation will be allowed.

Basis of Payment: This work will be considered included in the cost of "Furnishing and Erecting Structural Steel", "Erecting Structural Steel", or "Structural Steel Repair", as applicable, according to the Standard Specifications, unless otherwise specified on the plans.

Pages 199-223 have been deleted. The next page is 224.

Revised 10/27/15