

SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
08-F3000-20-BT	COOK	29	3
STA. TO STA.			
IDOT PROJECT NO.			
CENTENNIAL TRAIL			

CONTRACT NO. 63052

CODE NO	PAY ITEM	UNIT	TOTAL QUANTITY Y047
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	109
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	418
M2010500	TREE REMOVAL, HECTARES	HA	0.4
20101200	TREE ROOT PRUNING	EACH	10
M2020010	EARTH EXCAVATION	CU M	100
M2021200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU M	1,763
M2040800	FURNISHED EXCAVATION	CU M	179
M2070420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU M	355
M2101000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ M	5315
* M2113150	TOPSOIL FURNISH AND PLACE, 150 MM	SQ M	4,631
* M2500210	SEEDING, CLASS 2A	HA	0.2
* M2500312	SEEDING, CLASS 4A	HA	0.3
* M2500400	NITROGEN FERTILIZER NUTRIENT	KG	46
* M2500500	PHOSPHORUS FERTILIZER NUTRIENT	KG	46
* M2500600	POTASSIUM FERTILIZER NUTRIENT	KG	46
* M2510630	EROSION CONTROL BLANKET	SQ M	4,631
* M2520200	SUPPLEMENTAL WATERING	UNIT	10
28000300	TEMPORARY DITCH CHECKS	EACH	2
M2800400	PERIMETER EROSION BARRIER	METER	1476
M3511150	AGGREGATE BASE COURSE, TYPE B 150 MM	SQ M	4873
M4060100	BITUMINOUS MATERIALS (PRIME COAT)	LITER	6645
M4063310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	M TON	530
M4205200	PROTECTIVE COAT	SQ M	12
M4240150	PORTLAND CEMENT CONCRETE SIDEWALK 150MM	SQ M	12.0
M4248000	DETECTABLE WARNINGS	SQ M	3.6
M4402000	PAVEMENT REMOVAL	SQ M	156
M4402045	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	METER	3
M4820550	HOT-MIX ASPHALT SHOULDERS, 150MM	SQ M	745
60253000	CATCH BASINS TO BE RECONSTRUCTED WITH NEW TYPE 1 FRAME, OPEN LID	EACH	1
M6320030	GUARDRAIL REMOVAL	METER	7.6
* M6330610	REMOVE AND RE-ERECT STEEL PLATE BEAM GUARDRAIL	METER	320.0
M6640100	CHAIN LINK FENCE, 1.2 METER	METER	300
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	6
67100100	MOBILIZATION	L SUM	1
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1
M7200100	SIGN PANEL - TYPE 1	SQ M	1.9
M7290100	METAL POST - TYPE A	METER	12.0
* M7800115	THERMOPLASTIC PAVEMENT MARKING - LINE 150MM	METER	25
* M7800125	THERMOPLASTIC PAVEMENT MARKING - LINE 300MM	METER	42
* M7800205	PAINT PAVEMENT MARKING - LINE 100MM	METER	1477
84400405	RELOCATE EXISTING WOOD POLES	EACH	1
* A2000116	TREE, ACER X FREEMANII AUTUMN BLAZE (AUTUMN BLAZE FREEMAN MAPLE), 2" CALIPER, BALLED AND BURLAPPED	EACH	10
* A2006716	TREE, QUERCUS MACROCARPA (BUR OAK), 2" CALIPER, BALLED AND BURLAPPED	EACH	10
K1004595	PRUNING FOR SAFETY AND EQUIPMENT CLEARANCE	LSUM	1
XX004652	PIPE GATE	EACH	1
X0321322	DROP GATE	EACH	2
MX032529	SEGMENTAL CONCRETE BLOCK WALL	SQ M	102
XX006670	TRAIL HEAD SIGN, COMPLETE	EACH	1

* INDICATES SPECIALTY ITEMS

CODE NO	PAY ITEM	UNIT	TOTAL QUANTITY Y047
MX030567	RUSTIC RAIL FENCE	METER	63
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1
MZ022800	FENCE REMOVAL	METER	300

EARTHWORK SCHEDULE

LOCATION	SUITABLE EXCAVATION (EARTH EXCAVATION)	EARTH EX. ADJUSTED FOR SHRINKAGE (25%)	SUITABLE EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) (FURNISHED EXCAVATION)	UNSUITABLE EXCAVATION (REMOVAL & DISPOSAL OF UNSUITABLE MATERIAL)	UNSUITABLE EMBANKMENT	TOPSOIL FURNISH & PLACE 150MM	UNSUITABLE BALANCE WASTE (+) OR SHORTAGE (-)
	CU M	CU M	CU M	CU M	CU M	CU M	CU M	CU M
CENTENNIAL TRAIL	0	0	179	-179	1763	0	977	+786

REVISIONS		
NO.	NAME	DATE

URS 100 S. WACKER DR., SUITE 500... TEL. (312)-939-1000
CHICAGO, IL 60606 FAX (312)-939-4198

FOREST PRESERVE DISTRICT OF COOK COUNTY, ILLINOIS

CENTENNIAL TRAIL

SUMMARY OF QUANTITIES

DATE: 5/1/08

DRAWN BY: VAP

DESIGNED BY: SW

CHECKED BY: DDL