

SUMMARY OF QUANTITIES

PAY CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION CODE Y031-1F												
				LEMONT ROAD INTERCONNECT	LEMONT RD & 97TH ST/WESTGATE RD	LEMONT RD & TIMBER TR/CHEESE RD	LEMONT RD & 87TH ST	LEMONT RD & 83RD ST	NAPERVILLE ROAD INTERCONNECT	NAPERVILLE RD & DANADA DR	NAPERVILLE RD & LONGFELLOW DR	NAPERVILLE RD & FARNHAM LN	NAPERVILLE RD & ELM ST	NAPERVILLE RD & ROOSEVELT RD		
67100100	MOBILIZATION	L SUM	1													
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1													
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1													
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1													
81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	9645	6429						3216						
81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	4556	1953						2603						
81400100	HANDHOLE	EACH	27	14						13						
81400200	HEAVY-DUTY HANDHOLE	EACH	7	7												
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	9645	6429						3216						
85000200	MAINTAINANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	8		1	1	1	1		1	1	1	1			
85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	6		1		1	1		1		1	1			
85700500	FULL-ACTUATED CONTROLLER IN EXISTING CABINET	EACH	2			1					1					
86400100	TRANSCEIVER - FIBER OPTIC	EACH	6			1	1	1			1	1	1			
87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	750		750											
X0322925	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C	FOOT	18197	10329						7868						
X8710020	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM12F	FOOT	18197	10329						7868						
87900200	DRILL EXISTING HANDHOLE	EACH	14		1	2	2	1			1	2	2	2	1	
88500100	INDUCTIVE LOOP DETECTOR	EACH	2		2											
88600100	DETECTOR LOOP, TYPE 1	FOOT	180		180											
89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	4		1						1		1	1		
89501400	RELOCATE EXISTING EMERGENCY VEHICLE PRIORITY SYSTEM, DETECTOR UNIT	EACH	1		1											
89501410	RELOCATE EXISTING EMERGENCY VEHICLE PRIORITY SYSTEM, PHASING UNIT	EACH	4		1						1		1	1		
X8050015	SERVICE INSTALLATION - POLE MOUNTED	EACH	1		1											
X0325705	RE-OPTIMIZE TRAFFIC SIGNAL SYSTEM LEVEL 2	L SUM	1	0.5						0.5						

NOTE: FEDERAL CMAQ FUNDING 80%
DUPAGE COUNTY DIVISION OF TRANSPORTATION FUNDING 20%

REVISIONS	
NAME	DATE

DUPAGE COUNTY DIVISION OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: NONE
DATE: 8/21/08

DRAWN BY: TH
DESIGNED BY: TH
CHECKED BY: DAZ