

| ROUTE NO. SECTION     |                         | COLINITY |                   | TOTAL | SHEET | SHEE  |
|-----------------------|-------------------------|----------|-------------------|-------|-------|-------|
| F.A.I. 80             | 14VBR-2<br>&<br>14VBR-3 | BUREAU   |                   | 219   | 134   | 35 \$ |
| FED. ROAD DIST. NO. 7 |                         | ILLINOIS | FED. ALD PROJECT- |       |       |       |

Contract No. 66731

sheet NO. 30 35 sheets

## GENERAL NOTES

All dimensions shall remain the same as shown on contract plans, except dimensions A and B which are to be revised as shown to provide additional clearance. Additional concrete needed to revise dimension A and B= 0.0165 cu, yds./ft, of parapet, Place aluminum sheet in curb portion at and near piers. Full thickness saw cut at all joint locations in lieu of cork joint filler.



#3 (E) BAR

