## STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION

Contract No. 66731


When cantilever forming brackets are used, the work shall be done according to Article 503.06(b) of the Standard Specifications, except as modified below and in the details shown on this sheet.

as modified below and in the details shown on this sheet.


The finishing machine rails shall be placed on the top fiange of the exterior beams.

The beams or girders, supporting cantilever forming brackets, shall be tied together at 4 foot intervals.

For Standard construction, or Stage Construction the Hardwood bracing materials shall be placed as shown between webs of beams in each bay.



FORM BRACES FOR STAGE CONSTRUCTION



FORM BRACES FOR STANDARD CONSTRUCTION

CANTILEVER FORMING BRACKETS

FOR SUPERSTRUCTURES WITH

W27 BEAMS AND SMALLER

F.A.I. RTE. 80 - SEC. 14VBR-2 & 14VBR-3

BUREAU COUNTY

STATION 413+39.84

STRUCTURE NO. 006-0167 (E.B.)

STRUCTURE NO. 006-0168 (W.B.)

DESIGNED Nicholas R. Barnett

CHECKED Ray Ahanchi

DRAWN h.t. duong

CHECKED NRB/GRA

Sep. 30, 2008

EXAMINED Themas Amazaraki

PASSED Rala C. CHECKED SIRUCTURES

ENGINEER OF BRIDGES AND STRUCTURES